#### Whāingaroa / Raglan WWTP Discharge Consent Project February 2025 – Community Meeting







### Initial Technical Work Completed in the Gully

- Groundwater monitoring to date
- Soil samples and testing/saturation tests and initial permeability testing.
- Initial modeling:
  - hydraulic (how water flows through a system)
  - hydrogeology (how water moves underground)



## Soil Types in the Gully

- The gully has layers of volcanic ash deposits, made up of materials from silty clays to fine sands.
- In the middle of the gully, windblown sands have settled on the valley slopes, adding to the mix of sediments.
- Near the shoreline, these deposits are overlain by dunes made of fine **sand mixed with silt**.



### **Gully Permeability**

- The types of soils in the middle and upper parts of the gully don't let water soak in easily - low permeability.
- This was confirmed through tests in two handdug bores and site mapping, which showed wetland areas, seepage spots, and other signs of water staying on or near the surface for a long time.



# **Key Findings**

- The proposed **discharge flow rates are low compared to surface stormwater runoff** in the gully.
- The valley appears stable with **little erosion risk** based on site observations. Scour and erosion are not considered a high risk.
- Because the gully has low-permeability soils, flows won't soak into the deeper subsurface that much and will mostly stay at or near the surface, adding to surface runoff.
- Risk that any portion of the discharged water that does infiltrate could resurface in the lower section of the gully.







#### **Next Steps**

- There is a risk that a flow path could form across the beach.
- To better understand how flows might impact the sand dunes, further testing is being done in the dune area.
- This includes drilling with hand augers, testing soil permeability, measuring infiltration rates, and analysing soil samples further.



Sensitivity: General

#### **Raglan WWTP Membrane Bioreactor**

