







The Journey So Far

- Currently, Raglan's wastewater is treated at the WWTP on Wainui Road and discharged to the Whāingaroa harbour via an outfall pipeline.
- The Raglan community and mana whenua have had a long-standing history with wanting the town's wastewater discharge removed from the harbour.
- We have been on a journey with WDC and Watercare for 7+ years to find an alternative discharge solution.



The Journey So Far

- The existing discharge consent was due to expire in 2020.
- A short-term consent was lodged in 2019 to allow the continued lawful discharge of treated WW to the harbour, while a long-term solution was confirmed that provided for Raglan's growth.

 There has been a strong desire from mana whenua and the community for a land-based discharge solution.






Project Objectives

- Keep communities healthy.
- Protect the environment, particularly the water quality and ecology of the Whāingaroa Harbour.
- Recognise the significance of the Whāingaroa Harbour to mana whenua and support the kaitiaki management of customary fishing.
- Protect the community use of the area, along with the visitor experience.
- Work in partnership with the community and mana whenua.
- Retain flexability for future, sustainable, long-term solutions including potential resue of treated wastewater.
- Keep the overall costs of the wastewater solution to affordable levels.



Land Discharge Options Process





Challenges We Faced With Land Discharge

- Sub-surface/soil drip irrigation was the best form of land discharge method for the current plant.
- Suitable land size and soil type.




• Affordability.



Key Milestone - Plant Upgrades

 With strong community support the decision was made to upgrade the current plant to a Membrane BioReactor (MBR) system before a long-term discharge solution was confirmed.





Sensitivity: General

Raglan WWTP Membrane Bioreactor





Te Kauwhata Example




 The treated wastewater has the same clarity as drinking water and is close to a drinking water quality.



High-level Plant Process

Raglan WWTP MBR Upgrade – Overall Process Schematic






Re-looked at the Land Discharge Options

With the MBR producing such a high-quality discharge we re-look at possible land contact discharge options.

LOCATION MAP



OPTION 1 ARTISTS IMPRESSION





Preferred Option

- Can meet project objectives.
- Tainui o Tainui support.
- Avoids discharge to the Wainui Stream/sensitive environments.
- Provides land contact.
- Land is available and most affordable option.
- Additional benefit of gully restoration opportunities to enhance Wainui Reserve.



Technical Work Completed/Underway

- Archaeological assessment by Warren Gumbley no identified cultural or heritage sites within the project area.
- **Ecological** assessment site investigation found the gully to have low ecological values, but significant restoration opportunity.
- **Geotechnical and hydrogeological** assessments are underway. Two groundwater monitoring boreholes have been installed at the site and will monitor for three months.
- Of importance is understanding what volume of water can safely be discharged to the gully.



Technical Work Coming up

- Water Quality Assessment and Public Health Risk Assessment.
- Air Quality Assessment (of MBR and discharge location).
- Further **engineering design** off the discharge outlet.




Further Engagement

- 'Drop in' information sessions planned at Wainui Reserve carpark.
- Special interest group information.
- On-going engagement with:
 - Mana Whenua.
 - WDC Open Spaces Team.
 - Local plant nursery suppliers.
 - Bi-monthly community online meetings.
 - Community updates through online and local paper communication channels.
 - Waikato Regional Council who will be processing the consent application.



Sensitivity: General

Current Project Timeline





Current Construction Timeline

| End of 2025 – through 2026 | Start of 2027 to align with LTP funding. | End 2027. |
|------------------------------------------------|-------------------------------------------------------|--------------------------------------------------------|
| Start planting and restoration of gully. | Construction of the pipeline and outlet to the gully. | Wainui gully land contact discharge operational. |



Community Discussion



