

# **Enabling Housing Supply Variation 3 to the Proposed Waikato District Plan**

Amendments to Proposed Waikato District Plan – Decisions Version

Notified 19 September 2022

# Enabling Housing Supply

## Variation 3 to the Proposed Waikato District Plan

The provisions in the Intensification Planning Instrument (IPI) that are the basis for this Variation apply to the relevant residential zones in Huntly, Ngaaruawaahia, Pookeno and Tuakau.

Detailed below are the alterations to the proposed Waikato District Plan to incorporate changes to meet the requirements of section 77G of the Resource Management Act 1991 that requires Waikato District Council, as a Tier 1 territorial authority, to incorporate the Medium Density Residential Standards (MDRS), set out in schedule 3A, into all relevant residential zones. A territorial authority may amend the requirements to be less enabling if a qualifying matter applies.

Standard text is used for existing provisions contained in the proposed Waikato District Plan.

Green underline text is used for new provisions

~~Black strikethrough~~ text is used to show the deletion of existing provisions.

The provisions that incorporate the density standards in Part 2 of Schedule 3A of the Resource Management Act 1991 (the Act) and the objectives and policies in Clause 3 of Schedule 3A of the Act. In accordance with Section 80H of the Act these provisions are shown **shaded grey**.



Provisions that have legal effect are marked with a gavel (as shown in the margin of this paragraph).

Submissions can only be made on the changes to the district pan that from part of Variation 3 (these are marked in green underline, or ~~black strikethrough~~).

Table 1 below lists the provisions that are proposed to be added or amended by the variation.

Table 1: List of provisions subject to Variation 3

Part/Chapter	Proposed amendment
<b>Part 1: Introduction and General Provisions</b>	
Chapter 5: Definitions	Include definitions for: <ul style="list-style-type: none"> <li>• Landscaped area</li> <li>• MDRS</li> <li>• Qualifying matters</li> <li>• Servicing area</li> </ul>
Chapter 6: Abbreviations	Include abbreviation for: <ul style="list-style-type: none"> <li>• MDRS</li> </ul>
<b>Part 2: District-wide matters</b>	
Chapter 1: SD – Strategic directions	Add the following: <ul style="list-style-type: none"> <li>• Objective SD-O14</li> <li>• Policy SD-P2</li> </ul>
Chapter 6: EGEN – Electricity generation	Amend the following to include reference to the MRZ2: <ul style="list-style-type: none"> <li>• EGEN-R1</li> <li>• EGEN-R2</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 10: TEL – Telecommunications and	Amend the following to include reference to the MRZ2: <ul style="list-style-type: none"> <li>• TEL-R4</li> <li>• TEL-R5</li> </ul>

Intensification Planning Instrument: Notified 19 September 2022

Part/Chapter	Proposed amendment
radiocommunications	<ul style="list-style-type: none"> <li>• TEL-R9</li> <li>• TEL-R15</li> <li>• TEL-R17</li> <li>• TEL-R18</li> <li>• TEL-R19</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 - Medium density residential zone I throughout chapter.</p>
Chapter 11: TRPT – Transportation	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• TRPT-R2</li> <li>• TRPT-R3</li> <li>• TRPT-R4</li> <li>• Table 12</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 - Medium density residential zone I throughout chapter.</p>
Chapter 12: WWS – Water, wastewater and stormwater	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• WWS-R14</li> <li>• WWS-R22</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 - Medium density residential zone I throughout chapter.</p>
Chapter 14: HAZS – Hazardous substances	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• HAZS-R3</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 - Medium density residential zone I throughout chapter.</p>
Chapter 15: NH – Natural hazards and climate change	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• NH-R9</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 - Medium density residential zone I throughout chapter.</p>
Chapter 25: SUB – Subdivision	<p>Add the following:</p> <ul style="list-style-type: none"> <li>• Policy SUB-P3 (3)</li> <li>• Policy SUB-P23</li> <li>• Rule preamble in relation to section 106 of the RMA</li> <li>• Table with MRZ2 Rules: SUB-R152 to SUB-R163.</li> </ul> <p>Amend the following:</p> <ul style="list-style-type: none"> <li>• SUB-P3 (1)</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 – Medium density residential zone I throughout chapter.</p>
Chapter 29: EW – Earthworks	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• Objective EW-02</li> <li>• Policy EW-P1</li> <li>• Table with MRZ2 Rules: EW-R13 to EW-R16</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ1 - Medium density residential zone I throughout chapter.</p>
Chapter 30: LIGHT – Light	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• LIGHT-R1</li> <li>• LIGHT-R2</li> </ul>

Part/Chapter	Proposed amendment
	<ul style="list-style-type: none"> <li>• LIGHT-R3</li> <li>• LIGHT-R5</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 31: NOISE – Noise	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• Policy NOISE-PI(a)</li> <li>• NOISE-R3</li> <li>• Table with MRZ2 Rule: NOISE-R7</li> <li>• NOISE-R9</li> <li>• NOISE-R10</li> <li>• NOISE-R14</li> <li>• NOISE-R15</li> <li>• NOISE-R16</li> <li>• NOISE-R22</li> <li>• NOISE-R28</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 32: SIGN – Signs	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• Table with MRZ2 Rules: SIGN-R8 to SIGN-R10</li> <li>• SIGN-R20</li> <li>• SIGN-R23</li> <li>• SIGN-R26</li> <li>• SIGN-R32</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 33: TEMP – Temporary activities	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• Policy TEMP-PI</li> <li>• TEMP-RI</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
<b>Part 3: Area-specific matters</b>	
Chapter 2: GRZ – General residential zone	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• GRZ-PI2</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 3: MRZ I – Medium density residential zone I	<p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 3A: MRZ2 – Medium density residential zone 2	<p>Add the following:</p> <ul style="list-style-type: none"> <li>• New Chapter MRZ2 – Medium density residential zone 2</li> </ul>
Chapter 4: GRUZ – General rural zone	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• GRUZ-R34</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 8: LCZ – Local centre zone	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• LCZ-PI0</li> </ul>

Intensification Planning Instrument: Notified 19 September 2022

Part/Chapter	Proposed amendment
	<ul style="list-style-type: none"> <li>• LCZ-S1</li> <li>• LCZ-S5</li> <li>• LCZ-S6</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 9: COMZ – Commercial zone	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• COMZ-PI I</li> <li>• COMZ-S1</li> <li>• COMZ-S5</li> <li>• COMZ-S6</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 10: TCZ – Town centre zone	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• TCZ-PI8</li> <li>• TCZ-S1</li> <li>• TCZ-S4</li> <li>• TCZ-S8</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>
Chapter 11: GIZ – General industrial zone	<p>Amend the following to include reference to the MRZ2:</p> <ul style="list-style-type: none"> <li>• GIZ-S1</li> </ul> <p>Amend references from MRZ – Medium density residential zone to MRZ I - Medium density residential zone I throughout chapter.</p>

## Interpretation

### Definitions

*Explanatory note for the purpose of the IPI and to be removed upon completion of the process:*

Proposed additional definitions are shown in green underline. No modifications are proposed to any existing definitions within the proposed Waikato District Plan and are therefore not shown as part of the IPI.

<b>Term</b>	<b>Definition</b>
<u>Active transport</u>	<p><u>Has the same meaning as in the National Policy Statement on Urban Development 2020 (as set out in the box below).</u></p> <p><u>Means forms of transport that involve physical exercise, such as walking or cycling, and includes transport that may use a mobility aid such as a wheelchair.</u></p>
<u>Landscaped area</u>	<p><u>Means any part of the site that is grassed and/or planted in trees, shrubs, or ground cover and may include ancillary water, rocks, paved areas or amenity features.</u></p>
<u>MDRS</u>	<p><u>Has the same meaning as in section 2 of the Resource Management Act 1991 (as set out in the box below).</u></p> <p><u>Means the requirements, conditions, and permissions set out in Schedule 3A.</u></p>
<u>Qualifying matters</u>	<p><u>Has the same meaning as in section 2 of the Resource Management Act 1991 (as set out in the box below).</u></p> <p><u>Means a matter referred to in section 77I or 77O of the Resource Management Act 1991.</u></p>
<u>Servicing area</u>	<p><u>Means the use of land for services, storage or waste management to serve a dwelling or residential activity.</u></p>

## Interpretation

### Abbreviations

<b>Abbreviation</b>	<b>Full term</b>
CPTED	Crime prevention through environmental design
GFA	Gross floor area
<a href="#">MDRS</a>	<a href="#">Medium Density Residential Standard</a>
NES	National environmental standard
NESETA	Resource Management (National Environmental Standards for Electricity Transmission Activities) Regulations 2009
NESF	National Environmental Standards for Freshwater 2020
NESTF	Resource Management (National Environmental Standards for Telecommunication Facilities) Regulations 2016
NPS	National policy statement
NZCPS	New Zealand Coastal Policy Statement
NZECP	New Zealand Electrical Code of Practice for Electrical Safe Distances 34:2001 ISSN 0114-0663
RMA	Resource Management Act 1991

## SD – Strategic directions

*Explanatory note for the purpose of the IPI and to be removed upon completion of the process:*

Standard text is used for existing provisions contained in the proposed Waikato District Plan.

Green underline text is used for new provisions.

Provisions in this chapter incorporate the objectives and policies in Clause 6 of Schedule 3A of the Resource Management Act 1991 (the Act). In accordance with Section 80H of the Act these provisions are shown shaded grey.

### Introduction

This chapter:

- (a) Provides the overarching direction for the District Plan, including for developing the other chapters within the Plan, and its subsequent implementation and interpretation; and
- (b) Has primacy over the objectives and policies in the other chapters of the Plan, which must be consistent with the strategic objectives in this chapter.

The strategic objectives in this chapter are provided in no order of priority.

### Objectives

SD-O1 Socio-economic advancement.

The District has a thriving economy.

SD-O2 Tangata whenua.

Tangata whenua's relationships, interests, including commercial interests, and associations with their culture, traditions, ancestral lands, waterbodies, sites, areas and landscapes, and other taonga are recognised and provided for.

SD-O3 Growth targets.

The following growth targets are planned for:

	Minimum targets (number of dwellings)		
	2017-2026	2027-2046	Total
Waikato District	7,100	12,300	19,400

SD-O4 Housing variety.

A variety of housing types are available to meet the community's housing needs.

SD-O5 Integration of infrastructure and land use.

New development is integrated with the provision of infrastructure.

SD-O6 Hamilton's urban expansion area.

Land uses within Hamilton's Urban Expansion Area do not compromise its future urban development.



## Part 2: District-wide matters / Strategic direction / SD – Strategic directions

- SD-O7 Regionally significant infrastructure and industry.  
Recognise the importance of regionally significant infrastructure and regionally significant industry.
- SD-O8 Highly productive soils.  
High quality soils are protected from urban development, except in areas identified for future growth in the District Plan.
- SD-O9 Rural activities.  
The rural environment provides for a range of rural activities, including primary production and food supply.
- SD-O10 Reverse sensitivity.  
Existing activities are protected from reverse sensitivity effects.
- SD-O11 Historic heritage.  
Historic heritage contributes to the district's sense of place and identity.
- SD-O12 Natural environment.  
Outstanding natural features and landscapes, and significant indigenous terrestrial flora and fauna are protected.
- SD-O13 Climate change.  
Land use is planned to recognise, and avoid, remedy or mitigate the potential adverse effects of climate change induced weather variability and sea level rise.

### SD-O14 Well-functioning urban environment.

A well-functioning urban environment that enables all people and communities to provide for their social, economic, and cultural wellbeing, and for their health and safety, now and into the future.

## **Policy**

- SD-PI Activities within Hamilton's urban expansion area.  
Avoid subdivision, use and development within Hamilton's urban expansion area to ensure that future urban development is not compromised.

### SD-P2 Medium Density Residential Standards

Apply the MDRS across all relevant residential zones in the district plan except in circumstances where the qualifying matter is relevant (including matters of significance such as historic heritage and the relationship of Maaori and their culture and traditions with their ancestral lands, water, sites, waahi tapu, and other taonga).

## EGEN – Electricity generation

### Rules

EGEN-RI	Small-scale electricity generation	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Small-scale electricity generation and community-scale electricity generation that comply with each of the following standards, where applicable:</p> <p>(i) Is not located within an Identified Area;</p> <p>(ii) Is not located on unformed road;</p> <p>(iii) Maximum one wind turbine per site in the GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, RPZ - Rangitahi Peninsula zone, LLRZ – Large lot residential zone and SETZ – Settlement zone;</p> <p>(iv) Freestanding wind turbines must not exceed the building height limit of the zone in which they are located by more than 3m;</p> <p>(v) Freestanding wind turbines have a maximum blade diameter of 2.5m;</p> <p>(vi) Roof-mounted wind turbines must not exceed the building height limit of the zone in which they are located by more than 3m;</p> <p>(vii) Roof-mounted wind turbines have a maximum blade diameter of 2.5m;</p> <p>(viii) Any wind turbine on a site adjoining GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, RPZ - Rangitahi Peninsula zone, LLRZ – Large lot residential zone or SETZ – Settlement zone must meet</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, landscape, streetscape and amenity effects, including noise;</p> <p>(c) Shadow flicker effects;</p> <p>(d) The risk of hazards affecting public or individual safety, and risk of property damage;</p> <p>(e) Effects on the values, qualities and characteristics of any Identified Area; and</p> <p>(f) Ecology and biodiversity effects.</p>

	<p>the height in relation to boundary limits on the boundary with that adjoining zone;</p> <p>(ix) Solar panels on the roof of a building must not exceed 1.5m in height above the existing roof; or attached to a ground mounted frame;</p> <p>(x) Wind turbine noise must:</p> <p>(1) Not exceed the background sound level (L95) by more than 5dBA, or a level of 40dBA (L95), whichever is the greater, when measured at operational wind speeds, and for properties located adjacent to the facility when measured at:</p> <p>(a) Any existing building or structure for sensitive land uses; and</p> <p>(b) Any potential building site where a building or structure for sensitive land uses could be located as a permitted activity; and</p> <p>(2) Be measured and assessed in accordance with NZS6808: 2010 Acoustics – Wind Farm Noise; and</p> <p>(xi) All other structures not listed above must not be higher than the maximum building height limit of the zone in which they are located.</p>	
<b>EGEN-R2</b>	Community-scale electricity generation	
GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Small-scale electricity generation and community-scale electricity generation that comply with each of the following standards, where applicable:</p> <p>(i) Is not located within an Identified Area;</p> <p>(ii) Is not located on unformed road;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, landscape, streetscape and amenity effects, including noise;</p> <p>(c) Shadow flicker effects;</p>

	<ul style="list-style-type: none"> <li>(iii) Maximum one wind turbine per site in the GRZ – General residential zone, MRZ<u>1</u> – Medium density residential zone <u>1</u>, <u>MRZ2 – Medium density residential zone 2</u>, RPZ - Rangitahi Peninsula zone, LLRZ – Large lot residential zone and SETZ – Settlement zone;</li> <li>(iv) Freestanding wind turbines must not exceed the building height limit of the zone in which they are located by more than 3m;</li> <li>(v) Freestanding wind turbines have a maximum blade diameter of 2.5m;</li> <li>(vi) Roof-mounted wind turbines must not exceed the building height limit of the zone in which they are located by more than 3m;</li> <li>(vii) Roof-mounted wind turbines have a maximum blade diameter of 2.5m;</li> <li>(viii) Any wind turbine on a site adjoining GRZ – General residential zone, MRZ<u>1</u> – Medium density residential zone <u>1</u>, <u>MRZ2 – Medium density residential zone 2</u>, RPZ - Rangitahi Peninsula zone, LLRZ – Large lot residential zone or SETZ – Settlement zone must meet the height in relation to boundary limits on the boundary with that adjoining zone;</li> <li>(ix) Solar panels on the roof of a building must not exceed 1.5m in height above the existing roof; or attached to a ground mounted frame;</li> <li>(x) Wind turbine noise must:             <ul style="list-style-type: none"> <li>(1) Not exceed the background sound level (L95) by more than 5dBA, or a level of 40dBA (L95), whichever is the greater, when measured at operational wind speeds,</li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>(d) The risk of hazards affecting public or individual safety, and risk of property damage;</li> <li>(e) Effects on the values, qualities and characteristics of any Identified Area; and</li> <li>(f) Ecology and biodiversity effects.</li> </ul>
--	--	--

	<p>and for properties located adjacent to the facility when measured at:</p> <p>(a) Any existing building or structure for sensitive land uses; and</p> <p>(b) Any potential building site where a building or structure for sensitive land uses could be located as a permitted activity; and</p> <p>(2) Be measured and assessed in accordance with NZS6808: 2010 Acoustics – Wind Farm Noise; and</p> <p>(xi) All other structures not listed above must not be higher than the maximum building height limit of the zone in which they are located.</p>	
<p><b>EGEN-R3</b></p>	<p>Research and exploratory-scale investigations for renewable electricity generation activities</p>	
<p>All zones</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Research and exploratory-scale investigations for renewable electricity generation activities that comply with all of the following:</p> <p>(i) The noise limits that are applicable to the zone;</p> <p>(ii) The height of any equipment must not exceed the building height limit of the zone in which they are located by more than 3m, or within the GRUZ – General rural zone must not exceed 20m total height measured from the natural ground level immediately below the structure;</p> <p>(iii) The size and location of any equipment must not exceed height in relation to boundary relevant to the zone in which it is located;</p> <p>(iv) Setbacks relevant to the zone in which it is located;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, landscape, streetscape and amenity effects, including noise;</p> <p>(c) Shadow flicker effects;</p> <p>(d) The risk of hazards affecting public or individual safety, and risk of property damage;</p> <p>(e) Effects on the values, qualities and characteristics of any Identified Area; and</p> <p>(f) Ecology and biodiversity effects.</p>

	(v) Is not located within an identified area; and (vi) Is not located on a road, or unformed road.	
<b>EGEN-R4</b>	Temporary diesel-fuelled electricity generation activities	
All zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: DIS</b>
<b>EGEN-R5</b>	Electricity generation within the Huntly Power Station site in the HIZ – Heavy industrial zone	
HIZ – Heavy industrial zone	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Electricity generation within the Huntly Power Station site in the HIZ – Heavy industrial zone that complies with the HIZ – Heavy industrial zone rules.	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b> (a) The extent of effects associated with the HIZ – Heavy industrial zone rules that the activity does not comply with.
<b>EGEN-R6</b>	Large-scale wind farms located within the GRUZ – General rural zone, not within an Identified Area.  Wind turbine noise must be measured and assessed in accordance with NZS6808:2010 Acoustics – Wind Farm Noise	
GRUZ – General rural zone	<b>(1) Activity status: DIS</b>	
<b>EGEN-R7</b>	Large-scale wind farms located in a zone other than the GRUZ – General rural zone.  Wind turbine noise must be measured and assessed in accordance with NZS6808:2010 Acoustics – Wind Farm Noise	
All zones	<b>(1) Activity status: NC</b>	
<b>EGEN-R8</b>	Large-scale wind farm located within any Identified Area in the GRUZ – General rural zone.  Wind turbine noise must be measured and assessed in accordance with NZS6808:2010 Acoustics – Wind Farm Noise	
GRUZ – General rural zone	<b>(1) Activity status: NC</b>	

## TEL – Telecommunications and radiocommunications

### Rules

Advice note: +<sup>1</sup> Means activities not provided as a permitted activity under the Resource Management (National Environmental Standards for Telecommunication Facilities (“NESTF”)) Regulations 2016.

<b>TEL-R1</b>	Ancillary equipment	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Ancillary equipment that complies with the following:</p> <p>(i) It is not connected to an area, façade or item specifically listed in SCHED I – Historic heritage items.</p> <p>(ii) Not exceed 10m<sup>2</sup> in area above-ground; and</p> <p>(iii) Not exceed 2.5m in height measured from the natural ground level immediately below the structure.</p>	<p><b>(2) Activity status where compliance not achieved: CON</b></p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(b) The location of the proposed facility, equipment or structure;</p> <p>(c) The ability to provide screening or landscaping; and</p> <p>(d) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.</p>
<b>TEL-R2</b>	Below ground telecommunications and radiocommunications facilities, lines, cables and ducts	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>TEL-R3</b>	Cabinets+ <sup>1</sup>	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Cabinets that comply with the following standards:</p> <p>(i) Are not located within an Identified Area.</p> <p>(ii) Not exceed 10m<sup>2</sup> in area above-ground; and</p> <p>(iii) Not exceed 2.5m in height measured from the natural ground level immediately below the structure.</p>	<p><b>(2) Activity status where compliance not achieved: CON</b></p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(b) The location of the proposed facility, equipment or structure;</p> <p>(c) The ability to provide screening or landscaping; and</p> <p>(d) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.</p>
<b>TEL-R4</b>	Antennas and lines attached to retaining walls, tunnels, bridges and other structures located within the road+ <sup>1</sup>	

<p>All zones</p>	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <p>(a) Antennas that comply with all of the following standards:</p> <p>(i) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items;</p> <p>(ii) Panel antenna do not exceed 0.7m in width;</p> <p>(iii) Dish antenna do not exceed 0.6m in diameter within the GRZ – General residential zone, and MRZ1 – Medium density residential zone <u>1</u> and the MRZ2 – Medium density residential zone 2; and</p> <p>(iv) Within the GRZ – General residential zone, and MRZ1 – Medium density residential zone <u>1</u>, and the MRZ2 – Medium density residential zone 2, the maximum number of antennas per site is 4.</p> <p>(b) Rule TEL-R4(1)(a) does not apply a face-mounted panel antenna located within the fascia and below the roof line of an existing building, except where the area, façade or item is specifically listed in SCHED I – Historic heritage items.</p>	<p><b>Activity status where compliance not achieved: DIS</b></p>
<p><b>TEL-R5</b></p>	<p>Antennas<sup>+</sup> attached to a building and/or structure</p>	
<p>All zones</p>	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <p>(a) Antennas attached to a building and/or structure that comply with all of the following conditions standards:</p> <p>(i) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items;</p> <p>(ii) The building and/or structure is not located within:</p> <p>(1) GRZ – General residential zone;</p> <p>(2) MRZ1 – Medium density residential zone <u>1</u>;</p>	<p><b>(2) Activity status: CON</b>  <b>Where:</b></p> <p>(a) Antennas attached to a building that do not comply with the standards of Rule TEL-R4(1) and are located not within:</p> <p>(i) GRZ – General residential zone;</p> <p>(ii) MRZ1 – Medium density residential zone 1;</p> <p>(iii) LLRZ – Large lot residential zone; and</p> <p>(iv) SET – Settlement zone; and</p> <p>(v) MRZ2 – Medium density residential zone 2</p>



	<p>(3) LLRZ – Large lot residential zone; <del>and</del></p> <p>(4) SET – Settlement zone; <del>and</del></p> <p>(5) <u>MRZ2 – Medium density residential zone 2.</u></p> <p>(iii) The face of the antenna does not exceed 1.5m<sup>2</sup> or 1.2m in diameter for dish antennas, or 1.6m in length for Yagi antenna on an existing pole.</p> <p>(b) Rule TEL-R5(1)(a) does not apply to private television antennas and satellite dishes +1</p>	<p><b>Council’s control is reserved over the following matters:</b></p> <p>(b) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(c) The location of the proposed facility, equipment or structure;</p> <p>(d) The ability to provide screening or landscaping; and</p> <p>(e) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.</p> <p><b>(3) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) Antennas attached to a building and/or structure that comply with all of the following standards:</p> <p>(i) Are located within:</p> <p>(1) GRZ – General residential zone;</p> <p>(2) <u>MRZ1</u> – Medium density residential zone <u>1</u>;</p> <p>(3) RPZ – Rangitahi Peninsula zone;</p> <p>(4) LLRZ – Large lot residential zone;</p> <p>(5) SETZ – Settlement zone; <del>or</del></p> <p>(6) Road and unformed road; <del>or</del></p> <p>(7) <u>MRZ2 – Medium density residential zone 2</u></p> <p>(ii) The face of the antenna does not exceed 1.5m<sup>2</sup> or 1.2m in diameter for dish antennas.</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(b) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(c) The bulk, form, scale, location of the structure;</p> <p>(d) Visual, landscape, streetscape and amenity effects;</p>
--	---	--

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

		<p>(e) Where located within a road, the operation and function of road network activities; and</p> <p>(f) Effects on the values, qualities and characteristics of the site, heritage item or area.</p> <p><b>(4) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) Antennas attached to a building and/or structure do not comply with TEL-R5(3)(a)</p>
<b>TEL-R6</b>	Antennas inside new or existing buildings	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>TEL-R7</b>	Other antennas	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Antennas that comply with all of the following standards are excluded from any height standards in Rules TEL-R4(1), TEL-R5(1), and TEL-R9(1):</p> <p>(i) GPS Antennas that do not exceed the following dimensions:</p> <p>(1) 300mm high: and</p> <p>(2) 130mm in diameter.</p> <p>(ii) Omni-directional 'whip' or di-pole type antennas that do not exceed the following dimensions:</p> <p>(1) 1.6m high;</p> <p>(2) 1.5m horizontal length whip or rod; or</p> <p>(3) Cross section element no more than 60mm in diameter.</p> <p>(iii) Are not located within an Identified Area; and</p> <p>(iv) Do not connect to an area, façade or item specifically listed in SCHED 1 – Historic heritage items.</p>	<p><b>(2) Activity status: CON</b></p> <p><b>Where:</b></p> <p>(a) Antennas located within an Identified Area that comply with the following:</p> <p>(i) GPS antennas that do not exceed the following dimensions:</p> <p>(1) 300mm high: and</p> <p>(2) 130mm in diameter.</p> <p>(ii) Omni-directional 'whip' or di-pole type antennas that do not exceed the following dimensions:</p> <p>(1) 1.6m high;</p> <p>(2) 1.5m horizontal length whip or rod; or</p> <p>(3) Cross section element no more than 60mm in diameter.</p> <p><b>Council's control is reserved over the following matters:</b></p> <p>(b) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(c) The location of the proposed facility, equipment or structure;</p> <p>(d) The ability to provide screening or landscaping; and</p> <p>(e) Effects on the values, qualities and characteristics of the site</p>

		and/or items in SCHED I – Historic heritage items.				
<b>TEL-R8</b>	Small cell units exceeding the permitted volumetric dimension of 0.1 l m <sup>3</sup> regulated in the NESTF					
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Small cell units exceeding the permitted volumetric dimension of 0.1 l m<sup>3</sup> regulated in the NESTF that comply with all of the following standards:</p> <p>(i) Do not exceed a maximum volume of 0.25m<sup>3</sup>;</p> <p>(ii) Are not located within an Identified Area; and</p> <p>(iii) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items.</p>	<p><b>(2) Activity status: CON</b></p> <p><b>Where:</b></p> <p>(a) Small cell units are located in an Identified Area exceeding the maximum volumetric dimension volume of 0.1 l m<sup>3</sup> regulated in the NESTF, up to a maximum volume of 0.25m<sup>3</sup>.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(b) The location of the proposed facility, equipment or structure;</p> <p>(c) The ability to provide screening or landscaping; and</p> <p>(d) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.</p>				
<b>TEL-R9</b>	Poles, antennas and headframes+ <sup>1</sup>					
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Any poles and attached antenna that comply with the following standards:</p> <p>(i) Are not located within an Identified Area;</p> <p>(ii) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items;</p> <p>(iii) Comply with the height in relation to boundary limits for the zone in which it is located; and</p> <p>(iv) Not exceed the height limits set out in the following table:</p> <table border="1" data-bbox="411 1832 885 2031"> <thead> <tr> <th>Zone</th> <th>Permitted height measured from the natural ground level immediately below the structure</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> </tr> </tbody> </table>	Zone	Permitted height measured from the natural ground level immediately below the structure			<p><b>(2) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) Poles, antennas and headframes located in an Identified Area that comply with Rule TEL-R9(1).</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(b) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(c) The bulk, form, scale, location of the structure;</p> <p>(d) Visual, landscape, streetscape and amenity effects;</p> <p>(e) Where located within a road, the operation and function of road network activities; and</p> <p>(f) Effects on the values, qualities and characteristics of the site, heritage item or area.</p> <p><b>(3) Activity status: DIS</b></p>
Zone	Permitted height measured from the natural ground level immediately below the structure					

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

GRUZ – General rural zone; RLZ - Rural lifestyle zone	25m (and 30m for co-location of at least two operators)	<p><b>Where:</b></p> <p>(a) Poles, antennas and headframes located in an Identified Area that do not comply with the regulations 26-35 of the NESTF or Rule TEL-R9(1).</p>
GIZ – General industrial zone; HIZ – Heavy industrial zone and MSRZ – Motor sport and recreation zone	25m (and 30m for co-location of at least two operators)	
COMZ – Commercial zone; TCZ – Town centre zone; LCZ – Local centre zone; BTZ – Business Tamahere zone; TKAZ – Te Kowhai airpark zone	20m	
OSZ – Open space zone	20m	
GRZ – General residential zone; MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, RPZ – Rangitahi Peninsula zone; LLRZ – Large lot residential zone; SETZ – Settlement zone and Special purpose zones not otherwise listed.	15m	
Road or unformed road	That of the adjoining zone	
<p>(b) Headframes that comply with the following conditions standards:</p> <p>(i) Comply with the height in relation to boundary limits for the zone in which it is located;</p> <p>(ii) Within the GRZ – General residential zone, and MRZ1 – Medium density residential zone 1 and the MRZ2 – Medium density residential zone 2 do not exceed 1.0m diameter; or</p> <p>(iii) Within all other zones and unformed roads do not exceed 6.0m diameter; and</p>		

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

	<p>(iv) Within the road do not exceed 0.7m diameter.</p> <p>(c) Rule TELR9(1)(a) does not apply to lightning rods and GPS antennas, omni directional whip antenna, ancillary telecommunication devices and earth peaks.</p>	
<b>TEL-R10</b>	Externally-mounted telecommunication satellite dishes and ancillary components	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Externally-mounted telecommunication satellite dishes and ancillary components that comply with the following standards:</p> <p>(i) Do not exceed 1.0m in diameter, or 1.8m in diameter in GIZ – General industrial zone, HIZ – Heavy industrial zone, RLZ – Rural lifestyle zone and GRUZ – General rural zone;</p> <p>(ii) Are attached to existing buildings; and/or including a pole or structure other than a building when located in the RLZ – Rural lifestyle zone and GRUZ – General rural zone;</p> <p>(iii) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items; and</p> <p>(iv) Are not located within an Identified Area</p>	<p><b>(2) Activity status: CON</b></p> <p><b>Where:</b></p> <p>(a) Externally-mounted telecommunication satellite dishes and ancillary components that:</p> <p>(i) Do not exceed 1.0m in diameter;</p> <p>(ii) Are attached to existing buildings; and</p> <p>(iii) Are not located within an Identified Area.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(b) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(c) The location of the proposed facility, equipment or structure;</p> <p>(d) The ability to provide screening or landscaping; and</p> <p>(e) Effects on the values, qualities and characteristics of the site.</p> <p><b>(3) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) Externally-mounted telecommunication satellite dishes and ancillary components that</p> <p>(i) Are located within an Identified Area.</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(b) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(c) The bulk, form, scale, location of the structure;</p>

		<p>(d) Visual, landscape, streetscape and amenity effects;</p> <p>(e) Where located within a road, the operation and function of road network activities and</p> <p>(f) Effects on the values, qualities and characteristics of Identified Area.</p>
<b>TEL-R11</b>	Telecommunication kiosk	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Telecommunication kiosks that comply with all of the following standards:</p> <p>(i) Are not located within road or unformed road located adjacent to an Identified Area;</p> <p>(ii) Do not connect to an area, façade or item specifically listed in SCHED1 – Historic heritage items; and</p> <p>(iii) Are not located within an Identified Area; and</p> <p>(iv) Not exceed 10m<sup>2</sup> in area above-ground; and</p> <p>(v) Not exceed 2.5m in height measured from the natural ground level immediately below the structure.</p>	<p><b>(2) Activity status: CON</b></p> <p><b>Where:</b></p> <p>(a) Telecommunication kiosks, located within road or unformed road adjacent to an Identified Area, that comply with the standards for a new infrastructure activity and associated structures under Rule AINF-R1.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(b) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(c) The location of the proposed facility, equipment or structure;</p> <p>(d) The ability to provide screening or landscaping; and</p> <p>(e) Effects on the values, qualities and characteristics of the site.</p> <p><b>(3) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) Telecommunication kiosks that do not comply with one or more standards of Rules TEL-R11(1) or TEL-R11(2).</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(b) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(c) The bulk, form, scale, location of the structure;</p> <p>(d) Visual, landscape, streetscape and amenity effects;</p>

		<p>(e) Where located within a road, the operation and function of road network activities; and</p> <p>(f) Effects on the values, qualities and characteristics of the site, heritage item or area.</p>
<b>TEL-R12</b>	Self-contained power units	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Self-contained power units that comply with all of the following conditions standards:</p> <p>(i) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items;</p> <p>(ii) Are not located within an Identified Area.</p> <p>(iii) Not exceed 10m<sup>2</sup> in area above-ground; and</p> <p>(iv) Not exceed 2.5m in height measured from the natural ground level immediately below the structure.</p>	<p><b>(2) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) Self-contained power units that do not comply with the standards for a new infrastructure activity and associated structures under Rule under Rule AINF-R1.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(b) The bulk, form, scale, location of the structure;</p> <p>(c) Visual, landscape, streetscape and amenity effects;</p> <p>(d) Where located within a road, the operation and function of road network activities; and</p> <p>(e) Effects on the values, qualities and characteristics of the site, heritage item or area.</p> <p><b>(3) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) Self-contained power units are located within an Identified Area</p>
<b>TEL-R13</b>	Aerial telecommunication lines and associated support structures, including those not complying with regulations 41-42 of the NESTF	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Aerial telecommunication lines and associated support structures, including those not complying with regulations 41-42 of the NESTF, that comply with all of the following conditions standards:</p> <p>(i) Do not exceed 20m in height measured from the natural</p>	<p><b>(2) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) Aerial telecommunication lines and associated support structures, including those not complying with regulations 41-42 of the NESTF, that:</p> <p>(i) Do not comply with one or more standards of Rule TEL-R13(1); and</p> <p>(ii) Are not located within an Identified Area.</p>

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

	<p>ground level immediately below the structure; and</p> <p>(ii) Are located within the GRUZ – General rural zone; or</p> <p>(iii) Are located within road or unformed road located adjacent to the GRUZ – General Rural Zone.</p>	<p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(b) The functional and operational needs of, and benefits derived from, the infrastructure;</p> <p>(c) The bulk, form, scale, location of the structure;</p> <p>(d) Visual, landscape, streetscape and amenity effects;</p> <p>(e) Where located within a road, the operation and function of road network activities; and</p> <p>(f) Effects on the values, qualities and characteristics of the site, heritage item or area.</p>
<b>TEL-R14</b>	Lightning rods	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Lightning rods that comply with all of the following conditions standards:</p> <p>(i) Do not exceed 1.8m in height;</p> <p>(ii) Do not connect to an area, façade or item specifically listed in SCHED I – Historic heritage items.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>TEL-R15</b>	<p>Cabinets not meeting the NESTF regulations 19, 20, and 21 that are not located within:</p> <p>(a) GRZ – General residential zone;</p> <p>(b) MRZ1 – Medium density residential zone 1;</p> <p>(a) RPZ – Rangitahi Peninsula zone;</p> <p>(b) LLRZ – Large lot residential zone;</p> <p>(c) SETZ – Settlement zone; or</p> <p>(d) Road and unformed road; or</p> <p>(e) MRZ2 – Medium density residential zone 2</p>	
All zones	<p><b>(1) Activity status: CON</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(b) The location of the proposed facility, equipment or structure;</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>



Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

	<p>(c) The ability to provide screening or landscaping; and</p> <p>(d) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.</p>	
<b>TEL-R16</b>	Antennas attached to an existing pole in the road reserve that do not comply with Regulations 26 and 27 of the NESTF and antennas attached to an existing pole in unformed road	
All zones	<p><b>(1) Activity status: CON</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(b) The location of the proposed facility, equipment or structure;</p> <p>(c) The ability to provide screening or landscaping; and</p> <p>(d) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>TEL-R17</b>	Dish antennas not complying with regulations 26-35 of the NESTF that are not located within:	
	<p>(f) GRZ – General residential zone;</p> <p>(g) MRZ1 – Medium density residential zone 1;</p> <p>(h) RPZ – Rangitahi Peninsula zone;</p> <p>(i) LLRZ – Large lot residential zone;</p> <p>(j) SETZ – Settlement zone; <del>or</del></p> <p>(k) Road and unformed road, <b>or</b></p> <p>(l) MRZ2 – Medium density residential zone 2</p>	
All zones	<p><b>(1) Activity status: CON</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) The size, colour and design of the proposed facility, equipment or structure;</p> <p>(b) The location of the proposed facility, equipment or structure;</p> <p>(c) The ability to provide screening or landscaping; and</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

	(d) Effects on the values, qualities and characteristics of the site and/or items in SCHED I – Historic heritage items.	
<b>TEL-R18</b>	Cabinets not meeting the NESTF regulations 19, 20, and 21 that are located within: (m) GRZ – General residential zone; (n) MRZ <u>1</u> – Medium density residential zone <u>1</u> ; (o) RPZ – Rangitahi Peninsula zone; (p) LLRZ – Large lot residential zone; (q) SETZ – Settlement zone; <del>or</del> (r) Road and unformed road; <u>or</u> (s) <u>MRZ2 – Medium density residential zone 2</u>	
All zones	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b> (a) The functional and operational needs of, and benefits derived from, the infrastructure; (b) The bulk, form, scale, location of the structure; (c) Visual, landscape, streetscape and amenity effects; (d) Where located within a road, the operation and function of road network activities; and (e) Effects on the values, qualities and characteristics of the site, heritage item or area.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TEL-R19</b>	Dish antennas not complying with regulations 26-35 of the NESTF that are located within: (a) GRZ – General residential zone; (b) MRZ <u>1</u> – Medium density residential zone <u>1</u> ; (c) RPZ – Rangitahi Peninsula zone; (d) LLRZ – Large lot residential zone; (e) SETZ – Settlement zone; <del>or</del> (f) Road and unformed road; <u>or</u> (g) <u>MRZ2 – Medium density residential zone 2</u>	
All zones	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b>	<b>(2) Activity status: n/a</b>

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

	<ul style="list-style-type: none"> <li>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</li> <li>(b) The bulk, form, scale, location of the structure;</li> <li>(c) Visual, landscape, streetscape and amenity effects;</li> <li>(d) Where located within a road, the operation and function of road network activities; and</li> <li>(e) Effects on the values, qualities and characteristics of the site, heritage item or area.</li> </ul>	
<b>TEL-R20</b>	Poles, antennas and headframes not complying with regulations 26-35 of the NESTF	
All zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</li> <li>(b) The bulk, form, scale, location of the structure;</li> <li>(c) Visual, landscape, streetscape and amenity effects;</li> <li>(d) Where located within a road, the operation and function of road network activities; and</li> <li>(e) Effects on the values, qualities and characteristics of the site, heritage item or area.</li> </ul>	<b>(2) Activity status: n/a</b>
<b>TEL-R21</b>	Poles, antennas and headframes not complying with regulations 26-35 of the NESTF	
All zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The functional and operational needs of, and benefits derived from, the infrastructure;</li> <li>(b) The bulk, form, scale, location of the structure;</li> <li>(c) Visual, landscape, streetscape and amenity effects;</li> </ul>	<b>(2) Activity status: n/a</b>

Part 2: District-wide matters / Energy, infrastructure and transport / TEL – Telecommunications and radiocommunications

	(d) Where located within a road, the operation and function of road network activities; and (e) Effects on the values, qualities and characteristics of the site, heritage item or area.	
<b>TEL-R22</b>	Cabinets not meeting the NESTF regulations 19, 20, and 21 that are located within an Identified Area	
All zones	<b>(I) Activity status: DIS</b>	
<b>TEL-R23</b>	Antennas attached to a building and/or structure located within an Identified Area	
All zones	<b>(I) Activity status: DIS</b>	
<b>TEL-R24</b>	Dish antennas not complying with regulations 26-35 of the NESTF that are located within an Identified Area.	
All zones	<b>(I) Activity status: DIS</b>	
<b>TEL-R25</b>	Poles, antennas and headframes located within an Identified Area not complying with regulations 26-35 of the NESTF	
All zones	<b>(I) Activity status: DIS</b>	
<b>TEL-R26</b>	Aerial telecommunication lines and associated support structures located within an Identified Area	
All zones	<b>(I) Activity status: DIS</b>	

## TRPT – Transportation

### Rules

TRPT-RI	Vehicle access for all activities	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) All activities must comply with the following vehicle access standards:</p> <p>(i) The site has legal physical access to a formed road that is maintained by a road controlling authority;</p> <p>(ii) The site has a vehicle access that is constructed to comply with the relevant requirements of Table 1 – Separation distances, Figure 6 – Separation distances, Table 2 – Minimum sight distances and Figure 8 – Minimum sight distances, Tables 12 and 13 except:</p> <p>(1) Rule TRPT-RI(1)(a)(ii) does not apply where the separation distance requirements of Table 1 – Separation distances and Figure 6 – Separation distances cannot be achieved on a site’s road frontage due to existing vehicle accesses on adjacent sites;</p> <p>(iii) No new vehicle access shall be created from Newell Road (south of Birchwood Lane);</p> <p>(iv) No access, access leg or right-of-way shall run parallel to any road within 30m of the road, except:</p> <p>(1) Rule TRPT-RI(1)(a)(iv) does not apply to farm races, or unsealed internal rural accesses in sites within the Rangitahi Peninsula Structure Plan Area and Oporu Road;</p> <p>(v) On a site with legal access to two roads, the activity only</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Traffic generation by the activities to be served by the access;</p> <p>(b) Location, design, construction and materials of the vehicle access;</p> <p>(c) Safety for all users of the access and/or intersecting road including but not limited to vehicle occupants or riders and pedestrians;</p> <p>(d) Road network safety and efficiency;</p> <p>(e) Mitigation to address safety and/or efficiency, including access clearance requirements for firefighting purposes;</p> <p>(f) The foreseeable needs for access by emergency services and their vehicles;</p> <p>(g) The extent to which the safety and efficiency of rail and road operations will be adversely affected, including:</p> <p>(h) The outcome of any consultation with KiwiRail; NZTA; Waikato District Council, as the rail or road controlling authority; and</p> <p>(i) Any characteristics of the proposed use that will make compliance unnecessary; and</p> <p>(i) Management of effects on the values of the Identified Area.</p>

	<p>accesses the road with the lower classification in the road hierarchy in Table 4 – Functions of roads within the Road Hierarchy and Table 5 – Road Hierarchy list (where the roads have the same classification, access is only to the road with the lower average daily traffic movements) except in the KLZ – Kimihia Lakes zone where this rule does not apply;</p> <p>(vi) New vehicle accesses/entrances are not to be constructed to any site from the following roads:</p> <ol style="list-style-type: none"> <li>(1) Main Street, Huntly;</li> <li>(2) Jesmond Street, Ngaruawahia;</li> <li>(3) Bow Street, Raglan (James Street to Cliff Street);</li> <li>(4) George Street, Tuakau (Gibson Road to Liverpool Street);</li> <li>(5) Great South Road, Pokeno (Selby Street to Market Street); and</li> <li>(6) Main Street, Te Kauwhata (Saleyard Road to Baird Avenue); and</li> </ol> <p>(vii) No new vehicle access shall be created within 30 metres of a railway level crossing;</p> <p>(viii) All existing and new accesses and roads that cross an operational rail network via a level crossing must be maintained in accordance with the sight line triangles provided in Table 14 – Required restart sight distances for Figure 18; and</p> <p>(ix) New vehicle access shall not be located within an Identified Area, with the exception of a Significant Natural Area which is addressed in the ECO –</p>	
--	---	--

	<p>Ecosystems and indigenous biodiversity chapter.</p> <p>Advice note:</p> <p>Any new vehicle access (or additional land use utilising an existing vehicle entrance) on a highway will require the approval of the NZTA, as the road controlling authority, and on a limited access road will require the approval of the road controlling authority.</p>	
<b>TRPT-R2</b>	On-site parking and loading	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) All activities must comply with the following on-site parking and loading standards:</p> <p>(i) The loading space requirements, manoeuvring and parking space dimensions in Table 6 – Required loading bays, and Table 9 – Car manoeuvring and parking space dimensions, noting:</p> <p>(1) When calculating the requirements for loading on the basis of the prescribed floor area, the area for parking, loading and manoeuvring shall be excluded;</p> <p>(2) If the calculation results in a fraction, then that figure shall be rounded to the nearest whole number;</p> <p>(3) 90 percentile car dimensions in Figure 9 – 90th Percentile car tracking curve minimum radius apply;</p> <p>(4) The requirements of Table 6 – Required loading bays do not apply to residential and rural activities;</p> <p>(5) Accessible parking spaces must comply with the New Zealand Building Code DI/AS1 New Zealand Standard for</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The area, type, location and marking of parking spaces;</p> <p>(b) The area, design, gradient, stormwater management, construction and materials of parking and loading spaces,</p> <p>(c) Accessibility of parking areas from on-site activities;</p> <p>(d) Safety for all users of the access and/or intersecting road including but not limited to vehicle occupants, vehicle riders and pedestrians;</p> <p>(e) Mitigation to address amenity and connectivity.</p> <p>(f) The foreseeable needs for access by emergency services and their vehicles; and</p> <p>(g) Management of effects on the values of the Identified Area.</p>

	<p>Design for Access and Mobility – Buildings and Associated Facilities (NZS: 4121-2001) and Table 7 – Accessible parking spaces; and</p> <p>(ii) On-site bicycle space requirements in Table 8 – Required bicycle spaces, except:</p> <p>(I) The requirements of Table 8 – Required bicycle spaces do not apply to residential and rural activities;</p> <p>(iii) Where parking is provided any on-site car parking spaces for non-residential activities within the GRZ – General residential zone, and MRZ1 – Medium density residential zone 1, and <a href="#">the MRZ2 – Medium density residential zone 2</a>, must be set back at least 3m from the road boundary of the site and screened by planting or fencing from being viewed from the road;</p> <p>(iv) On-site car parking spaces (where provided) and loading bays comply with the requirements of Table 9 – Car manoeuvring and parking space dimensions and Figure 9 – 90th Percentile car tracking curve minimum radius and be located on the same site as the activity;</p> <p>(v) On-site car parking spaces and loading bays are to be sealed if five or more parking spaces are provided;</p> <p>(vi) On-site car parking spaces and loading bays are to be permanently marked if five or more parking spaces are provided;</p> <p>(vii) On-site car parking spaces and loading bays are not to be located on any shared access or residential living court;</p>	
--	--	--



	<p>(viii) Vehicles occupying any on-site car parking or loading spaces must have ready access to the road (or relevant access or right of way) at all times, without needing to move any other vehicle occupying other on-site car parking or loading spaces;</p> <p>(ix) Loading bays are not required on sites with sole frontages to the following:</p> <ol style="list-style-type: none"> <li>(1) Main Street, Huntly;</li> <li>(2) Jesmond Street, Ngaruawahia;</li> <li>(3) Bow Street, Raglan (James Street to Cliff Street);</li> <li>(4) George Street, Tuakau (Gibson Road to Liverpool Street);</li> <li>(5) Great South Road, Pokeno (Selby Street to Market Street); or</li> <li>(6) Main Street, Te Kauwhata (Saleyard Road to Baird Avenue); and</li> </ol> <p>(x) New on-site parking and loading bays shall not be located within an Identified Area, with the exception of a Significant Natural Area which is addressed in the ECO – Ecosystems and indigenous biodiversity chapter.</p>	
<b>TRPT-R3</b>	On-site manoeuvring and queuing	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ol style="list-style-type: none"> <li>(a) All activities must comply with the following on-site manoeuvring and queuing standards: <ol style="list-style-type: none"> <li>(i) On-site manoeuvring space shall be provided to ensure that no vehicle is required to reverse onto from or to a road except; <ol style="list-style-type: none"> <li>(1) Rule TRPT-R3(1)(a)(i) does not apply to Local Roads within the GRZ –</li> </ol> </li> </ol> </li> </ol>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ol style="list-style-type: none"> <li>(a) Location, area, design, construction and materials of the manoeuvring and queuing space;</li> <li>(b) Type and frequency of use;</li> <li>(c) The design of features intended to ensure safety for all users of the access site, and/or intersecting road including but</li> </ol>

	<p>General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone and SETZ – Settlement zone with a posted speed limit of less than 60 km/h;</p> <p>(ii) A 90th percentile car, as defined in Figure 9 – 90th Percentile car tracking curve minimum radius, can enter and exit all parking spaces without making more than one reverse movement, excluding spaces required for a dwelling;</p> <p>(iii) On-site manoeuvring space for any heavy vehicle shall comply with the tracking curve (relevant for the type of activities to be carried out on the site and the largest combination standard configuration heavy vehicle permitted on the road(s) to which the site has frontage trucks to be used)</p> <p>(iv) On-site manoeuvring space shall be formed;</p> <p>(v) On-site queuing space shall be provided in accordance with Table 10 – Queuing space for vehicles entering and exiting any on-site car parking, loading or manoeuvring space, where:</p> <p>(1) Length is measured from the road boundary where vehicles first enter the site; and</p> <p>(2) On-site queuing above must not encroach into the required on-site manoeuvring area;</p> <p>(vi) On-site manoeuvring and queuing spaces are not required on sites with vehicle accesses/entrances to the following:</p> <p>(1) Main Street, Huntly;</p>	<p>not limited to vehicle occupants, vehicle riders and pedestrians;</p> <p>(d) Road network safety and efficiency; and</p> <p>(e) Management of effects on the values of the Identified Area.</p>
--	--	--

	<p>(2) Jesmond Street, Ngaruawahia;</p> <p>(3) Bow Street, Raglan (James Street to Cliff Street);</p> <p>(4) George Street, Tuakau (Gibson Road to Liverpool Street);</p> <p>(5) Great South Road, Pokeno (Selby Street to Market Street);</p> <p>(6) Main Street, Te Kauwhata (Saleyard Road to Baird Avenue); and</p> <p>(vii) New on-site manoeuvring shall not be located within an Identified Area, with the exception of a Significant Natural Area which is addressed in the ECO – Ecosystems and indigenous biodiversity chapter.</p>	
<p><b>TRPT-R4</b></p>	<p>Traffic generation</p>	
<p>All zones</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Where any site gains access from an arterial or regional arterial (including state highway) road, there is a maximum of 50 Equivalent Car Movements (ECM) per day.</p> <p>Note: ECM – 1 car movement is equivalent to 1 car movement / 1 truck movement is equivalent to 3 car movements / 1 truck and trailer movement is equivalent to 5 car movements.</p> <p>Any other site must comply with the following traffic generation conditions standards:</p> <p>(i) Within the GRZ – General residential zone, MRZ<sub>1</sub> – Medium density residential zone <u>1</u>, <u>MRZ2 – Medium density residential zone 2</u>, or RLZ – Rural lifestyle zone there is a maximum of 100 vehicle movements per site per day, and no more than 15% of these vehicle</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The trip characteristics of associated with the proposed activity;</p> <p>(b) The design of features intended to ensure safety for all users of the access site, and/or intersecting road including but not limited to vehicle occupants, vehicle riders and pedestrians;</p> <p>(c) Land transport network safety and efficiency, particularly at peak traffic times (of both the activity and road network); and</p> <p>(d) Mitigation to address adverse effects, such as:</p> <p>(i) Travel planning;</p> <p>(ii) Providing alternatives to private vehicle trips; including accessibility to public transport;</p> <p>(iii) Staging development; and</p> <p>(iv) Contributing to improvements to the road network.</p>

	<p>movements are heavy vehicle movements; or</p> <p>(ii) Within the RPZ – Rangitahi Peninsula zone there is a maximum of 200 vehicle movements per site per day, and no more than 5% of these vehicle movements are heavy vehicle movements; or</p> <p>(iii) Within the BTZ – Business Tamahere zone, COMZ – Commercial zone, TCZ – Town centre zone or LCZ – Local centre zone there is a maximum of 300 vehicle movements per site per day, and no more than 15% of these vehicle movements are heavy vehicle movements; or</p> <p>(iv) Within the GRUZ – General rural zone:</p> <p>(1) There is maximum 200 vehicle movements per site per day and no more than 15% of these vehicle movements are heavy vehicle movements;</p> <p>(2) For activities directly associated with horticulture harvesting, a maximum of 300 vehicle movements per site per day for up to a month, once in a 12-month period and no more than 33% of these vehicle movements are heavy vehicle movements; or</p> <p>(3) Within the Agricultural Research Centres identified on the planning maps as a specific controls there is maximum 3000 vehicle movements per site per day; or</p> <p>(v) Within the GIZ – General industrial zone and HIZ – Heavy industrial zone (excluding the Huntly Power Station and Huntly Quarry site):</p>	
--	---	--

	<p>(1) Maximum 250 vehicle movements per site per day and no more than 15% of these vehicle movements are heavy vehicle movements; or</p> <p>(vi) From the Huntly Power Station site as shown as the HIZ – Heavy industrial zone on the planning maps:</p> <p>(1) All vehicle movements generated from all activities on the site combined (including those movements which were lawfully established prior to 5 December 2012), there is a maximum 750 vehicle movements per site per day; and</p> <p>(2) Maximum 300 of these vehicle movements are heavy vehicle movements; or</p> <p>(vii) From the Huntly Quarry site:</p> <p>(1) All vehicle movements generated from all activities on the site combined (excluding those movements which were lawfully established prior to 5 December 2012), there is maximum 350 vehicle movements per site per day; and</p> <p>(2) No more than 150 of these vehicle movements are heavy vehicle movements, increasing to 200 once the Huntly Bypass section of the Waikato Expressway is open for public use. Or</p> <p>(viii) Within PREC27 and PREC28 of the TKAZ – Te Kowhai airpark zone there is a maximum 250 vehicle movements per site per day and no more than 15% of these vehicle movements are heavy vehicle movements; or</p>	
--	--	--

	<p>(ix) Within PREC29 and PREC30 of the TKAZ – Te Kowhai airpark zone there is a maximum of 30 vehicle movements per site per day and no more than 4 of these vehicle movements are heavy vehicle movements except:</p> <p>(x) Movement restrictions do not apply if the activity is an event or promotion (including temporary events) in PREC29 or a community facility in PREC29; or</p> <p>(xi) From the Horotiu Industrial Park does not exceed 15.4 trips/ha gross land area/peak hour;</p> <p>(xii) Within the KLZ – Kimihia Lakes zone there is a maximum of 850 vehicle movements per hour and no more than 15% of these vehicle movements are heavy vehicle movements</p> <p>Advice Note:</p> <p>Where the likely vehicle movement rates or the actual generation rates of the actual activity are unknown, Table 11 – Vehicle movement rates provides indicative traffic generation rates for various activities.</p>	
<b>TRPT-R5</b>	Operation, maintenance and minor upgrading of existing public roads, State Highways and associated road network activities	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Operation, maintenance and minor upgrading of existing public roads, State Highways, rail corridors and associated rail network and road network activities must comply with the following standards:</p> <p>(i) The works occur within the road reserve or railway corridor;</p> <p>(ii) Works within the road or railway corridor must be for the purpose of:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Adverse effects on amenity values, including construction effects such as vibration and noise;</p> <p>(b) Adverse operational effects, particularly on residential or other sensitive land uses, including effects of vibration, noise, glare and vehicle emissions;</p> <p>(c) Severance and changes to drainage patterns;</p>

	<p>(1) Maintaining or improving effectiveness or efficiency consistent with the function of the existing public road or railway corridor; or</p> <p>(2) Maintaining or improving safety for road users or adjacent properties; and</p> <p>(iii) Lighting shall be designed and located to comply with the Australia New Zealand Roadway Lighting Standard 1158, (series) – Lighting for Roads and Public Spaces: 2005; and</p> <p>(iv) Any earthworks must comply with Rule AINF-R8.</p>	<p>(d) The benefits provided by the activity, including safety and efficiency of the road network;</p> <p>(e) Management of sediment and dust, including the staging of works;</p> <p>(f) The volume, extent and depth of the earthworks activities; and</p> <p>(g) The location of the earthworks activities, taking into account any effects on the values, qualities and characteristics of the site.</p>
<b>TRPT-R6</b>	New public roads, including where the road has been identified on the planning maps as an indicative road, and associated road network activities	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) New public roads, including where the road has been identified on the planning maps as an indicative road, and associated road network activities must comply with the following standards:</p> <p>(i) The public road is located within road or unformed road as shown on the planning maps;</p> <p>(ii) The public road is not located within an Identified Area;</p> <p>(iii) The design requirements of Tables 12 or 13 based on their function within the Road Hierarchy as set out in Table 4 – Functions of roads within the Road Hierarchy, except:</p> <p>(1) Any National routes or Regional arterial roads shall be subject to Rule TRPT-R6(2);</p> <p>(2) The specified minimum Road/right of way reserve widths in Tables 12 or 13 do not include any</p>	<p><b>(2) Activity status: RDIS</b></p> <p><b>Where:</b></p> <p>(a) New public roads, including where the road has been identified on the planning maps as an indicative road, and associated road network activities that</p> <p>(i) Are not located within an Identified Area; and</p> <p>(ii) Do not comply with one or more of the standards of Rule TRPT-R6(1)</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(b) Adverse effects on amenity values, including construction effects such as vibration and noise;</p> <p>(c) Adverse operational effects, particularly on residential or other sensitive land uses, including effects of vibration, noise, glare and vehicle emissions;</p> <p>(d) Severance and changes to drainage patterns;</p> <p>(e) The benefits provided by the activity, including safety and efficiency of the road network;</p>

	<p>additional width required for a turning head;</p> <p>(3) Any private access, right of way or access allotment over 70m in length must be constructed to be in accordance with the highest dimensions required for an access allotment in Tables 12 or 13; and</p> <p>(4) The requirements of Tables 12 or 13 shall not apply to taxiways within the TKAZ – Te Kowhai airpark zone;</p> <p>(iv) Within road or unformed road located within the Tamahere RLZ – Rural lifestyle zone, all roads must:</p> <p>(v) Comply with the minimum widths specified in Figure 12; and</p> <p>(vi) Have swale drains on both sides of the carriageway capable of collecting all road runoff and overland flow towards the road or right of way from a 20% Annual Exceedance Probability event; and</p> <p>(vii) In areas of poorly-drained soils, either the stormwater is to be directed to areas with higher infiltration, or infiltration systems are to be constructed.</p> <p>(viii) Within road or unformed road located within the RPZ – Rangitahi peninsula zone, the relevant access and road requirements of the Rangitahi Structure Plan take priority over the standards in Table 12 or 13 in the event of any conflict;</p> <p>(ix) The road connection between Wayside Road and Travers Road comprising the extension of Bragato Way, Te Kauwhata:</p>	<p>(f) Management of sediment and dust, including the staging of works;</p> <p>(g) The volume, extent and depth of the earthworks activities; and</p> <p>(h) The location of the earthworks activities, taking into account any effects on the values, qualities and characteristics of the site</p> <p><b>(3) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) New public roads, including where the road has been identified on the planning maps as an Indicative road, and associated road network activities that are located within an Identified Area</p>
--	--	--



	<p>(x) All roads and vehicle accesses shall be constructed in accordance with Table 12 and Figures 14, 15 and 16; and</p> <p>(xi) Stormwater collection must be through grassed swales prior to reaching reticulated systems; and</p> <p>(xii) Any earthworks must comply with Rule AINF-R8.</p> <p>Advice note:</p> <p>Where the standards of Table 12 or 13 do not specify a specific dimension and instead state this aspect is subject to a specific design; this aspect of the road is considered to be exempt when determining a permitted activity under Rule TRPT-R6(1). The design of that specific aspect of the road is therefore subject to a separate certification process by the relevant road controlling authority.</p>	
<b>TRPT-R7</b>	Access and new roads in the TKAZ – Te Kowhai airpark zone	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Airpark roads which are to be vested in Council must comply with the following conditions standards:</p> <p>(i) The design requirements of Table 12 or 13, based on their function within the Road Hierarchy as set out in Table 4 – Functions of roads within the Road Hierarchy, except:</p> <p>(1) The requirements of Table 12 or 13 shall not apply to taxiways within Te Kowhai airpark.</p> <p>(ii) Road alignment and the taxiway network within the TKAZ – Te Kowhai airpark zone shall be in general accordance with APP10 – Te Kowhai Aerodrome.</p> <p>(iii) The western boundary of the TKAZ – Te Kowhai airpark zone shall provide for</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the Te Kowhai airpark zone Framework Plan is not complied with;</p> <p>(b) The extent to which connectivity can safely and practically be achieved between Te Kowhai aerodrome and Te Kowhai village;</p> <p>(c) Adverse effects on amenity values, including construction effects such as vibration and noise;</p> <p>(d) Adverse operational effects, particularly on residential or other sensitive land uses, including effects of vibration, noise, glare and vehicle emissions;</p> <p>(e) Severance and changes to drainage patterns;</p>

	<p>future connectivity options (vehicular and / or pedestrian) in general accordance with the location identified in APP10 – Te Kowhai Aerodrome.</p> <p>(iv) Any earthworks must comply with Rule AINF-R8.</p>	<p>(f) The benefits provided by the activity, including safety and efficiency of the road network;</p> <p>(g) Management of sediment and dust, including the staging of works;</p> <p>(h) The volume, extent and depth of the earthworks activities;</p> <p>(i) The location of the earthworks activities, taking into account any effects on the values, qualities and characteristics of the site or area; and</p> <p>(j) adverse effects on the safety and efficiency of the land transport network.</p>
<b>TRPT-R8</b>	Off-road pedestrian walkways and cycleways, being sections of the public walkway and cycleway network that are not located within the road network	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Off-road pedestrian walkways and/or cycleways, that comply with all of the following standards:</p> <p>(i) Have a minimum 2.0m width or 2.5m where alongside an arterial road or forming a shared path;</p> <p>(ii) Are formed;</p> <p>(iii) Any earthworks must comply with Rule AINF-R8; and</p> <p>(iv) Are not located within an Identified Area.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Design, construction and materials;</p> <p>(b) Safety for cyclists and pedestrians;</p> <p>(c) Connectivity with other off-road pedestrian and cycle facilities and the road network; and</p> <p>(d) Visual and amenity effects; and</p> <p>(e) The location of the earthworks activities, taking into account any effects on the values, qualities and characteristics of the site or area</p>
<b>TRPT-R9</b>	Stock underpasses located within:	
	<p>(a) Road and unformed road;</p> <p>(b) GRUZ – General rural zone</p>	
GRUZ – General rural zone, road and unformed road	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Stock underpasses in the GRUZ – General rural zone located in the road and unformed road that comply with all of the following standards:</p> <p>(i) Any earthworks must comply with Rule AINF-R8; and</p> <p>(ii) Are not located within an Identified Area.</p>	<p><b>(2) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) Stock underpasses not provided for under Rule TRPT-R9(1)</p>
<b>TRPT-R10</b>	Esplanade reserves and strips where a road is stopped	

All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Where land comprising a stopped road or any part of a stopped road adjoins:</p> <p>(i) The mark of mean high water springs of the sea; or</p> <p>(ii) The bank of any river with an average width of 3m or more; or</p> <p>(iii) The margin of any lake with an area of 8 hectares or more Section 345(3) of the Local Government Act 1974 and section 118 of the Public Works Act 1981 will apply only where the land comprising the stopped road or part of the stopped road is identified:</p> <p>(iv) In APP7 – Esplanade priority areas; or</p> <p>(v) On the planning maps as requiring an esplanade reserve, esplanade strip or access strip to be set aside.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>TRPT-R11</b>	Buildings and structures within a road/rail level crossing sight triangle	
All zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the safety and efficiency of rail and road operations will be adversely affected;</p> <p>(b) The outcome of any consultation with KiwiRail; and</p> <p>(c) Any characteristics of the proposed use that will make compliance unnecessary.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

**Table I – Separation distances**

Separation distance of an access onto a road from an intersection or between accesses									
Posted speed	Design speed	Distance (m)							
		P		K		M		N	
		National Regional Arterial and Arterial	Collector Road and Local Road	National Regional Arterial and Arterial	Collector Road and Local Road	National Regional Arterial and Arterial	Collector Road and Local Road	National Regional Arterial and Arterial	Collector Road and Local Road
100 km/h	110 km/h	800	500	500	100	60		200	100
80 km/h	100 km/h	550	305	305	80			100	80
70 km/h	80 km/h	220	200	220	30		45	40	30
60 km/h	70 km/h						20	20	
50 km/h or less	60 km/h						20	15	

*Advice note: The references P, K, M and N are illustrated in Figure 6 – Separation distances*




Figure 6 – Separation distances

**Table 2 – Minimum sight distances**

Design speed (km/h)	From a vehicle entrance generating up to and including 40 vehicle movements per day	From a vehicle entrance generating more than 40 vehicle movements per day	
		Rural areas	Urban areas
40	65m	75m	65m
50	90m	100m	90m
60	115m	125m	115m
70	140m	150m	140m
80	180m	180m	170m
90	215m	215m	-
100	250m	250m	-
110	290m	290m	-

Advice notes:

(1) Sight distances are measured as illustrated in Figure 8 – Minimum sight distances


(2) Urban areas being those with a posted speed limit of 70 km/h or below.

**Table 3 – Road centreline radius**

Road centreline Radius	Approx. design speed
0 – 45m	50 km/h
45 – 60m	60 km/h
60 – 80m	65 km/h
80 – 100m	70 km/h
100 – 120m	75 km/h
120 – 150m	80 km/h

150 – 200m	85 km/h
200 – 300m	95 km/h
300 – 400m	100 km/h
>400m	110km/h

Advice note: curve radius can be determined using the following formula in Figure 7 – Curve radius formula.



**Figure 7 – Curve radius formula**




Figure 8 – Minimum sight distances



**Table 4 – Functions of roads within the Road Hierarchy**

<b>Category</b>	<b>Function</b>
National routes	Motorways, expressways and state highways that: <ul style="list-style-type: none"> <li>• form a strategic network of national importance</li> <li>• provide for the collection and distribution of goods significant to the national economy</li> <li>• the through traffic function predominates.</li> </ul>
Regional arterial roads: <ul style="list-style-type: none"> <li>• state highways not included in National Routes category</li> <li>• roads giving access to important tourist areas or centres of large populations</li> <li>• roads linking different transport modes</li> <li>• roads providing significant intra-urban links.</li> </ul>	State highways and roads that: <ul style="list-style-type: none"> <li>• form a strategic network of regional importance</li> <li>• provide for the collection and distribution of goods significant to the regional economy</li> <li>• rural roads that typically provide for more than 6,000 vehicle movements per day (vmpd)</li> <li>• include rest areas</li> <li>• the through-traffic function predominates.</li> </ul>
Arterial roads: <ul style="list-style-type: none"> <li>• links between residential, commercial, industrial or recreational land use activities</li> <li>• provide alternative links between centres of population or are significant for the movement of goods or produce within the district.</li> </ul>	Roads that: <ul style="list-style-type: none"> <li>• form a strategic network of district importance</li> <li>• provide for the collection and distribution of goods significant to the district's economy</li> <li>• rural roads that typically provide for less than 6,000 vehicle movements per day (vmpd)</li> <li>• the through traffic function needs to be balanced against the property access function.</li> </ul>
Collector roads: <ul style="list-style-type: none"> <li>• provide links between local roads and arterials.</li> </ul>	Roads that: <ul style="list-style-type: none"> <li>• provide locally-preferred routes between or within areas of population or activities</li> <li>• provide alternative routes to arterials</li> <li>• are sealed and are of road geometry aligned with operational safety standards required for the traffic volumes on each section</li> </ul>

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

	the through traffic function needs to be balanced against the property access function.
Local roads	Roads whose primary function is property access.
Cul-de-sacs and no-exit roads	Roads that do not provide a vehicular thoroughfare between roads, and whose primary function is property access.

Advice note: Corridor widths, road standards and the location of structures and services will vary for each road category, in accordance with Tables 12 and 13.

**Table 5 – Road Hierarchy list**

<b>National Routes</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
State Highway 1	North district boundary	Hamilton City boundary
State Highway 1	Hamilton City boundary	South district boundary
State Highway 2	State Highway 1	East district boundary
State Highway 26	Hamilton City boundary	East district boundary

<b>Regional Arterial</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
State Highway 1B (Gordonton Road)	State Highway 1	Taylor Road
State Highway 1B (Taylor Road)	Gordonton Road	Puketaha Road
State Highway 1B (Puketaha Road)	Taylor Road	Telephone Road
State Highway 1B (Telephone Rd)	Puketaha Road	Holland Road
State Highway 1B (Marshmeadow Road)	Holland Road	State Highway 26
State Highway 1B (Hoeka Road)	State Highway 26	Tauwhare Road

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Regional Arterial</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
State Highway 1B (Marychurch Road)	Tauwhare Road	Southeast district boundary
Gordonton Road	Taylor Road	Hamilton City boundary
State Highway 23	Hamilton City boundary	Manukau Road, Raglan
State Highway 21 (Airport Road)	Tamahere interchange	West district boundary
State Highway 39 (Koura Drive)	State Highway 1	State Highway 39 (Limmer Road)
State Highway 39 (Te Kowhai Road)	State Highway 39 (Koura Drive)	State Highway 39 (Limmer Road)
State Highway 39 (Limmer Road)	State Highway 39 (Limmer Road)	State Highway 39 (Horotiu Road)
State Highway 39 (Horotiu Road)	State Highway 39 (Limmer Road)	State Highway 39 (Whatawhata Road)
State Highway 39 (Kakaramea Road)	State Highway 23	South district boundary
Great South Road	Gordonton Road	State Highway 1 (Waikato Expressway)

<b>Arterial</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
Buckland Road	Tuakau Road	George Street
George Street (Tuakau)	Buckland Road	Whangarata Road
Glen Murray Road	Te Ohaki Road	Marshall Road
Gordonton Road	Borman Road/Hamilton City boundary	State Highway 1B/Taylor Road
Great South Road	Gordonton Road	State Highway 1 (Waikato Expressway)

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Arterial</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
Hetherington Road	Te Ohaki Road	State Highway 22
Holland Road	Ruakura Road	Waverley Road
Horotiu Bridge Road	River Road	Great South Road
Horotiu Road	Ngaruawahia Road	State Highway 39
Ngaruawahia Road	Havelock Road	Horotiu Road
Okaeria Road	Cozen Road	State Highway 2
Piako Road	State Highway 1B	Valentine Road
Puketaha Road	Gordonton Road	Piako Road
River Road (Ngaruawahia)	Kay Road	Great South Road
River Road (Tuakau)	Whangarata Road	Tuakau Bridge
Ruakura Road	State Highway 26	District boundary
Tahuna Road	Ohinewai South Road	District boundary
Tauwhare Road	State Highway 21	State Highway 26
Te Kauwhata Road	State Highway 1	Mahi Road
Victoria Road	Tauwhare Road	Bellevue Road
Waerenga Road	Wira Street	Cozen Road
Waverley Road	Holland Road	Piako Road
Whatawhata Avenue	Ellery Street	Havelock Road
Whitikahu Road	State Highway 1B	Orini Road

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Collector</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
Aka Aka Road	Waiuku Road	Otaua Road
Bankier Road	Horsham Downs Road	State Highway 1B/Gordonton Road
Dean Road	Great South Road	State Highway 1
George Street (Tuakau)	Dominion Road	Buckland Road
Great South Road (Huntly)	State Highway 1	Rayner Road
Great South Road (Pokeno)	State Highway 1	State Highway 1
Hakanoa Street	Onslow Street	Fletcher Street
Harris Street	Rotowaro Road	Te Ohaki Road
Harrisville Road	Mill Road	Dominion Road
State Highway 22	Tuakau Bridge	Hetherington Road
Horace Russell Road	Riverbank Road	State Highway 1
Kaiaua Road	Mangatangi Road	District boundary
Lake Road	River Road	State Highway 1B
Lyons Road	Mangatawhiri Road	Paparimu Road
Mangatangi Road	Mangatawhiri Road	Kaiaua Road
Mangatawhiri Road	State Highway 2	Mangatangi Road
Matangi Road	District boundary	Tauwhare Road
Mercer Ferry Road	Riverbank Road	Murray Road
Mile Bush Road	State Highway 22	Murray Road
Newell Road	State Highway 1	Devine Road
Onewhero-Tuakau Bridge Road	State Highway 22	Speed restriction
Onslow Street	Cul-de-sac west end	William Street

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Collector</b>		
<i>Road Name</i>	<i>Start</i>	<i>Finish</i>
Otaua Road	Aka Aka Road	Waiuku-Otaua Road
Paparimu Road	Lyons Road	District boundary
Platt Road	State Highway 26	Tauwhare Road
Pokeno Road	Great South Road	Ridge Road
Rawiri Road	Mangatangi Road	State Highway 2
Rayner Road	Main Street	William Street
Rotowaro Road	Harris Street	Waingaro Road
State Highway 22	Tuakau Bridge	Hetherington Road
Tainui Bridge Road	State Highway 1	Harris Street
Te Mata Road	State Highway 23	Ruapuke Road
Te Pahu Road	State Highway 23	District boundary
Tuakau Bridge-Port Waikato Road	State Highway 22	Maunsell Road
Waingaro Road	Great South Road	Ohautira Road
Wainui Road	Bow Street	Whaanga Road
Wainui Road/Bankart Street	Wainui Road (north)	Wainui Road (north)
Waiuku-Otaua Road	Otaua Road	Misa Road
Wallis Street	Bow Street	End of kerb and channel
Whangarata Road	River Road	Ridge Road
William Street	Rayner Road	Onslow Street

**Table 6 – Required loading bays**

<b>Activity</b>	<b>Minimum Required Loading Bays</b>
Bulk retail and car yards	1 heavy goods vehicle
Early childhood education and day care facility	Nil
Clubrooms at sports facilities	1 heavy goods vehicle
Community facilities, conference facilities and place of assembly	1 heavy goods vehicle
Marae complex	1 heavy goods vehicle
Papakaainga building	Nil
Dairies, takeaway food, bottle stores	1 heavy goods vehicle, except that in the RPZ – Rangitahi Peninsula zone 1 heavy goods vehicle per 1000m <sup>2</sup> of GFA of Rangitahi commercial activity is required
Minor residential unit	Nil
Residential unit	Nil
Retirement village	Nil
Te Kauwhata Lakeside Retirement Village Retirement villages located within the Lakeside Te Kauwhata Precinct	Nil
Multi-unit development	Nil
Boarding houses / boarding establishments	Nil
Emergency service facilities	Nil
Garden centres	1 heavy goods vehicle
Health facility, veterinary and personal services	Nil
Home businesses	Nil
Hospitality services (e.g. cafés, taverns)	1 heavy goods vehicle, except that in the RPZ – Rangitahi Peninsula zone 1 heavy goods vehicle per 1000m <sup>2</sup> GFA of Rangitahi commercial activity is required.
Housing for the elderly/ residential care	Nil

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Activity</b>	<b>Minimum Required Loading Bays</b>
Indoor sports facilities	Nil
Industrial activity	1 heavy goods vehicle
Infrastructure sites and activities	Nil
Office	Nil
Outdoor sports field	Nil
Hospital or care facilities associated with retirement village	1 heavy goods vehicle
Retail activity	Nil
School	1 bus space per 200 students where school bus services are provided
Service stations	Nil
Supermarket activity	Under 2500m <sup>2</sup> GFA – 1 heavy goods vehicle Over 2500m <sup>2</sup> GFA – 2 heavy goods vehicles
Tertiary education facilities	1 heavy goods vehicle
Visitor accommodation	1 heavy goods vehicle






Figure 9 – 90th Percentile car tracking curve minimum radius

**Table 7 – Accessible parking spaces**

Parking spaces are to be provided for people with disabilities and accessible routes from the parking spaces to the associated activity or road as required by the New Zealand Building Code D1/AS1. The dimensions and accessible route requirements are detailed in the New Zealand Building Code D1/AS1 New Zealand Standard for Design for Access and Mobility – Buildings and Associated Facilities (NZS: 4121- 2001).

**Table 8 – Required bicycle spaces**

<b>Activity</b>	<b>Required number of bicycle spaces</b>
Bulk retail and car yards	GFA less than or equal to 1,500 m <sup>2</sup> = No bicycle space required; For GFA greater than 1,500 m <sup>2</sup> = 1 bicycle space for every 1,500m <sup>2</sup> GFA or part thereof
Early Childhood Education and day care facility	Less than or equal to 4 classroom equivalents = No bicycle space required; Greater than 4 classroom equivalents = 1 bicycle space for every 4 classroom equivalents or part thereof
Clubrooms and sports facilities	GFA less than or equal to 3,500 m <sup>2</sup> = No bicycle space required; For GFA greater than 3,500 m <sup>2</sup> = 1 bicycle space for every 3,500 m <sup>2</sup> GFA or part thereof
Community facilities, conference facilities and place of assembly	GFA less than or equal to 1,500 m <sup>2</sup> = No bicycle space required; For GFA greater than 1,500 m <sup>2</sup> = 1 bicycle space for every 1,500m <sup>2</sup> GFA or part thereof
Marae complex	GFA less than or equal to 1,500 m <sup>2</sup> = No bicycle space required; For GFA greater than 1,500 m <sup>2</sup> = 1 bicycle space for every 1,500m <sup>2</sup> GFA or part thereof
Papakaainga building	GFA less than or equal to 3,000 m <sup>2</sup> = No bicycle space required; For GFA greater than 3,000 m <sup>2</sup> = 1 bicycle space for every 3,000 m <sup>2</sup> GFA or part thereof
Dairies, takeaway food, bottle stores	GFA less than or equal to 3,000 m <sup>2</sup> = No bicycle space required; For GFA greater than 3,000 m <sup>2</sup> = 1 bicycle space for every 3,000 m <sup>2</sup> GFA or part thereof

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Activity</b>	<b>Required number of bicycle spaces</b>
	Except that in the RPZ – Rangitahi Peninsula zone the following applies: GFA less than or equal to 5,000 m <sup>2</sup> = No bicycle space required; For GFA greater than 5,000 m <sup>2</sup> = 1 bicycle space for every 5,000 m <sup>2</sup> GFA or part thereof
Minor residential unit	Less than or equal to 10 minor residential units = No bicycle space required; For greater than 10 minor residential units = 1 bicycle space for every 10 minor residential units or part thereof
Residential unit	Less than or equal to 10 residential units = No bicycle space required; For greater than 10 residential units = 1 bicycle space for every 10 residential units or part thereof
Retirement village	Less than or equal to 10 residential units = No bicycle space required; For greater than 10 residential units = 1 bicycle space for every 10 residential units or part thereof
Multi-unit development	Less than or equal to 10 residential units = No bicycle space required; For greater than 10 residential units = 1 bicycle space for every 10 residential units or part thereof
Boarding houses / boarding establishments	Less than or equal to 30 units = No bicycle space required; For greater than 30 units = 1 bicycle space for every 30 units or part thereof
Emergency service facilities	Less than or equal to 10 on-duty staff = No bicycle space required; For greater than 10 on-duty staff = 1 bicycle space for every 10 on-duty staff or part thereof
Garden centres	GFA less than or equal to 1,000 m <sup>2</sup> = No bicycle space required; For GFA greater than 1,000 m <sup>2</sup> = 1 bicycle space for every 1,000m <sup>2</sup> GFA or part thereof
Health facility, veterinary and personal services	Less than or equal to 4 on-duty staff = No bicycle space required; For greater than 4 on-duty staff = 1 bicycle space for every 4 on-duty staff or part thereof
Home occupations	In addition to residential requirements: Less than or equal to 10 employees = No bicycle space required; For greater than 10 employees = 1 bicycle space for every 10 employees or part thereof

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation


<b>Activity</b>	<b>Required number of bicycle spaces</b>
Hospitality services (e.g. cafés, taverns)	<p>Net public floor area less than or equal to 100 m<sup>2</sup> = No bicycle space required;                      Net public floor area greater than 100 m<sup>2</sup> = 1 bicycle space for every 100m<sup>2</sup> net public floor area or part thereof</p> <p>Except that in the RPZ – Rangitahi Peninsula zone the following applies:                      Net public floor area less than or equal to 150 m<sup>2</sup> = No bicycle space required;                      Net public floor area greater than 150 m<sup>2</sup> = 1 bicycle space for every 150m<sup>2</sup> net public floor area or part thereof</p>
Housing for the elderly / residential care	<p>Less than or equal to 40 occupants = No bicycle space required;                      For greater than 40 occupants = 1 bicycle space for every 40 occupants or part thereof</p>
Indoor sports facilities	<p>Less than or equal to 40 persons provided for in the design = No bicycle space required;                      For greater than 40 persons provided for in the design = 1 bicycle space for every 40 persons provided for in the design or part thereof</p>
Industrial activity	<p>GFA less than or equal to 1,000 m<sup>2</sup> = No bicycle space required;                      For GFA greater than 1,000 m<sup>2</sup> = 1 bicycle space for every 1,000m<sup>2</sup> GFA or part thereof</p>
Infrastructure sites and activities	<p>Less than or equal to 10 on-duty staff = No bicycle space required;                      For greater than 10 on-duty staff = 1 bicycle space for every 10 on-duty staff or part thereof</p>
Office	<p>GFA less than or equal to 350 m<sup>2</sup> = No bicycle space required;                      For GFA greater than 350 m<sup>2</sup> = 1 bicycle space for every 350m<sup>2</sup> GFA or part thereof</p>
Outdoor sports field	<p>Less than or equal to 6,600 m<sup>2</sup> of sports field = No bicycle space required;                      Greater than 6,600 m<sup>2</sup> of sports field = 1 bicycle space for every 6,600 m<sup>2</sup> of sports field or part thereof</p>
Hospital or care facilities associated with retirement village	<p>Less than or equal to 20 full-time staff equivalents = No bicycle space required;                      For greater than 20 full-time staff equivalents = 1 bicycle space for every 20 full-time staff equivalents or part thereof</p>
Retail activity	<p>GFA (including indoor and outdoor retail area) less than or equal to 300 m<sup>2</sup> = No bicycle space required;</p>

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Activity</b>	<b>Required number of bicycle spaces</b>
	For GFA (including indoor and outdoor retail area) greater than 300 m <sup>2</sup> = 1 bicycle space for every 300 m <sup>2</sup> GFA (including indoor and outdoor retail area) or part thereof
School	Less than or equal to 10 full-time staff equivalents = No bicycle space required; For greater than 10 full-time staff equivalents = 1 bicycle space for every 10 full-time staff equivalents or part thereof
Service stations	GFA (excluding car washes and canopies over petrol pumps) less than or equal to 450 m <sup>2</sup> = No bicycle space required; For GFA (excluding car washes and canopies over petrol pumps) greater than 450 m <sup>2</sup> = 1 bicycle space for every 450m <sup>2</sup> GFA (excluding car washes and canopies over petrol pumps) or part thereof
Supermarket activity	GFA less than or equal to 250 m <sup>2</sup> = No bicycle space required; For GFA greater than > 250 m <sup>2</sup> = 1 bicycle space for every 250m <sup>2</sup> or part thereof
Tertiary education facilities	Less than or equal to 10 full-time staff equivalents = No bicycle space required; For greater than 10 full-time staff equivalents = 1 bicycle space for every 10 full-time staff equivalents or part thereof
Visitor accommodation	Less than or equal to 40 persons to be accommodated = No bicycle space required; For greater than 40 persons to be accommodated = 1 bicycle space for every 40 persons to be accommodated or part thereof

**Table 9 – Car manoeuvring and parking space dimensions**

Type of parking		Stall width (a)	Stall depth		Aisle width (d)	Total depth (c)	
Parking angle	Type		From wall (b)	From kerb (c)		One row	Two rows
All measurements are in metres							
0°	Parallel	2.5	See Note 1		3.5	5.9	8.3
30°	Nose in	2.5	4.2	4.0	3.5	7.7	11.9
45°	Nose in	2.5	4.9	4.5	3.5	8.4	13.3
60°	Nose in	2.5	5.4	4.9	4.1	9.5	14.9
		2.6			3.5	8.9	14.3
		2.7			3.5	8.9	14.3
75°	Nose in	2.5	5.4	4.9	6.3	11.7	17.1
		2.6			5.2	10.6	16.0
		2.7			4.6	10.0	15.4
90°	Nose in	2.5	5.1	4.6	7.7	12.8	17.9
		2.6			7.0	12.1	17.2
		2.7			6.8	11.9	17.0



**Figure 10 – Car manoeuvring and parking space dimensions**

**Table 10 – Queuing space**

<b>Number of parking spaces</b>	<b>Minimum queuing length at each vehicle entrance</b>
Less than 3	No queuing space required.
Residential activities	
3 – 20	5.5m
21 – 50	10.5m
51 – 100	15.5m
101 – 150	20.5m
151 or over	25.5m
Drive-through facilities with access from an arterial road	50m

**Table 11 – Vehicle movement rates**

<b>Activity</b>	<b>Indicative daily vehicle movements*</b>
Bulk retail and car yards	45 per 100m <sup>2</sup> gross floor area (GFA)
Early childhood education and day care facility	4 per child the facility is designed to accommodate
Dairies, bottle stores	100 per 100m <sup>2</sup> GFA
Takeaway food	360 per 100m <sup>2</sup> GFA
Residential units	10 per residential unit
Garden centres	100 per 100m <sup>2</sup> GFA
Health facility veterinary, and personal services	79.4 per professional the facility is designed to accommodate
Hospitality services (e.g. cafés, bars)	90 per 100m <sup>2</sup> GFA



Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

<b>Activity</b>	<b>Indicative daily vehicle movements*</b>
Housing for the elderly/residential care	2 per resident the facility is designed to accommodate
Industrial activities	Manufacturing 30 per 100m <sup>2</sup> GFA Warehouse 2.4 per 100m <sup>2</sup> GFA
Offices	25 per 100m <sup>2</sup> GFA
Hospital	15 per patient bed the facility is designed to accommodate
Retail activity	130 per 100m <sup>2</sup> GFA
School	2 per student the primary school is designed to accommodate, or 1 per student the secondary school is designed to accommodate
Service stations	700 per 100m <sup>2</sup> GFA
Supermarket activity	130 per 100m <sup>2</sup> GFA
Tertiary education facilities	2 per student the facility is designed to accommodate
Visitor accommodation	3 per bed the facility is designed to accommodate

*Advice note: \* Based on Trips and parking related to land use - NZ Transport Agency research report 453, November 2011*

**Table 12 – Access and road standards (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone, LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone, HIZ – Heavy industrial zone, TKAZ – Te Kowhai Airpark zone, RPZ – Rangitahi Peninsula zone and MSRZ – Motorsport and recreation zone)**

Road Type	General				Seal Width				Berms		General	
	Number of Allotments or Activities	Design Speed (km/h)	Design Vehicle (RTS 18 Vehicle)	*Minimum Road/ROW Reserve Width (m)	Minimum Trafficable Carriageway (m)	Minimum Median Provision (m)	Parking Provision	Minimum Total Seal Width (m) Does not include concrete kerb width	Minimum Services (m)	Minimum Footpath / Shared path (m)	Kerb and Channel / Water-table	Turning Area for no exit roads (RTS 18 Vehicle)
<b>Access and road standards (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone, LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)</b>												
Access leg to an allotment (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)	1	N/A	8m Rigid	4	N/A							
Access leg to an allotment (LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)	1	N/A		6	N/A							
Private access, including ROWs and access allotments (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)	2 to 4	N/A		8	5	N/A	N/A	4	Unsealed 1.2m on at least one side	N/A	Nib on one side, mountable on other	Subject to specific design that has been certified
Private access, including ROWs and access allotments (LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)	2 to 8	N/A		10	6		N/A	6			Mountable	Subject to specific design that has been certified
Access allotment (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)	5 to 8	N/A		8	5		Optional	5			Mountable	Yes
Service Lane (LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)	N/A	N/A	Subject to specific design that has been certified	8	6		No parking	6	Subject to specific design that has been certified	Optional	Non-mountable	Subject to specific design that has been certified
Local Road (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)	>8	50	8m Rigid	20	6	None	1m on each side	8		1.8m on each side		8m Rigid

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)												
Local Road (LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)			19m Semi		9		Optional	9				19m Semi
Collector Road (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)	>100	50	8m Rigid	22	6	Subject to specific design that has been certified	2.5m on each side	11		1.8m on each side		8m Rigid
Collector Road (LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)			19m Semi		7			12				19m Semi
Arterial Road (GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone)	N/A	60	19m Semi	30	10	3	Recessed 2.5m on each side	13		1.8m on each side		N/A
Arterial Road (LCZ – Local centre zone, COMZ – Commercial zone, TCZ – Town centre zone, GIZ – General industrial zone and HIZ – Heavy industrial zone)												
Local roads in Lorenzen Bay Structure Plan Area	>8	50-80 (max)	N/A	17 (Complies with Figure 13)	6		2.5 metres on alternative sides	11	Subject to specific design that has been certified	1.5 metres on one side of the road	Subject to specific design that has been certified	Yes
Roads in Te Kauwhata Structure Plan area	>1	50-80 (max)	N/A	20	Refer to Figures 14 -16 (cross-sections)							

Advice notes:

The Regional Infrastructure Technical Specifications May 2018 contains further details on road width/design requirements.


Figure 11 illustrates the various parts of the road (seal width, berm etc.) defined in Tables 12 and 13.

\*Accesses shall have a minimum height clearance of 4.0m and a maximum gradient of 1 in 5 (with minimum 4.0m transition ramps of 1 in 8) except where the access terminates less than 135m from the nearest road that has reticulated water supply (included hydrants).

**Table 13 – Access and road standards (GRUZ – General rural zone and RLZ – Rural lifestyle zone)**

Road Type	General				Seal Width				Berms		General	
	Number of Allotments or Activities	Design Speed (km/h)	Design Vehicle (RTS 18 Vehicle)	*Minimum Road/ROW Reserve Width (m)	Minimum Trafficable Carriageway (m)	Minimum Median Provision (m)	Parking Provision	Minimum Total Seal Width (m) Does not include concrete kerb width	Minimum Services (m)	Minimum Footpath / Shared path (m)	Kerb and Channel / Water-table	Turning area for no exit roads (RTS 18 Vehicle)
<b>GRUZ – General rural zone and RLZ – Rural lifestyle zone</b>												
Access leg to an allotment	1	N/A	8m Rigid	6	N/A							
Private access, including ROWs and access allotments	2 to 3	N/A		6	3	N/A	N/A	3	Subject to specific design that has been certified	N/A	Optional	Subject to specific design that has been certified
Access allotment	4 to 8	N/A		10	5		5	Yes				
Local	>8	Subject to specific design	Subject to specific design that has been certified	20	6	No	6	Subject to specific design that has been certified			RLZ – Rural lifestyle zone - nibs along seal edge. All others to specific design that has been certified.	8m Rigid
Collector <1000 adt	>100		19m Semi	20	7	Subject to specific design that has been certified	8.5					
Collector >1000 adt or Arterial	N/A	110	20	7	10		N/A					


Advice note: \*Accesses shall have a minimum height clearance of 4.0m and a maximum gradient of 1 in 5 (with minimum 4.0m transition ramps of 1 in 8)




**Figure 11 – Attachment to Tables 12 and 13**

*Advice note: The purpose of Figure 11 is to define the various aspects of the road as set out in Tables 12 and 13. Figure 11 is not intended to prescribe a preferred road layout.*

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation



CROSS SECTION OF LOCAL ROAD - TAMAHERE COUNTRY LIVING ZONE  
SCALE : 1:50




CROSS SECTION OF COLLECTOR ROAD - TAMAHERE COUNTRY LIVING ZONE  
SCALE : 1:50




**Figure 12 – Tamahere RLZ – Rural lifestyle zone – road cross sections**

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation



CROSS SECTION THROUGH COLLECTOR ROAD - LORENZEN BAY  
SCALE : 1:25




CROSS SECTION THROUGH MINOR ROAD - LORENZEN BAY  
SCALE : 1:25



**Figure 13 – Lorenzen Bay Structure Plan - road cross sections**

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation



**CROSS SECTION THROUGH COLLECTOR ROAD 25.5m (vpd>1500)**

SCALE 1:50  
TE KAUWHATA STRUCTURE PLAN


**NOTE:**  
1. SWALE DESIGN TO INCLUDE ANTI-SCOUR MECHANISMS WHERE REQUIRED.



**Figure 14 – Te Kauwhata Structure Plan – road cross sections – collector roads**



Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation




CROSS SECTION THROUGH LOCAL ROAD A (500<vpd<1500)

SCALE : 1:50

TE KAUWHATA STRUCTURE PLAN

NOTE:

1. SWALE DESIGN TO INCLUDE ANTI-SCOUR MECHANISMS WHERE REQUIRED.



CROSS SECTION THROUGH LOCAL ROAD B (vpd<500)


SCALE : 1:50

TE KAUWHATA STRUCTURE PLAN



Figure 15 – Te Kauwhata Structure Plan – road cross sections – local roads

Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation




CROSS SECTION THROUGH GREENWAY CORRIDOR 25m

SCALE : 1:50

TE KAUWHATA STRUCTURE PLAN

NOTE:  
SWALE DESIGN TO INCLUDE  
ANTI-SCOUR MECHANISMS  
WHERE REQUIRED



CROSS SECTION THROUGH WHANGAMARINO MARGIN (vpd<500)

SCALE : 1:50

TE KAUWHATA STRUCTURE PLAN



Figure 16 – Te Kauwhata Structure Plan – road cross sections – greenway corridor and Whangamarino margin roads

## Railway Level Crossing Sight Explanations


### *Developments near Existing Level Crossings*

*It is important to maintain clear visibility around level crossings to reduce the risk of collisions. All the conditions set out in this standard apply during both the construction and operation stages of any development.*

### *Approach sight triangles at level crossings with Give Way signs.*

*On sites adjacent to rail level crossings controlled by Give Way signs, no building, structure or planting shall be located within the shaded areas shown in Figure 17. These are defined by a sight triangle taken 30 metres from the outside rail and 320 metres along the railway track.*

APPROACH SIGHT TRIANGLES AT RAILWAY LEVEL CROSSINGS



**Figure 17 – Approach sight triangles for level crossings with “Give Way” signs**

## Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

*Advice notes: The approach sight triangles ensure that clear visibility is achieved around rail level crossings with Give Way signs so that a driver approaching a rail level can either:*

- See a train and stop before the crossing: or*
- Continue at the approach speed and cross the level crossing safely.*


*Of particular concern are developments that include shelter belts, tree planting, or series of building extensions. These standards apply irrespective of whether any visual obstructions already exist.*

*No approach sight triangles apply for level crossings fitted with alarms and/or barrier arms. However, care should be taken to avoid developments that have the potential to obscure visibility of these alarm masts. This is particularly important where there is a curve in the road on the approach to the level crossing, or where the property boundary is close to the edge of the road surface and there is the potential for vegetation growth.*

*Restart sight triangles at level crossings*

*On sites adjacent to all rail level crossings, no building, structure or planting shall be located within the shaded areas shown in Figure 18. These are defined by a sight triangle taken 5 metres from the outside rail and distance A along the railway track. Distance A depends on the type of control (Table 14).*

RESTART SIGHT TRIANGLES AT RAILWAY LEVEL CROSSINGS



**Figure I8 – Restart sight triangles for all level crossings (except those fitted with train activities barriers)**

**Table I4 – Required restart sight distances for Figure I8**

Required approach visibility along tracks A (m)		
Signs only	Alarms only	Alarms and barriers
677 m	677 m	60m

Refer to next page for advice notes.

## Part 2: District-wide matters / Energy, infrastructure and transport / TRPT – Transportation

### *Advice notes:*

*The restart sight line triangles ensure that a road vehicle driver stopped at a level crossing can see far enough along the railway to be able to start off, cross and clear the level crossing safely before the arrival of any previously unseen train. Of particular concern are developments that include shelter belts, tree planting or series of building extensions. These standards apply irrespective of whether any visual obstructions already exist.*

*Figures 17 and 18 show a single set of rail tracks only. For each additional set of tracks add 25 m to the along-track distance in Figure 17, and 50 m to the along-track distance in Figure 18.*

*All figures are based on the sighting distance formula used in NZTA Traffic Control Devices Manual 2008, Part 9 Level Crossings. The formulae in this document are performance based; however, the rule contains fixed parameters to enable easy application of the standard. Approach and restart distances are derived from a:*

- Train speed of 110 km/h*
- Vehicle approach speed of 20 km/h*
- Fall of 8 % on the approach to the level crossing and a rise of 8 % at the level crossing*
- 25 m design truck length*
- 90° angle between road and rail*

## WWS – Water, wastewater and stormwater

### Rules

<b>WWS-RI</b>	Stormwater systems for new development or subdivision	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) New development or subdivision must have a stormwater system that complies with all of the following standards:</p> <p>(i) Operates by gravity;</p> <p>(ii) Manages stormwater through a Stormwater Management Plan in the following manner:</p> <p>(1) Primary systems detain or retain runoff from all impervious surfaces during a 10% Annual Exceedance Probability storm event to ensure that the rate of any stormwater discharge off-site is at or below pre-development rates; and</p> <p>(2) Secondary overflows are conveyed to a system or drainage path designed to collect concentrated stormwater during events up to and including a 1% Annual Exceedance Probability; or</p> <p>(3) A controlled discharge to a network or receiving environment that will have equivalent capacity (as in (i) and (ii) above) once the catchment is fully developed.</p> <p>(iii) Stormwater management measures must be in place and operational upon the completion of subdivision and/or development;</p> <p>(iv) Systems must be designed using rainfall data specific to the area in which the property is located and be adjusted for a climate change</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The likely effectiveness of the system to avoid flooding, nuisance or damage to other buildings and sites;</p> <p>(b) The capacity of the system and suitability to manage stormwater;</p> <p>(c) The potential for adverse effects to the environment in terms of stormwater quantity and stormwater quality effects; and</p> <p>(d) Extent to which low impact design principles and approaches are used.</p>

	<p>temperature increase of 2.1°C;</p> <p>(v) Stormwater management measures, including low impact design measures, must be implemented as appropriate in accordance with the following drainage hierarchy:</p> <ol style="list-style-type: none"> <li>(1) Retention of rainwater/stormwater for reuse;</li> <li>(2) Soakage techniques;</li> <li>(3) Infiltration rate of a minimum of 7mm/hour;</li> <li>(4) Treatment, detention and gradual release to a watercourse;</li> <li>(5) Treatment, detention and gradual release to a piped stormwater system.</li> <li>(6) Stormwater treatment shall address water quality; downstream erosion and scour effects; and cumulative volume effects.</li> </ol> <p>(vi) Where land is subject to instability, stormwater discharges directly to ground occurs only where the ground conditions have been identified as being suitable to absorb such discharges without causing, accelerating or contributing to land instability and downstream effects either on the site or on neighbouring properties;</p> <p>(vii) Connection of new development to any existing stormwater drainage system must not result in the minimum level of service not being met or the minimum level of capacity being exceeded. Alteration of the existing receiving stormwater network drainage system to achieve minimum level of service or additional onsite detention volume to ensure</p>	
--	---	--



Part 2: District-wide matters / Energy, infrastructure and transport / WWS – Water, wastewater and stormwater

	<p>existing capacity will be required.</p> <p>Advice notes:</p> <p>Acceptable means of compliance for the provision, design and construction of stormwater infrastructure, including low impact design features, are contained within the Regional Infrastructure Technical Specifications (RITS). Refer also to Waikato Stormwater Management Guideline and Waikato Stormwater Run-off Modelling Guideline.</p> <p>A stormwater discharge consent may also be required from the Waikato Regional Council.</p>	
<b>WWS-R2</b>	Wastewater servicing for new development or subdivision	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) New development or subdivision must have a wastewater system that complies with the following standards:</p> <p>(i) Is connected to public, reticulated wastewater network; or</p> <p>(ii) Is connected to a community-scale wastewater system; or</p> <p>(iii) Is provided with a site-contained, alternative method of wastewater disposal that complies with AS/NZS 1547:2012.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Health and safety of the occupants;</p> <p>(b) Capacity of the system;</p> <p>(c) Infiltration capacity of the soil;</p> <p>(d) Location, including proximity to waterways and effects on habitats; and</p> <p>(e) Contamination of downstream properties by wastewater.</p>
<b>WWS-R3</b>	Below ground pipelines for the conveyance of water, wastewater and stormwater	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Pipelines for the conveyance of water, wastewater and stormwater that comply with all of the following:</p> <p>(i) Any aboveground section of a pipeline must comply with the following:</p> <p>(I) Not exceed 25m in length, and</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, streetscape and amenity effects;</p> <p>(c) Road network safety and efficiency;</p>

Part 2: District-wide matters / Energy, infrastructure and transport / WWS – Water, wastewater and stormwater

	<p>(2) Not exceed 300mm in diameter.</p> <p>(3) Is not located within an Identified Area and .</p> <p>(b) The maximum dimensions in Rule WWS-R3(1)(a)(i) do not apply to any above-ground section of pipeline which is attached to or contained within the superstructure of a bridge.</p>	<p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>
<b>WWS-R4</b>	Below ground pipelines for the conveyance of water, wastewater and stormwater located within an Identified Area	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Below ground pipelines for the conveyance of water, wastewater and stormwater located within an Identified Area that comply with all of the following:</p> <p>(i) There are no aboveground sections of pipeline within an Identified Area; and</p> <p>(ii) Are not within a site or area in SCHED1 – Historic heritage items or SCHED3 – Sites and areas of significance to Maori.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, streetscape and amenity effects;</p> <p>(c) Road network safety and efficiency;</p> <p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>
<b>WWS-R5</b>	Pump stations for the conveyance of water, wastewater and stormwater	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Pump stations for the conveyance of water, wastewater and stormwater that complies with the following standards :</p> <p>(i) Is not located within an Identified Area.</p> <p>(ii) Not exceed 10m<sup>2</sup> in area above-ground; and</p> <p>(iii) Not exceed 3m in height measured from the natural ground level immediately below the structure.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, streetscape and amenity effects;</p> <p>(c) Road network safety and efficiency;</p> <p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>
<b>WWS-R6</b>	Stormwater treatment, detention and retention facilities or devices	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

Part 2: District-wide matters / Energy, infrastructure and transport / WWS – Water, wastewater and stormwater

	(a) Stormwater treatment, detention and retention facilities or devices, excluding stormwater wetlands or ponds.	
<b>WWS-R7</b>	Stormwater ponds or wetlands	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Stormwater ponds or wetlands that comply with the following:</p> <p>(i) The area of the pond or wetland does not exceed the equivalent site building coverage standards applicable to the zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, streetscape and amenity effects;</p> <p>(c) Road network safety and efficiency;</p> <p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>
<b>WWS-R8</b>	Ventilation facilities, drop shafts and manholes	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Ventilation facilities, drop shafts and manholes that comply with the following:</p> <p>(i) Are not located within an Identified Area.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, streetscape and amenity effects;</p> <p>(c) Road network safety and efficiency;</p> <p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>
<b>WWS-R9</b>	Below ground reservoirs	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Below ground reservoirs that comply with all of the following:</p> <p>(i) Are not located within an Identified Area; or</p> <p>(ii) Are not located within road or unformed road.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</p> <p>(b) Visual, streetscape and amenity effects;</p>

Part 2: District-wide matters / Energy, infrastructure and transport / WWS – Water, wastewater and stormwater


		<p>(c) Road network safety and efficiency;</p> <p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>
<b>WWS-R10</b>	Water supply servicing for new development or subdivision	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) New development or subdivision must have a water supply system that complies with the following standards:</p> <p>(i) For the GRUZ – General rural zone, RLZ – Rural lifestyle zone, LLRZ – Large lot residential zone and SETZ – Settlement zone, potable water supply must be provided;</p> <p>(b) For all other zones:</p> <p>(i) Be connected to any available public, reticulated water supply system nearby; and</p> <p>(ii) In addition to connection to reticulated supply for potable water, may also use rainwater harvesting (installation of rain storage tanks for water conservation) to supplement water supply, but not for potable uses.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Health and safety of the occupants; and</p> <p>(b) Sufficiency of supply for fire-fighting.</p>
<b>WWS-R11</b>	The construction of new regional flood management infrastructure in close proximity to existing flood management infrastructure, undertaken by or on behalf of the public authority responsible for the regional flood management infrastructure	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) All activities must comply with the following standards:</p> <p>(i) Activities are carried out:</p> <p>(ii) Within 20m of the landward toe of a stopbank (See Figure 5 below);</p> <p>(iii) On a stopbank;</p> <p>(iv) Within the flood channel (between a stopbank and river bank); and</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	(v) Within a 20m radius of a pump station or floodgate.	
--	---	--

**STOPBANK DIAGRAM**

**Legend**

- |                             |   |
|-----------------------------|---|
| 1. Design flood level (DFL) | 10. Stopbank  |
| 2. Low water channel        | 11. Land within 20m of the landward toe of a stopbank |
| 3. Flood Channel            |   |
| 4. Riverside stopbank toe   |   |
| 5. Riverside batter         |   |
| 6. Stopbank crest level     |   |
| 7. Landside batter          |   |
| 8. Landward stopbank toe    |   |
| 9. Riverside land           |   |



**Figure 5 – Stopbank diagram**

<b>WWS-RI 2</b>	Flood control, renewal, maintenance, unscheduled, and storm response works undertaken by or on behalf of the public authority responsible for the regional flood management infrastructure	
All zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>WWS-RI 3</b>	In close proximity to existing flood management infrastructure: (a) The maintenance of existing stock-proof fences; (b) Grazing of animals; (c) Any farming activity other than the grazing of animals; (d) Planting of trees; (e) The construction of any road or race for the passage of stock or vehicles; (f) The erection of any new fence, shelter, building or structure; (g) The excavation or the digging of any drain; and (h) A network utility or private infrastructure including underground pipes and cables with written approval from the public authority responsible for the regional flood management infrastructure.	

All zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>WWS-RI 4</b>	Stormwater ponds or wetlands, that serve more than one site, located within: <ul style="list-style-type: none"> <li>(a) GRZ – General residential zone;</li> <li>(b) MRZ<u>1</u> – Medium density residential zone <u>1</u>;</li> <li>(c) RPZ – Rangitahi Peninsula zone;</li> <li>(d) SETZ – Settlement zone;</li> <li>(e) LLRZ – Large lot residential zone;</li> <li>(f) RLZ – Rural lifestyle zone;</li> <li>(g) Road and unformed road; <del>and</del></li> <li>(h) Identified Areas; <u>and</u></li> <li>(i) <u>MRZ2 – Medium density residential zone 2.</u></li> </ul>	
All specified in rule	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</li> <li>(b) Visual, streetscape and amenity effects;</li> <li>(c) Road network safety and efficiency;</li> <li>(d) The risk of hazards to public or individual safety, and risk of property damage; and</li> <li>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</li> </ul>	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>WWS-RI 5</b>	Outfall structures located within an Identified Area	
All zones	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) The functional need and operational need of, and benefits derived from, the infrastructure;</li> <li>(b) Visual, streetscape and amenity effects;</li> <li>(c) Road network safety and efficiency;</li> </ul>	<b>(2) Activity status where compliance not achieved: n/a</b>

Part 2: District-wide matters / Energy, infrastructure and transport / WWS – Water, wastewater and stormwater

	<p>(d) The risk of hazards to public or individual safety, and risk of property damage; and</p> <p>(e) Effects on the specific values, qualities and characteristics of any Identified Area.</p>	
<b>WWS-R16</b>	New capital works relating to regional flood management infrastructure, including but not limited to flood control dams, flood gates, stopbanks, channels, and culverting of waterways	
All zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The extent to which adverse effects are avoided, remedied or mitigated.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>WWS-R17</b>	Any other activity that is not permitted under Rules WWS-R11 – WWS-R13 but complies with the activity specific standards in Rule WWS-R11(1)	
All zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the activity will affect the integrity of the flood control asset;</p> <p>(b) The extent to which the activity will impede maintenance access;</p> <p>(c) Methods to avoid, remedy, or mitigate adverse effects on the integrity of the flood control assets; and</p> <p>(d) Methods to avoid, remedy, or mitigate adverse effects on maintenance access.</p> <p>Non-notification:</p> <p>Applications utilising Rule WWS-R17 that do not simultaneously trigger other consent requirements shall not be publicly notified and shall not be served on any party other than Council and the public authority responsible for the regional flood management infrastructure.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>WWS-R18</b>	Water treatment plants not located within road or unformed road	

Part 2: District-wide matters / Energy, infrastructure and transport / WWS – Water, wastewater and stormwater

All zones	<b>(I) Activity status: DIS</b>
<b>WWS-R19</b>	Wastewater treatment plants located within the following: (a) GIZ – General industrial zone; (b) HIZ – Heavy industrial zone; (c) MSRZ – Motor sport and recreation zone; (d) GRUZ – General rural zone; (e) RLZ – Rural lifestyle zone; (f) OSZ – Open space zone
As specified in rule	<b>(I) Activity status: DIS</b>
<b>WWS-R20</b>	Above ground reservoirs
All zones	<b>(I) Activity status: DIS</b>
<b>WWS-R21</b>	Water treatment plants located within the road and or unformed road
All zones	<b>(I) Activity status: NC</b>
<b>WWS-R22</b>	Wastewater treatment plants located within the following: (a) GRZ – General residential zone; (b) MRZ <sub>1</sub> – Medium density residential zone <sub>1</sub> ; (c) RPZ – Rangitahi Peninsula zone; (d) LLRZ – Large lot residential zone; (e) SETZ – Settlement zone; (f) COMZ – Commercial zone; (g) TCZ – Town centre zone; (h) LCZ – Local centre zone; (i) BTZ – Business Tamahere zone; (j) Road and unformed road; <del>or</del> (k) Identified Area; <del>or</del> (l) <u>MRZ<sub>2</sub> – Medium density residential zone <sub>2</sub></u>
As specified in rule	<b>(I) Activity status: NC</b>



## HAZS – Hazardous substances

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Overview

The use of hazardous substances in New Zealand is primarily managed by the Hazardous Substances and New Organisms Act 1996 (HSNO Act), the Health and Safety at Work Act 2015 (HSW Act) and relevant regulations.

Because the District Plan seeks to avoid duplication of requirements and obligations that arise under other legislation and regulations, the provisions of this chapter are designed to manage the effects of use, storage, or disposal of hazardous substances, only to the extent that those effects are not within the ambit of existing legislation and regulations.

### Objectives

HAZS-O1 Manufacture, use and storage of hazardous substances.

To protect the community and natural environment from the adverse effects associated with the manufacture, use and storage of hazardous substances.

HAZS-O2 Use of hazardous substances.

To enable activities to utilise hazardous substances where necessary for their operations, in appropriate locations.

### Policies

HAZS-P1 Reverse sensitivity.

Ensure that activities are able to utilise hazardous substances in compliance with relevant regulation as necessary to their operation, without being compromised by 'reverse sensitivity' (that is, by residential or other sensitive activities moving closer and seeking higher amenity levels, including reduced risks from hazardous substances).

HAZS-P2 Significant hazardous facilities.

Ensure that significant hazardous facilities are appropriately sited and managed in order to reduce risks to the environment and community to acceptable levels.

HAZS-P3 Duplication of regulation.

Avoid any unnecessary duplication of regulation between the Hazardous Substances and New Organisms Act 1996, the Health and Safety at Work Act 2015 and relevant regulations, and the District Plan.

## Rules

*Land use – activities (zones specified in first column)*

<b>HAZS-R1</b>	The storage, handling or use of hazardous substances except where Rule HAZS-R2, HAZS-R3 or HAZS-R4 apply	
All zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved:</b> n/a
<b>HAZS-R2</b>	The storage, handling or use of hazardous substances in a Significant Hazard Facility	
All zones	<p><b>(1) Activity status: DIS</b></p> <p><b>For discretionary activities, the following criteria identify those matters which Council may assess the activity against. However, for discretionary activities Council’s assessment is not restricted to these matters:</b></p> <ul style="list-style-type: none"> <li>(a) Risk assessment comprising: <ul style="list-style-type: none"> <li>(i) The probability and potential consequences of an accident leading to the release or loss of control of hazardous substances;</li> <li>(ii) Potential risks and effects on people and neighbouring activities, with an emphasis on sensitive activities such as residential activities, educational facilities and community facilities;</li> <li>(iii) Potential risks and effects on natural ecosystems and the life supporting capacity of land and water, waterbodies and sources of potable water;</li> <li>(iv) Potential risks and effects on sites of significance to tangata whenua, sites of historical or archaeological significance and Outstanding Natural Features and Landscapes;</li> <li>(v) The potential for natural hazards to impact on the operation of the hazardous facility; and</li> <li>(vi) The potential for cumulative adverse effects of hazardous substances.</li> </ul> </li> <li>(b) Alternative locations: <ul style="list-style-type: none"> <li>(i) An assessment of alternative locations, having particular regard to locations both within the site and outside the site;</li> </ul> </li> <li>(c) Records for existing activity: <ul style="list-style-type: none"> <li>(i) The record of compliance and acceptable risk management of any existing activity where expansion of an existing activity is proposed.</li> </ul> </li> </ul>	

*Note: Land use activities continue on the next page.*

Part 2: District-wide matters / Hazards and risks / HAZS – Hazardous substances

<b>HAZS-R3</b>	Significant hazard facility
<ul style="list-style-type: none"> <li>• LLRZ – Large lot residential zone;</li> <li>• GRZ – General residential zone;</li> <li>• MRZ1 – Medium density residential zone 1;</li> <li>• MRZ2 – Medium density residential zone 2;</li> <li>• RLZ – Rural lifestyle zone;</li> <li>• SETZ – Settlement zone;</li> <li>or</li> <li>• RPZ – Rangitahi Peninsula zone</li> </ul>	<b>(1) Activity status: NC</b>
<b>HAZS-R4</b>	Any new storage or use of hazardous substances with explosive or flammable intrinsic properties within 12m of the centre line of a National Grid Transmission Line
All zones	<b>(1) Activity status: NC</b>

## NH – Natural hazards and climate change

The relevant area specific zone chapter provisions apply in addition to this chapter.

### Overview

- (1) The NH – Natural hazards and climate change chapter identifies risks associated with natural hazards and manages land use in areas subject to risk from natural hazards. It identifies areas where certain types of new development will be avoided because of the natural hazards present, but also recognises that there is existing development, including infrastructure, already located on land subject to natural hazards. These areas will require management through mitigation and adaptation to ensure that the risk of damage to property, or injury or loss of lives is not increased.
- (2) This chapter sets out a two-tiered approach where natural hazard risk from subdivision, use and development is to be avoided within the following identified high risk natural hazard areas:
  - (a) High Risk Flood Area;
  - (b) High Risk Coastal Inundation Area; and
  - (c) High Risk Coastal Erosion Area.
- (3) Outside of these areas, subdivision, use and development is provided for where natural hazard risk can be adequately avoided, remedied or mitigated and the risk is not exacerbated or transferred to adjoining sites.
- (4) The following natural hazards areas have been identified and mapped in the District Plan:

Overlay	Description
<b>Flood hazards</b>	
High flood risk area	Identifies areas within the floodplain where the depth of flood water in a 1% AEP flood event exceeds 1 metre and the speed of flood water exceeds 2 metres per second, or the flood depth multiplied by the flood speed exceeds one.
Flood plain management area	Identifies the 1% Annual Exceedance Probability (AEP) floodplain and has been developed through both 1D and 2D modelling, depending on the level of information available.
Flood ponding area	Identifies areas that experience floodwater ponding in a 1% AEP rainfall event.
Residual risk areas / Defended areas	Identifies areas of land that would be at risk from a natural hazard event if it were not for a structural defence such as a stop bank.
<b>Coastal hazards</b>	
High risk coastal inundation area / High risk coastal erosion area	Identify land where there is significant risk from either coastal inundation or coastal erosion with existing sea level and coastal processes.
Coastal sensitivity area (Erosion) / Coastal sensitivity area (Inundation)	Identify land that is potentially vulnerable to either coastal erosion or coastal inundation over a 100 year period to 2120, assuming a sea level rise of 1.0 metre.

<b>Subsidence risk</b>	
Mine subsidence risk area	Identifies an area where subsidence has occurred at Huntly due to former underground coal mining.

## Objectives

- NH-O1** High risk natural hazards areas.  
In an identified high risk natural hazards area, the risks associated with natural hazards on people, property and infrastructure from subdivision, use and development of land are avoided.
- NH-O2** Areas at risk from natural hazards.  
Subdivision, use and development within areas at risk from natural hazards are managed so that natural hazard risks on people, property and infrastructure are avoided, remedied or mitigated.
- NH-O3** Awareness of natural hazard risks.  
Ensure communities respond effectively and efficiently to natural hazards.
- NH-O4** Climate change.  
Communities are well-prepared to adapt to the effects of climate change.

## Policies

- NH-P1** New development in areas at high risk from natural hazards.
- (I) Avoid subdivision, use and new development in the following high risk natural hazard areas:
- (a) High risk flood area;
  - (b) High risk coastal inundation area;
  - (c) High risk coastal erosion area,
- where there is an increase in risk to people and property.
- NH-P2** Changes to existing land use activities and development in areas at high risk from natural hazards.  
In areas of High risk flood, High risk coastal erosion and High risk coastal inundation, ensure that when changes to existing land use activities and development occur, a range of risk reduction options are assessed, and development that would increase risk to people's safety, well-being and property is avoided.
- NH-P3** Small scale non-habitable structures in areas subject to high risk from natural hazards.  
Enable small scale accessory and farm buildings to be located within areas at high risk from natural hazards, including High risk flood, High risk coastal inundation and High risk coastal erosion, provided the risks to people, property and the environment beyond the site are managed to acceptable levels.

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

- NH-P4 New emergency services and hospitals in areas at significant high risk from natural hazards.
- Avoid locating new emergency service facilities and hospitals in areas which are at high risk from natural hazards, including High risk flood, High risk coastal inundation and High risk coastal erosion, unless, considering engineering and technical constraints or functional and operational requirements, they cannot be reasonably located elsewhere and will not increase the risk to or vulnerability of people or communities.
- NH-P5 New and upgrading of infrastructure and utilities in areas subject to high risk from natural hazards.
- (I) Enable the construction of new infrastructure, utilities and ancillary activities and upgrading of existing infrastructure and utilities, in areas at high risk from natural hazards, including High risk flood, High risk coastal inundation and High risk coastal erosion areas only where:
- (a) The infrastructure and utilities are technically, functionally or operationally required to locate in areas subject to natural hazards, or it is not reasonably practicable to be located elsewhere; and
  - (b) Any increased risks to people, property and the environment are mitigated to the extent practicable; and
  - (c) The infrastructure and utilities are designed, maintained and managed, including provision of hazard mitigation works where appropriate, to function to the extent practicable during and after natural hazard events.
- NH-P6 Existing infrastructure and utilities in all areas subject to natural hazards.
- Provide for the operation, maintenance and minor upgrading of existing infrastructure and utilities in all areas subject to natural hazards.
- NH-P7 Managing natural hazard risk generally.
- (I) Outside of high risk natural hazard areas, provide for subdivision, use and development where:
- (a) Natural hazard risk has been appropriately identified and assessed;
  - (b) The risk can be adequately avoided, remedied or mitigated;
  - (c) The risk does not transfer to adjoining sites; and
  - (d) The risk is not exacerbated.
- NH-P8 Protection from risks of coastal hazards.
- Recognise the importance of natural features and buffers, and soft hazard protection works, and prefer them wherever practicable over hard protection structures, where new hazard mitigation measures and/or works are required to protect people, property infrastructure and the environment from the risks of coastal hazards.
- NH-P9 Limitations on hard protection works for coastal hazard mitigation.
- (I) Ensure that where hard protection structures and works are proposed to protect existing development on public or privately-owned land from coastal hazards that the following is achieved:

## Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

- (a) The structures have primarily a public and/or environmental benefit when located on public land;
  - (b) The structures are effective considering a range of coastal hazard events including the effects of climate change and the activities or development they are designed to protect;
  - (c) The economic, social and environmental benefits outweigh costs;
  - (d) Risk to people, property, infrastructure, the natural environment, historic heritage or Sites and Areas of Significance to Maaori is not transferred or increased;
  - (e) Structures are located as far landward as practicable; and
  - (f) Public access both to and along the coastal area and to the coastal marine area are provided for where the structure is located on public land
- (2) Ensure that when new hard protection structures are to be located in an area where an adaptive management strategy has been prepared to manage coastal hazards, they are consistent with that strategy.
- (3) Where adaptive management strategies have been prepared, plan change or resource consent processes should have regard to these strategies.

NH-PI0 Natural features and buffers providing natural hazard protection.

- (1) Protect, maintain and, where appropriate, enhance the integrity of natural features and buffers which provide a natural defence against the effects of natural hazards and sea level rise, including natural ponding areas, coastal dunes, intertidal areas, wetlands, waterbody margins, riparian/coastal vegetation and floodways.
- (2) Enable natural systems to adapt and respond to natural coastal processes including the effects of climate change.

NH-PI1 Areas defended by stopbanks adjacent to the Waikato River.

- (1) Control subdivision, use and development in areas identified as Defended Areas adjacent to the Waikato River by:
  - (a) Assessing the potential risk of overtopping or structural failure of the stopbanks, and overwhelming of associated flood protection structures, before subdivision, use and development occurs; and
  - (b) Requiring that consideration be given to appropriate mitigation to reduce any residual risk identified to acceptable levels; and
  - (c) Ensuring that any residual risk is not transferred to neighbouring sites; and
  - (d) Recognising the functional needs and operational needs of the National Grid.
- (2) Specify minimum setbacks for buildings and earthworks from stopbanks to:
  - (a) Protect the structural integrity of the stopbanks; and
  - (b) Provide a buffer to reduce the potential risk to life and damage to property from deep and fast-flowing flood waters in the event of a breach.

- NH-P12 New development that creates demand for new protection structures and works.  
Avoid locating new subdivision, use and development in High risk flood, High risk coastal inundation and High risk coastal erosion areas where a demand or need for new structural protection works will be required to reduce the risk from natural hazards to acceptable levels.
- NH-P13 Reduce potential for flood damage to buildings located on the floodplains and flood ponding areas.
- (I) Reduce the potential for flood damage to buildings located on floodplains and flood ponding areas by ensuring that the minimum floor level of building development is above the design flood levels/ponding levels in a 1% AEP flood event, plus an allowance for freeboard, unless:
- (a) The building is of a type that is not likely to suffer material damage during a flood; or
  - (b) The building is a small-scale addition to an existing building; or
  - (c) The risk from flooding is otherwise avoided, remedied or mitigated.
- NH-P14 Control filling of land within the 1% AEP floodplain and flood ponding areas.  
Control filling of land within the 1% AEP floodplain and flood ponding areas to ensure that the potential adverse effects on flood storage capacity, overland flows, run-off volumes on surrounding properties or infrastructure, are avoided or mitigated.
- NH-P15 Managing flood hazards through integrated catchment management.
- (I) Manage flood hazards by requiring new subdivision and development within floodplains, flood ponding areas and overland flow paths to adopt integrated catchment plan-based management methods which:
- (a) Maintain the function of natural floodplains, wetlands and ponding areas including flood storage capacity; and
  - (b) Retain the function and capacity of overland flow paths to convey stormwater run-off; and
  - (c) Do not transfer or increase risk elsewhere within the catchment; and
  - (d) Promote best practice stormwater management with reference to the Waikato Stormwater Management Guideline and the Regional Infrastructure Technical Specifications (RITS); and
  - (e) Minimise impervious surfaces.
- NH-P16 Development in the coastal sensitivity areas.
- (I) In coastal sensitive areas, control subdivision, use and development by ensuring that the subdivision, use and development is:
- (a) Supported by a detailed site specific risk assessment, which includes measures to address the effects of climate change; and
  - (b) Designed, constructed and located to minimise the level or risk to people, property and the environment.



Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

- NH-P17      Setbacks from the coast.
- Avoid increasing the risk from coastal hazards by requiring new built development to be set back from the coastal edge, unless there is a functional or operational need for facilities to be located at or near the coast.
- NH-P18      Residential development and subdivision potentially subject to fire risk.
- (1)          In areas assessed or identified as being potentially subject to elevated fire risk, ensure that an appropriate design and layout, including a buffer area or setback, is provided around for new residential subdivision and development, and the following matters are considered:
- (a)          Access for emergency service vehicles;
  - (b)          Provision of and access to emergency firefighting water supply;
  - (c)          Separation and management of vegetation (with regard to slope, aspect, management regimes and use of less flammable vegetation); and
  - (d)          The design and materials of any buildings.
- NH-P19      Development on land subject to instability or subsidence.
- Avoid locating new subdivision, use and development, including rezoning, on land assessed as being subject to, or likely to be subject to, instability or subsidence, unless appropriate mitigation is provided and the activity does not increase the risk to people, property or infrastructure.
- NH-P20      Development of land in the Mine subsidence risk area
- (1)          On land identified within the Mine subsidence risk area, ensure that:
- (a)          An assessment by an appropriately qualified engineer occurs before subdivision, use or development takes place to confirm that the land is suitable for development; and
  - (b)          Buildings are designed and constructed, and uses appropriate materials, to effectively minimise the risk of damage to the buildings from ground subsidence.
- NH-P21      Stormwater management in areas subject to risk of land instability or subsidence.
- (1)          Avoid discharge of stormwater directly to ground on land that is potentially at risk of land instability or subsidence unless:
- (a)          An assessment has been undertaken by an appropriately qualified geotechnical specialist, indicating that the site is suitable for the proposed discharges; and
  - (b)          Any adverse effects on the site and receiving environment can be appropriately mitigated.
- NH-P22      Liquefaction susceptible land risk assessment.
- (1)          On land assessed as potentially susceptible to liquefaction, ensure that:
- (a)          An assessment by a geotechnical specialist occurs before new subdivision, use or development takes place; and

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

- (b) The level of assessment reflects the type and scale of the subdivision, use or development and the overall vulnerability of the activity to the effects of liquefaction; and
- (c) The assessment confirms that the land is suitable for the proposed development.

NH-P23 Control activities on land susceptible to damage from liquefaction

Control subdivision, use and development on land assessed as being susceptible to liquefaction induced ground damage, to ensure that appropriate mitigation is provided so that the level of risk to people, property, infrastructure.

NH-P24 Natural hazard risk information.

- (I) Enable people to be informed and have access to information on the natural hazards affecting their properties and surrounding area, including through:
  - (a) Provision of Land Information Memoranda;
  - (b) Natural hazard technical information, including the projected effects of climate change, risk registers and mapping on the Council's website, the Waikato Regional Council Hazards Portal, this district plan and accompanying planning maps;
  - (c) Education, provision of information and community engagement; and
  - (d) Alignment with the work of other agencies including iwi and the Waikato Regional Council.

NH-P25 Awareness of Community Response Plans.

Improve response to and recovery from natural hazard events by encouraging community awareness and use of information and methods contained in Community Response Plans.

NH-P26 Effects of climate change on new subdivision and development.

- (I) Ensure that adequate allowances are made for the projected effects of climate change in the design and location of new subdivision and development including new urban zoning throughout the District, including undertaking assessments where relevant that provide for:
  - (a) The projected increase in rainfall intensity, as determined by national guidance, assuming a temperature increase of not less than 2.3°C by 2120;
  - (b) The projected increase in sea level, where relevant, as determined by national guidance and the best available information, but being not less than 1m by 2120;
  - (c) In respect to new urban zoning, stress testing under the RCP 8.5 scenario for rainfall<sup>1</sup> and RCP 8.5H+ for sea level rise<sup>2</sup>;

---

<sup>1</sup> Stress testing under the RCP 8.5 scenario for rainfall, see Ministry for the Environment, 2018: Climate Change Projections for New Zealand. September 2018. Publication No. MFE 1385.

<sup>2</sup> Stress testing under the RCP 8.5H+ scenario for sea level rise, see Ministry for the Environment, 2017: Coastal Hazards and Climate Change – Guidance for Local Government. December 2017. Publication No. ME 1341.

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

- (d) In respect to the coastal environment, increases in storm surge, waves and wind; and
- (e) The ability for natural systems to respond and adapt to the projected changes included in (a) to (d) above.

NH-P27 Future land use planning and climate change.

- (1) Increase the ability of the community to adapt to the effects of climate change when undertaking future land use planning by:
  - (a) Ensuring the potential environmental and social costs of climate change, including effects on indigenous biodiversity (inland migration), historic heritage, Sites and areas of Significance to Maaori, mahinga kai, public health and safety, public access to the coast and waterway margins, and the built environment are addressed;
  - (b) Encouraging the incorporation of sustainable design measures within new subdivision, land use and development, including:
    - (i) Low impact, stormwater management, urban design and green infrastructure;
    - (ii) Of relocatable buildings and structures in areas potentially at risk due to sea level rise or increased flood levels;
    - (iii) Efficient water storage;
    - (iv) Provision of renewable energy generation; and
    - (v) Transferring to activities with lower greenhouse gas emissions.
  - (c) Providing ongoing monitoring of changes to the environment due to climate change; and
  - (d) Facilitating community discussion on adaptive pathways to manage the risks associated with climate change and incorporating them, where appropriate, into the district plan through plan changes.

NH-P28 Precautionary approach for dealing with uncertainty.

In areas throughout the district likely to be affected by climate change over the next 100 years, adopt a precautionary approach towards new subdivision, use and development which may have potentially significant or irreversible adverse effects, but for which there is incomplete or uncertain information.

NH-P29 Provide sufficient setbacks for new development.

- (1) Protect people, property and the environment from the projected adverse effects of climate change, including sea level rise, by providing sufficient setbacks from water bodies and the coast when assessing new development.
- (2) Ensure that, in establishing development setbacks for new development, adequate consideration is given to:
  - (a) The protection of natural ecosystems, including opportunities for the inland migration of coastal habitats;
  - (b) The vulnerability of the community;

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

- (c) The maintenance and enhancement of public access to the coast and public open space;
- (d) The requirements of infrastructure; and
- (e) Natural hazard mitigation provision, including the protection of natural defences.

NH-P30 Assess the impact of climate change on the level of natural hazard risks.

- (1) For all new subdivision, use and development requiring rezoning or a resource consent, ensure that account is taken of the projected effects of climate change over the next 100 years when assessing any identified risks from natural hazards, and their effects on people, property, infrastructure and the environment.
- (2) Ensure that, when assessing the effects of climate change on the level of natural hazard risk in accordance with Policy NH-P30(1) above, the allowances in Policy NH-26(1)(a)-(d) are applied.
- (3) Where the assessment required by Policy NH-P30(1) indicates that natural hazards are likely to be exacerbated by climate change, ensure that subdivision and development are designed and located so that any increased and cumulative risk from natural hazards is managed to acceptable levels and any intolerable risks are avoided or reduced to tolerable or acceptable levels.

## Rules

- (1) The rules in this chapter apply alongside the National Environmental Standards for Electricity Transmission 2010 (NESETA).
- (2) The rules in this chapter do not apply to:
  - (a) Any activity which is a regulated activity under the National Environmental Standards for Telecommunication Facilities 2016 (NESTF);
  - (b) Plantation forestry activities regulated under the National Environmental Standards for Plantation Forestry (NESPF).

### *Flood plain management area and Flood ponding area*

<b>NH-RI</b>	Construction of a new building, or reconstruction of or an addition to an existing building, unless specified in Rules NH-R2 – NH-R6	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) The minimum floor level is at least 0.5m above the 1% AEP flood level; and</li> <li>(b) Compliance with Standard NH-RI(1)(a) shall be demonstrated by a suitably qualified engineer with experience in hydrology.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Assessment of risk from the 1% AEP flood event;</li> <li>(b) Alternative locations within the site outside of the 1% AEP floodplain or flood ponding area;</li> <li>(c) The type of building development proposed and whether it is likely to suffer material damage during a flood;</li> </ul>

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

		<p>(d) Ability to manage risk through building materials, structural or design work, engineering solutions or other appropriate measures; and</p> <p>(e) Other mitigation measures to reduce the potential for flood damage to buildings.</p>
<b>NH-R2</b>	Additions to an existing building that does not increase the ground floor area of the building by more than 15m <sup>2</sup>	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R3</b>	Standalone garage with a gross floor area not exceeding 40m <sup>2</sup>	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R4</b>	Construction of an accessory building without a floor	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R5</b>	Construction of a farm building without a floor	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R6</b>	Construction, replacement, repair, maintenance, minor upgrading or upgrading of utilities	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R7</b>	Earthworks associated with construction, replacement, repair, maintenance, minor upgrading or upgrading of utilities, including the formation and maintenance of access tracks.	

Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R8</b>	Earthworks to create a building platform for residential purposes	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <p>(a) Filling height is only to the extent necessary to achieve compliance with Rule NH-R1(1)(a).</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Timing, location and scale of earthworks;</p> <p>(b) Adverse effects on:</p> <p>(i) Existing overland flow paths and surface drainage patterns;</p> <p>(ii) Flood storage capacity;</p> <p>(iii) Runoff volumes;</p> <p>(iv) Adjoining properties, including the transfer of risk;</p> <p>(v) Infrastructure and flood protection works;</p> <p>(vi) Consideration of soil types and potential for erosion; and</p> <p>(c) Mitigation including compensatory storage, or other flood management measures proposed.</p>
<b>NH-R9</b>	Earthworks not provided for under Rules NH-R7 or NH-R8	
Flood plain management area and Flood ponding area across all zones	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <p>(a) In the GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone and RLZ – Rural lifestyle zone, a maximum volume of filling above natural ground level of 10m<sup>3</sup> per site, and a maximum cumulative volume of filling and excavation of 20m<sup>3</sup>; or</p> <p>(b) In the GRUZ – General rural zone – a maximum volume of filling above natural ground level of 100m<sup>3</sup> per site, and a</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Timing, location and scale of earthworks;</p> <p>(b) Adverse effects on:</p> <p>(i) Existing overland flow paths and surface drainage patterns;</p> <p>(ii) Flood storage capacity;</p> <p>(iii) Runoff volumes;</p> <p>(iv) Adjoining properties, including the transfer of risk;</p> <p>(v) Infrastructure and flood protection works;</p>

	<p>maximum cumulative volume of filling and excavation of 200m<sup>3</sup> per site; or</p> <p>(c) All other zones – a maximum volume of filling above natural ground level of 20m<sup>3</sup> per site, and a maximum cumulative volume of filling and excavation of 50m<sup>3</sup> per site; and</p> <p>(d) Height and depth of earthworks in all zones:</p> <p>(i) A maximum height of 0.2m of filling above natural ground level; and</p> <p>(ii) a maximum depth of excavation of 0.5m below natural ground level.</p> <p>Advice note: where a site is located partly within the flood plain management area or flood ponding area this rule only applies to that part of the site within the flood plain management area or flood ponding area.</p>	<p>(vi) Consideration of soil types and potential for erosion; and</p> <p>(c) Mitigation including compensatory storage, or other flood management measures proposed.</p>
<b>NH-R10</b>	Subdivision to create one or more additional vacant lot(s) other than a utility allotment, access allotment or subdivision to create a reserve allotment.	
Flood plain management area and Flood ponding area across all zones	<b>(1) Activity status: DIS</b>	

*High risk flood area*

<b>NH-R11</b>	Repair, maintenance or minor upgrading of existing utilities	
High risk flood area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R12</b>	Construction, replacement or upgrading of telecommunication lines, poles, cabinets and masts/poles supporting antennas	
High risk flood area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R13</b>	Construction, replacement or upgrading of electricity lines, poles, cabinets, and supporting structures	
High risk flood area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b> Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

<b>NH-R14</b>	Construction of an accessory building without a floor;	
High risk flood area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R15</b>	Construction of a farm building without a floor.	
High risk flood area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R16</b>	New utilities not provided for in Rules NH-R12 or NH-R13	
High risk flood area across all zones	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) Functional and operational requirements to be located in the High risk flood area;</li> <li>(b) The adverse effects on people and property from establishing or upgrading the utility in the High risk flood area;</li> <li>(c) The potential for the development to transfer/increase flood risk to neighbouring properties;</li> <li>(d) Consideration of alternative locations;</li> <li>(e) Consideration of the projected effects of climate change;</li> <li>(f) Any mitigation measures to reduce the risk to people's safety, well-being and property.</li> </ul>	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R17</b>	Upgrading of existing utilities not provided for in Rule NH-R11	
High risk flood area across all zones	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) Functional and operational requirements to be located in the High risk flood area;</li> <li>(b) The adverse effects on people and property from establishing or upgrading the utility in the High risk flood area;</li> <li>(c) The potential for the development to</li> </ul>	<b>(2) Activity status where compliance not achieved: n/a</b>



Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

	<p>transfer/increase flood risk to neighbouring properties;</p> <p>(d) Consideration of alternative locations;</p> <p>(e) Consideration of the projected effects of climate change;</p> <p>(f) Any mitigation measures to reduce the risk to people's safety, well-being and property.</p>	
<b>NH-R18</b>	One addition to a lawfully established building existing at 17 January 2022, where the addition does not increase the ground floor area of the existing building by more than 15m <sup>2</sup> , unless provided for in Rules NH-R17 or NH-R18	
High risk flood area across all zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The ability to manage flood risk through appropriate building materials, structural or design work or other engineering solutions;</p> <p>(b) The setting of an appropriate floor level for the addition, taking into consideration the location of the addition and the floor level of the existing building;</p> <p>(c) Any mitigation measures to reduce the risk to people's safety, well-being and property.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R19</b>	<p>Subdivision that creates one or more additional vacant lot(s) where:</p> <p>(a) The additional lot(s) are located entirely outside the High risk flood area; or</p> <p>(b) The additional lot(s) are partially within the High risk flood area and each additional lot(s) contains an area capable of containing a complying building platform entirely outside the High risk flood area.</p> <p>This rule does not apply to subdivision for a utility allotment, access allotment or subdivision to create a reserve allotment.</p>	
High risk flood area across all zones	<b>(1) Activity status: DIS</b>	
<b>NH-R20</b>	Construction of a new building or additions to an existing building, not provided for in Rules NH-R11 – NH-R18	
High risk flood area across all zones	<b>(1) Activity status: NC</b>	
<b>NH-R21</b>	Subdivision that does not comply with Rule NH-R19	

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

	This rule does not apply to subdivision for a utility allotment, access allotment or subdivision to create a reserve allotment.
High risk flood area across all zones	<b>(1) Activity status: NC</b>
<b>NH-R22</b>	Emergency service facilities and hospitals
High risk flood area across all zones	<b>(1) Activity status: NC</b>

*Defended area (Residual risk)*

<b>NH-R23</b>	Activities are permitted activities within the Defended area identified on the planning maps, unless specified in Rules NH-R24 to NH-R26 below, or as otherwise specified in the relevant zone chapter or the Part 2 – District-wide matters chapters	
Defended area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R24</b>	Subdivision that creates one or more additional vacant lot(s).  This rule does not apply to subdivision for a utility allotment, an access allotment or subdivision to create a reserve allotment.	
Defended area across all zones	<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b> Nil.  <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) The actual level of service provided by the structural defence and associated flood protection works, including any change in the level of service anticipated due to climate change and sea level rise;</li> <li>(b) The impact of any planned improvements, maintenance or upgrading on the residual risk;</li> <li>(c) The effect of groundwater levels and variability in ground conditions on stop-bank security at and adjacent to the site to be subdivided;</li> <li>(d) The likely depth and duration of flooding as a result of a breach or overtopping event or flood ponding;</li> <li>(e) The location of the subdivision, including services such as wastewater, water supply and roading/access (including escape</li> </ul>	<b>(2) Activity status where compliance not achieved: n/a</b>

	<p>routes), in relation to potential breakout points (failure zone);</p> <p>(f) The adverse effects on:</p> <p>(i) People and property,</p> <p>(ii) Historic heritage and Sites and Areas of Significance to Maaori, and</p> <p>(iii) Overall vulnerability from potential failure or overwhelming of the structural defences and associated flood protection works relevant to the proposed new lot(s);</p> <p>(g) Potential for the development to transfer/increase flood risk/residual risk to neighbouring properties;</p> <p>(h) Any additional mitigation measures proposed or site features which reduce residual risk (e.g., natural high ground; evacuation plan).</p>	
<b>NH-R25</b>	Construction of a new building, or reconstruction of, or new accessory building, located within 50m of the toe of a stop-bank where the stop-bank is under the responsibility of the Council, the Waikato Regional Council or the Crown.	
Defended area across all zones	<b>(1) Activity status: DIS</b>	
<b>NH-R26</b>	Earthworks located within 50m of the toe of a stop-bank where the stop-bank is under the responsibility of the Council, the Waikato Regional Council or the Crown.	
	This rule does not apply to earthworks associated with utilities where the written approval of the authority managing the stop-bank has been obtained.	
Defended area across all zones	<b>(1) Activity status: DIS</b>	

*Coastal sensitivity areas*

<b>NH-R27</b>	Additions to an existing lawfully established building	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) The gross floor area of all additions to the building from 17 January 2022 do not exceed a total of 15m<sup>2</sup>.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The ability to manage coastal hazard risk through appropriate building materials, structural or design work, engineering solutions, and other appropriate mitigation measures, including</p>

		<p>the ability to relocate the building;</p> <p>(b) The setting of minimum floor levels where appropriate;</p> <p>(c) The application of mitigation through natural features and buffers where appropriate;</p> <p>(d) The ability to impose time limits or triggers to determine when the building and services to be removed or relocated;</p> <p>(e) The degree to which coastal hazard risk, including the effects of climate change over a period to 2120, has been assessed in a site specific coastal hazard risk assessment;</p> <p>(f) Suitability of the site for the proposed use, including the provision for servicing such as access, wastewater, stormwater, and water supply;</p> <p>(g) Adverse effects to people and property and overall vulnerability from the establishment of the new building or additions to an existing building</p> <p>(h) Any mitigation measures to reduce risk; and</p> <p>(i) Whether there is any suitable alternative location for the activity to locate within the site.</p>
<b>NH-R28</b>	Construction of an accessory building without a floor	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R29</b>	Construction of a farm building without a floor	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R30</b>	Construction, upgrading, minor upgrading, replacement, repair or maintenance of utilities excluding hard protection structures.	

Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R31</b>	Maintenance or repair of an existing lawfully established hard protection structure	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R32</b>	Construction of a new building, or reconstruction of, or additions to existing buildings in the RPZ – Rangitahi Peninsula zone and Coastal sensitivity area (Erosion) on a certificate of title which was created by subdivision consent granted between 28 September 2015 and 17 January 2022	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Compliance with the requirements of any consent notice for the certificate of title pursuant to section 221 of the Resource Management Act 1991 containing specific design or location requirements for buildings.	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) The ability to manage coastal hazard risk through appropriate building materials, structural or design work, engineering solutions, and other appropriate mitigation measures, including the ability to relocate the building; (b) The setting of minimum floor levels where appropriate; (c) The application of mitigation through natural features and buffers where appropriate; (d) The ability to impose time limits or triggers to determine when the building and services to be removed or relocated; (e) The degree to which coastal hazard risk, including the effects of climate change over a period to 2120, has been assessed in a site specific coastal hazard risk assessment; (f) Suitability of the site for the proposed use, including the provision for servicing such as

		<p>access, wastewater, stormwater, and water supply;</p> <p>(g) Adverse effects to people and property and overall vulnerability from the establishment of the new building or additions to an existing building</p> <p>(h) Any mitigation measures to reduce risk; and</p> <p>(i) Whether there is any suitable alternative location for the activity to locate within the site.</p>
<b>NH-R33</b>	Construction of a new building or additions to an existing building not provided for in Rules NH-R27- NH-R30 and NH-R32	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The ability to manage coastal hazard risk through appropriate building materials, structural or design work, engineering solutions, and other appropriate mitigation measures, including the ability to relocate the building;</p> <p>(b) The setting of minimum floor levels where appropriate;</p> <p>(c) The application of mitigation through natural features and buffers where appropriate;</p> <p>(d) The ability to impose time limits or triggers to determine when the building and services to be removed or relocated;</p> <p>(e) The degree to which coastal hazard risk, including the effects of climate change over a period to 2120, has been assessed in a site specific coastal hazard risk assessment;</p> <p>(f) Suitability of the site for the proposed use, including the provision for servicing such as access, wastewater, stormwater, and water supply;</p> <p>(g) Adverse effects to people and property and overall vulnerability from the</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

	<p>establishment of the new building or additions to an existing building</p> <p>(h) Any mitigation measures to reduce risk; and</p> <p>(i) Whether there is any suitable alternative location for the activity to locate within the site.</p>	
<p><b>NH-R34</b></p>	<p>Any subdivision to create any additional vacant lots where the additional vacant lot(s) are located partially or entirely within the Coastal sensitivity area (Inundation), Coastal sensitivity area (Erosion).</p> <p>This rule does not apply to subdivision for a utility allotment, access allotment or subdivision creating a reserve allotment</p>	
<p>Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones</p>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Whether the vacant lot(s) are capable of containing a complying building platform entirely outside the Coastal sensitivity area (Inundation), or the Coastal sensitivity area (Erosion); or</p> <p>(b) Where the vacant lot(s) are not capable of containing a complying building platform entirely outside of the Coastal sensitivity area (Inundation), or the Coastal sensitivity area (Erosion):</p> <p>(i) The degree to which coastal hazard risk, including the effects of climate change over a period to 2120, has been assessed in a site specific coastal hazard risk assessment;</p> <p>(ii) Suitability of the vacant lot for the likely future uses, including the provision for servicing such as access, wastewater, stormwater, and water supply;</p> <p>(iii) The degree to which alternative subdivision layout(s) have been investigated to avoid or mitigate coastal hazards;</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

	<p>(iv) Adverse effects to people, property and the environment and overall vulnerability from the likely future uses, including any mitigation measures to reduce risk; and</p> <p>(v) The setting of minimum floor levels in areas subject to inundation.</p>	
<b>NH-R35</b>	Construction of a new hard protection structure, or any extension to, or upgrade or replacement of an existing hard protection structure	
Coastal sensitivity area (Erosion) and the Coastal sensitivity area (Inundation) across all zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Whether structures have primarily a public and/or environmental benefit when located on public land;</li> <li>(b) The extent to which the structure is effective, considering a range of coastal hazard events including the effects of climate change and the activities or development they are designed to protect;</li> <li>(c) The extent to which economic, social and environmental benefits outweigh costs;</li> <li>(d) Whether risk to people, property, infrastructure, environment, historic heritage or sites and areas of significance to Maaori is not transferred or increased;</li> <li>(e) The extent to which structures are located as far landward as practicable;</li> <li>(f) Whether public access both to and along the coastal area and to the coastal marine area are provided for where the structure is located on public land; and</li> <li>(g) Whether an adaptive management strategy has been prepared to manage coastal hazards, and whether the</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>



Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

	structure is consistent with that strategy.	
--	---	--

*High risk coastal erosion area*

<b>NH-R36</b>	Construction of an accessory building without a floor	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The gross floor area of the building does not exceed 40m <sup>2</sup> .	<b>(2) Activity status where compliance not achieved: NC</b>
<b>NH-R37</b>	Construction of a farm building without a floor	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The gross floor area of the building does not exceed 40m <sup>2</sup> .	<b>(2) Activity status where compliance not achieved: NC</b>
<b>NH-R38</b>	Repair, maintenance or minor upgrading of existing utilities excluding hard protection structures	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R39</b>	Construction, operation, replacement or upgrading of telecommunications lines, poles, cabinets and masts/poles supporting antennas	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R40</b>	New electricity lines, poles, cabinets and masts/ poles supporting antennas	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R41</b>	Maintenance or repair of an existing lawfully established hard protection structure.	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R42</b>	Earthworks for an activity listed in Rules NH-R36 – NH-R41, including the maintenance and repair of access tracks	
High risk coastal erosion area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The maximum volume of filling does not exceed 10m <sup>3</sup> per site; and	<b>(2) Activity status where compliance not achieved: DIS</b>

	(b) The maximum depth of any excavation or filling does not exceed 0.5m above or below ground level.	
<b>NH-R43</b>	Construction of a new hard protection structure, or any extension to, or upgrade or replacement of an existing hard protection structure.	
High risk coastal erosion area across all zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Whether structures have primarily a public and/or environmental benefit when located on public land;</li> <li>(b) The extent to which the structure is effective, considering a range of coastal hazard events including the effects of climate change and the activities or development they are designed to protect;</li> <li>(c) The extent to which economic, social and environmental benefits outweigh costs;</li> <li>(d) Whether risk to people, property, infrastructure, environment, historic heritage or sites and areas of significance to Maaori is not transferred or increased;</li> <li>(e) The extent to which structures are located as far landward as practicable;</li> <li>(f) Whether public access both to and along the coastal area and to the coastal marine area are provided for where the structure is located on public land; and</li> <li>(g) Whether an adaptive management strategy has been prepared to manage coastal hazards, and whether the structure is consistent with that strategy.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R44</b>	Earthworks not provided for in Rule NH-42	
High risk coastal erosion area	<b>Activity status: DIS</b>	

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

across all zones	
<b>NH-R45</b>	Relocation of an existing building within the same site where the building is relocated landward of its existing position
High risk coastal erosion area across all zones	<b>Activity status: DIS</b>
<b>NH-R46</b>	Replacement of an existing building within the same site where: <ul style="list-style-type: none"> <li>(a) The replacement building is located landward of the existing building that it replaces;</li> <li>(b) The replacement building is relocatable on a suspended timber floor; and</li> <li>(c) The gross floor area of the replacement building is no larger than the existing building that it replaces</li> </ul>
High risk coastal erosion area across all zones	<b>Activity status: DIS</b>
<b>NH-R47</b>	Construction of new utilities not provided for in Rules NH-R39 and NH-R40
High risk coastal erosion area across all zones	<b>Activity status: DIS</b>
<b>NH-R48</b>	Upgrading of existing utilities not provided for in Rules NH-R38 and NH-R39
High risk coastal erosion area across all zones	<b>Activity status: DIS</b>
<b>NH-R49</b>	Subdivision that creates one or more additional vacant lot(s) where the additional lot(s) are partially within the High risk coastal erosion area and each additional lot(s) contains a net site area capable of containing a complying building platform entirely outside the High risk coastal erosion area.  This rule does not apply to subdivision for a utility allotment, access allotment or subdivision to create a reserve allotment.
High risk coastal erosion area across all zones	<b>Activity status: DIS</b>
<b>NH-R50</b>	Construction of a new building or additions to an existing building, not provided for in Rules NH-R36 – NH-R40, NH-R45 – NH-R48
High risk coastal erosion area across all zones	<b>Activity status: NC</b>

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

<b>NH-R51</b>	Subdivision to create one or more additional lot(s) that does not comply with Rule NH-R49.  This rule does not apply to subdivision for a utility allotment, access allotment or subdivision to create a reserve allotment.
High risk coastal erosion area across all zones	<b>Activity status: NC</b>
<b>NH-R52</b>	Emergency service facilities and hospitals
High risk coastal erosion area across all zones	<b>Activity status: NC</b>

*High risk coastal inundation area*

<b>NH-R53</b>	Construction of an accessory building without a floor	
High risk coastal inundation area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The gross floor area of the building does not exceed 40m <sup>2</sup> .	<b>(2) Activity status where compliance not achieved: NC</b>
<b>NH-R54</b>	Construction of a farm building without a floor	
High risk coastal inundation area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The gross floor area of the building does not exceed 40m <sup>2</sup> .	<b>(2) Activity status where compliance not achieved: NC</b>
<b>NH-R55</b>	Repair, maintenance or minor upgrading of existing utilities excluding hard protection structures	
High risk coastal inundation area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R56</b>	Construction, operation, replacement or upgrading of telecommunications lines, poles, cabinets and masts/poles supporting antennas	
High risk coastal inundation area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R57</b>	New electricity lines, poles, cabinets and masts/ poles supporting antennas	
High risk coastal inundation area across all zones	<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NH-R58</b>	Maintenance or repair of an existing lawfully established hard protection structure.	

High risk coastal inundation area across all zones	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R59</b>	Earthworks for an activity listed in Rules NH-R53 – NH-R57, including the maintenance and repair of access tracks	
High risk coastal inundation area across all zones	<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) The maximum volume of filling does not exceed 10m<sup>3</sup> per site; and</li> <li>(b) The maximum depth of any excavation or filling does not exceed 0.5m above or below ground level.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>NH-R60</b>	Construction of a new hard protection structure, or any extension to, or upgrade or replacement of an existing hard protection structure.	
High risk coastal inundation area across all zones	<p><b>(1) Activity status: RDIS</b>  <b>Activity-specific standards:</b>                  Nil</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Whether structures have primarily a public and/or environmental benefit when located on public land;</li> <li>(b) The extent to which the structure is effective, considering a range of coastal hazard events including the effects of climate change and the activities or development they are designed to protect;</li> <li>(c) The extent to which economic, social and environmental benefits outweigh costs;</li> <li>(d) Whether risk to people, property, infrastructure, environment, historic heritage or sites and areas of significance to Maaori is not transferred or increased;</li> <li>(e) The extent to which structures are located as far landward as practicable;</li> <li>(f) Whether public access both to and along the coastal area and to the coastal marine area are provided for where the</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

Part 2: District-wide matters / Hazards and risks / NH – Natural hazards and climate change

	<p>structure is located on public land; and</p> <p>(g) Whether an adaptive management strategy has been prepared to manage coastal hazards, and whether the structure is consistent with that strategy.</p>	
<b>NH-R61</b>	Earthworks not provided for in Rule NH-59	
High risk coastal inundation area across all zones	<b>Activity status: DIS</b>	
<b>NH-R62</b>	Construction of new utilities not provided for in Rules NH-R56 and NH-R57	
High risk coastal inundation area across all zones	<b>Activity status: DIS</b>	
<b>NH-R63</b>	Upgrading of existing utilities not provided for in Rules NH-R55 and NH-R56	
High risk coastal inundation area across all zones	<b>Activity status: DIS</b>	
<b>NH-R64</b>	<p>Subdivision that creates one or more additional vacant lot(s) where the additional lot(s) are partially within the High risk coastal inundation area and each additional lot(s) contains a net site area capable of containing a complying building platform entirely outside the High risk coastal inundation area.</p> <p>This rule does not apply to subdivision for a utility allotment, access allotment or subdivision to create a reserve allotment.</p>	
High risk coastal inundation area across all zones	<b>Activity status: DIS</b>	
<b>NH-R65</b>	Construction of a new building or additions to an existing building, not provided for in Rules NH-R53 – NH-R57, NH-R62 – NH-R63	
High risk coastal inundation area across all zones	<b>Activity status: DIS</b>	
<b>NH-R66</b>	<p>Subdivision to create one or more additional lot(s) that does not comply with Rule NH-R64</p> <p>This rule does not apply to subdivision for a utility allotment, access allotment or subdivision to create a reserve allotment.</p>	
High risk coastal inundation	<b>Activity status: NC</b>	

area across all zones	
<b>NH-R67</b>	Emergency service facilities and hospitals
High risk coastal inundation area across all zones	<b>Activity status: NC</b>

*Mine subsidence risk area*

<b>NH-R68</b>	Additions to an existing building	
Mine subsidence risk area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Additions do not increase the gross floor area of the building by more than 15m<sup>2</sup>; and</li> <li>(b) Additions do not result in the length of any wall of the building exceeding 20m.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Construction standards and materials;</li> <li>(b) Suitability of the site for development; and</li> <li>(c) The potential effects on health and safety.</li> </ul>
<b>NH-R69</b>	Standalone garage	
Mine subsidence risk area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) The gross floor area of the building does not exceed 55m<sup>2</sup>; and</li> <li>(b) The maximum length of any wall does not exceed 20m.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Construction standards and materials;</li> <li>(b) Suitability of the site for development; and</li> <li>(c) The potential effects on health and safety.</li> </ul>
<b>NH-R70</b>	Construction, replacement, repair, minor upgrading, upgrading or maintenance of utilities and associated earthworks	
Mine subsidence risk area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R71</b>	Earthworks	
Mine subsidence risk area across all zones	<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) The maximum volume of filling does not exceed 20m<sup>3</sup> per site; and</li> <li>(b) The maximum depth of any excavation or filling does not exceed 1m above or below ground level.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Location and scale of earthworks;</li> <li>(b) Geotechnical and geological stability of the site following the completion of earthworks;</li> </ul>

		<p>(c) Risk to people and property from subsidence as a result of earthworks; and</p> <p>(d) Any other mitigation measures to reduce risk.</p>
<b>NH-R72</b>	<p>The construction or alteration of a building that is not provided for under Rule Rules NH-R68 – NH-R71 where a Consent Notice is registered against the Record of Title confirming that a geotechnical assessment has been approved at the time of subdivision and the approved geotechnical report confirms that the ground is suitable for building development and the building development is in accordance with any recommendations of the geotechnical report.</p>	
Mine subsidence risk area across all zones	<p><b>(1) Activity status: CON</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council's control is reserved to the following matters:</b></p> <p>(a) The degree to which the requirements and recommendations of the geotechnical report approved at the time of subdivision have been incorporated in the building design; and</p> <p>(b) Whether confirmation is provided from a suitably experienced and qualified geotechnical engineer that confirms the proposed building development is consistent with the recommendations and requirements of the geotechnical report approved at the time of subdivision.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NH-R73</b>	<p>Construction of a building, or reconstruction of, or accessory building or the reconstruction of or additions to an existing building not provided for in Rules NH-R68 – NH-R70 or NH-R72</p>	
Mine subsidence risk area across all zones	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Construction standards and materials;</p> <p>(b) Suitability of the site for development; and</p> <p>(c) The potential effects on health and safety.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>



<b>NH-R74</b>	Subdivision to create one or more additional vacant lot(s) other than a utility allotment, access allotment or subdivision to create a reserve allotment
Mine subsidence risk area across all zones	<b>Activity status: DIS</b>

*Liquefaction*

<b>NH-R75</b>	Overview of method
All zones	<p>(1) Areas in the District susceptible to liquefaction have not been identified on the planning maps as a natural hazard overlay as is the case with the other natural hazards in this chapter. Where specific land uses have already been identified as restricted discretionary activities in the activity status tables in the relevant zone, liquefaction risk has been added as a matter over which the Council will reserve its discretion, where it is considered relevant for that activity. To satisfy the requirements of sections 104 and 106 of the RMA, identification of appropriate mitigation may be required where the site and proposed development are considered vulnerable to liquefaction based on site-specific characteristics. It is expected that best practice geotechnical and engineering methods will be used to ensure that the site is suitable for the intended use.</p> <p>(2) Where potential liquefaction risk is identified as a matter that the Council restricts its discretion to, the additional matters outlined in Rules NH-R76 and NH-R77 below apply where relevant.</p>
<b>NH-R76</b>	Additional matters of restricted discretion for subdivision to create one or more additional vacant lots – liquefaction risk
All zones	<p>(1) Where potential liquefaction risk is identified as a matter that the Council will restrict its discretion to in a subdivision rule elsewhere in this Plan, and where that proposal involves subdivision to create one or more additional vacant lots, the Council restricts its discretion to the following additional matters (note: these matters will also be relevant to the assessment of a discretionary or non-complying resource consent application where a potential liquefaction hazard has been identified on a site):</p> <p>(a) Geotechnical assessment and/or investigation of any potential liquefaction hazard on the site at a level sufficient to confirm the level of risk and its suitability for the proposed activity (refer to the information requirements in section below);</p> <p>(b) Measures proposed to mitigate the effects of liquefaction hazard if present including:</p> <p>(i) Location, size, layout and design of allotments, structures, and building platforms, including consideration given to alternative siting away from where liquefaction risk is greatest;</p> <p>(ii) Location, timing, scale and nature of earthworks;</p> <p>(iii) Provision for ground strengthening and foundation design;</p> <p>(iv) Provision for resilient services and infrastructure, including wastewater, water supply, roads and access;</p> <p>(v) Setbacks in relation to waterways, waterbodies or any steep change in ground elevation, sloping ground or free face, or alternative geotechnical measures to address any identified potential for lateral spread; and</p>

	(vi) Effects on adjoining properties.
<b>NH-R77</b>	Additional matters of restricted discretion for new land use (e.g., multi-unit development) – liquefaction risk
All zones	<p>(I) Where potential liquefaction risk is identified as a matter that the Council will restrict its discretion to in a rule elsewhere in this Plan for new land use, the Council restricts its discretion to the following additional matters (note: these matters will also be relevant to the assessment of a discretionary or non-complying resource consent application where a potential liquefaction hazard has been identified on a site):</p> <p>(a) Geotechnical assessment and/or investigation of any potential liquefaction hazard on the site at a level sufficient to confirm the level of risk and its suitability for the proposed activity (refer to the information requirements in section below);</p> <p>(b) Measures proposed to mitigate the effects of liquefaction hazard, if present, including:</p> <p>(i) Location, size, layout and design of buildings, structures, car parking areas, access and provision for resilient infrastructure and services, including wastewater, stormwater and water supply;</p> <p>(ii) Location, timing, scale and nature of earthworks;</p> <p>(iii) Provision for ground strengthening and foundation design;</p> <p>(iv) Setbacks in relation to waterways, waterbodies or any steep change in ground elevation, sloping ground (or free face, or alternative geotechnical measures to address any identified potential for lateral spread);</p> <p>(v) Consideration given to ease of repair (including access to repair damaged structures) of liquefaction-induced damage; and</p> <p>(vi) Effects on adjoining properties.</p>

Advice note:

*Effects on archaeological sites, both recorded (identified by the New Zealand Archaeological Association) and unrecorded, are regulated under the Heritage New Zealand Pouhere Taonga Act 2014. Heritage New Zealand Pouhere Taonga must be contacted regarding development and the need to undertake an archaeological assessment to determine the need for an archaeological authority. In the event of an accidental discovery, the Heritage New Zealand Pouhere Taonga Lower Northern Office must be contacted immediately.*

## **Information Requirements for all resource consent applications addressing natural hazards**

### **NH-INFO1 – General**

- (I) The following documents, to the extent relevant to the proposal:
- (a) Geotechnical assessment, including identification and assessment of any potentially liquefaction prone land and land subject to slope instability;
  - (b) An assessment of natural hazard risk, including the type of natural hazards present, such as flooding, slope stability, liquefaction, subsidence and coastal hazards. The assessment shall include the level of risk and any increase in risk as a result of the proposal associated with each hazard. Where applicable, the projected effects of climate change over the period to 2120 must be included;

- (c) Remediation and mitigation measures necessary to make the site and any proposed buildings suitable for the proposed use, such as minimum floor levels, foundation design for relocatability, and appropriate time limits and/or triggers for the removal of any building and onsite wastewater disposal systems.
- (2) Plans identifying:
  - (a) Topographical features within the site and surrounding area; and
  - (b) The location of natural hazards on all or part of the site.
- (3) Consideration of the information contained in the following stormwater catchment management plans, or any approved updated version, where relevant:
  - (a) Ngaruawahia Catchment Management Plan, March 2015;
  - (b) Tamahere Stormwater Catchment Management Plan and Report, 2011
  - (c) Port Waikato Stormwater Catchment Management Plan and Report, 2004;
  - (d) Pokeno Catchment Management Plan, 2010;
  - (e) Te Kauwhata Catchment Management Plan, 2009; or
  - (f) Tuakau Catchment Management Plan, Draft 2014.

### **NH-INFO2 – Liquefaction potential**

- (1) For land use resource consent applications where the additional matters the Council will restrict its discretion to include liquefaction, as per Rule NH-R77, the following information is required:
  - (a) A preliminary geotechnical assessment in sufficient detail to determine:
    - (i) The liquefaction vulnerability category, being either “liquefaction damage is unlikely” or “liquefaction damage is possible”, as shown in Table 4.4 in “Preliminary Document: Planning and engineering guidance for potentially liquefaction prone land – Resource Management Act and Building Act aspects. Pub MfE and MBIE, September 2017”; or
    - (ii) Whether or not the site is susceptible to liquefaction using an alternative accepted method, observation, or desktop study.
  - (b) Where a “liquefaction damage is possible” category has been identified for the site as per NH-INFO2(1)(a)(i) above, or an alternative accepted method, observation or desktop study indicates that the site is susceptible to liquefaction as per NH-INFO2(1)(a)(ii) above, the assessment will be required to determine the liquefaction vulnerability in more detail, and in proportion to the scale and significance of the liquefaction hazard, and must:
    - (i) Identify any areas which require particular ground strengthening or other mitigation measures, and recommendations for such mitigation; and
    - (ii) Identify areas to be excluded from built development, due to liquefaction hazard constraints (which includes lateral spread), or which require geotechnical setbacks; and
    - (iii) Indicate options and recommended locations for the proposed activities and infrastructure recommended by the geotechnical engineer.
  - (c) All geotechnical assessments in respect of liquefaction risk are to be prepared by a suitably qualified and experienced engineer with experience in geotechnical engineering or a Professional Engineering Geologist (IPENZ registered).
- (2) For subdivision consent applications that create one or more additional vacant lots as per Rule NH-R76:
  - (a) An assessment in accordance with NH-INFO2(1)(a) above will be required to be provided.
  - (b) Where a “liquefaction damage is possible” category has been identified for the site as per 15.13.2(1)(a)(i) above, or an alternative accepted method, observation, or desktop study indicates that the site is susceptible to liquefaction as per NH-INFO2(1)(a)(ii) above, the subdivision application will be required to include sufficient information and proposed measures to satisfy that liquefaction risk can be adequately avoided, remedied or mitigated, including the potential effects of lateral spread.

- (c) Subdivision plans shall show, to the extent relevant or appropriate to the scale and significance of the liquefaction hazard identified:
  - (i) Any areas which require particular ground strengthening or other mitigation
  - (ii) Measures, and recommendations for such mitigation; and
  - (iii) Any areas which should be excluded from built development due to geotechnical constraints, or which require geotechnical setbacks; and
  - (iv) Any features of subdivision layout recommended by the geotechnical engineer, for example any recommended locations for proposed activities and other infrastructure as a result of geotechnical constraints.
- (d) All geotechnical reports in respect of liquefaction potential are to be prepared by a suitably qualified and experienced engineer with experience in geotechnical engineering or Professional Engineering Geologist (IPENZ registered).

**NH-INFO3 – RLZ – Rural lifestyle zone in Tamahere**

- (1) Any resource consent in relation to land located in the RLZ – Rural lifestyle zone in Tamahere will be required to include details of ponding of stormwater and overland flow paths as a result of a 1% AEP storm event (with rainfall events adjusted for climate change), as well as mitigation measures taking account of information that the Council holds in respect to the Tamahere stormwater catchment area.

**NH-INFO3 – Defended areas**

- (1) For any Restricted Discretionary Activity land use and subdivision applications within the Defended Area, the following information is required to the extent relevant to the scale of the proposal:
  - (a) A risk assessment, carried out by a suitably-qualified and experienced risk assessment practitioner, which identifies the nature and level of residual risk, and details of appropriate methods to further reduce residual risk, where appropriate.

## SUB – Subdivision

*Explanatory note for the purpose of the IPI and to be removed upon completion of the process:*

Standard text is used for existing provisions contained in the proposed Waikato District Plan.

Green underline text is used for new provisions.

~~Black Strikethrough~~ is used to show the deletion of existing provisions that applied to the MRZ.

Only the subdivision rules pertaining to the MRZ2 – Medium density residential zone 2 and the consequential amendments to MRZ1 – Medium density residential zone 1 are included for the purpose of the IPI.

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Objective

SUB-O1 Subdivision.

Subdivision layout and design promotes the land use outcomes sought for the residential, business, industrial, open space and special purpose zones.

SUB-O2 Subdivision and development in the MTZ – Matangi zone.

Subdivision, layout and design maximises efficient use of the land and minimises any adverse effects.

### Policies

SUB-PI Subdivision location and design.

(I) Ensure subdivision, is located and designed to:

- (a) Be sympathetic to the natural and physical qualities and characteristics of the surrounding environment;
- (b) Establish boundaries that minimises, to the extent practicable, buildings and structures dominating adjoining land or public places, the coast, or fresh waterbodies;
  - (i) Arrange allotments to promote view sharing
  - (ii) Promote safe communities through quality urban design;
  - (iii) Accommodate safe and stable building platforms and vehicle accesses; and
  - (iv) Promote consistent grid layout.

SUB-P2 Residential subdivision.

(I) Promote residential subdivision and development that:

- (a) Integrates staging to ensure multi-modal connectivity;
- (b) Limits the number and length of cul-de-sacs;

Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

- (c) Ensures pedestrian access is consistent with the Crime Prevention through Environmental Design (CPTED) principles;
  - (i) Discourages the creation of rear lots;
  - (ii) Includes adequate lighting levels in publicly accessible spaces;
  - (iii) Reflects local characteristics;
  - (iv) Orientates lots are orientated in a way that:
    - (1) Maximizes solar access; and
    - (2) Addresses the street frontage and public places.
  - (v) Creates lots that can accommodate a variety of density with a mix of usable lot types; and
  - (vi) Designs infrastructure to manage stormwater in a sustainable manner by:
    - (1) Minimising environmental impacts and maintenance costs, and reducing stormwater discharging to existing reticulated networks; and
    - (2) Promoting and maintaining riparian margins.

SUB-P3 Lot sizes.

- (1) Except for residential subdivision within the MRZ2 – Medium density residential zone 2, mMinimum lot size and dimension of lots enable the achievement of the character and density outcomes of each zone; and
- (2) Prevent undersized lots in the SETZ – Settlement zone and LLRZ – Large lot residential zone.
- (3) Within the MRZ2 – Medium density residential zone 2, subdivision enables medium density residential outcomes.

SUB-P4 Servicing requirements.

- (1) Require subdivision and development in all zones except for GRUZ – General rural zone and RLZ – Rural lifestyle zone to be serviced to a level that will provide for the anticipated activities in a structure plan, or otherwise anticipated within the zone, including through the provision of:
  - (a) Reserves for community, active and passive recreation;
  - (b) Pedestrian and cycle connections;
  - (c) Roads;
  - (d) Public transport infrastructure, e.g. bus stops;
  - (e) Telecommunications;
  - (f) Electricity;
  - (g) Stormwater collection, treatment and disposal;
  - (h) Wastewater treatment and reticulation, water provision for domestic and fire fighting purposes; and

Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

- (i) Connections to identified adjacent future growth areas.
- SUB-P5 Co-ordination between servicing and development and subdivision
- (1) Ensure development and subdivision:
    - (a) Is located in areas where infrastructure capacity has been planned and able to be funded;
    - (b) Where located in areas subject to an approved structure plan, provides sufficient infrastructure capacity to meet the demand identified in the structure plan;
    - (c) Achieves the lot yield anticipated in an approved structure plan; and
    - (d) Includes infrastructure provision for both the strategic infrastructure network and local infrastructure connections.
- SUB-P6 Achieving sufficient development density to support the provision of infrastructure services in areas without a structure plan.
- In areas where there is no structure plan, ensure that the land is developed efficiently to support the provision of infrastructure services.
- SUB-P7 Staging of subdivision.
- Require any staging of subdivision to be undertaken in a manner that promotes efficient development and integration of infrastructure and community facilities.
- SUB-P8 Connected neighbourhoods.
- (1) Design subdivision to support the creation of a liveable, walkable and connected neighbourhood by having:
    - (a) A road network that achieves all of the following:
      - (i) Easy and safe to use for pedestrians and cyclists;
      - (ii) Accessible for emergency and other services;
    - (b) Connected with a variety of routes within the immediate neighbourhood and between adjacent land areas; and
    - (c) Connected to public transport, shops, schools, employment, open spaces and other amenities; and
  - (2) Vehicle crossings and associated access are designed and located to provide for safe and efficient movement to and from sites and minimising potential conflict between vehicles, pedestrians, and cyclists on the adjacent road network.
- SUB-P9 Recreation and access.
- (1) Provide for the recreation and amenity needs of residents by:
    - (a) Encouraging open spaces which are prominent and accessible by pedestrians;
    - (b) Requiring the location, number and size of open spaces to be in proportion to the future density of the neighbourhood and provide for a range of different activities and users; and
    - (c) Enabling pedestrian and/or cycle linkages.

Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

- SUB-PI0 Reverse sensitivity
- (1) Other than in the GIZ – General industrial zone and HIZ – Heavy industrial zone, development and subdivision design minimises the potential for reverse sensitivity effects on adjacent sites, adjacent activities, or the wider environment; and
  - (2) Avoid, to the extent possible, and otherwise minimise, potential reverse sensitivity effects of locating new sensitive land uses in the vicinity of an intensive farming, extraction industry or industrial activity and regionally significant infrastructure.
- SUB-PI1 Boundary adjustments and relocations.
- Boundary adjustments and boundary relocations are designed to provide for more the efficient use of land.
- SUB-PI2 GRZ – General residential zone Te Kauwhata Ecological Area.
- (1) Subdivision in the Te Kauwhata Ecological Residential Area is designed and located to:
    - (a) Promote the natural features and landscapes of the Whangamarino Wetland and Lake Waikare; and
    - (b) Achieve the minimum lot size.
- SUB-PI3 Structure and master planning.
- Ensure that development and subdivision within approved structure or master plan areas is consistent with the development pattern and infrastructure provisions in the approved structure or master plan.
- SUB-PI4 Future development – Tuakau, Pokeno, and Te Kowhai within the LLRZ – Large lot residential zone.
- In Tuakau, Pokeno, and Te Kowhai, buildings, access, and lot boundaries are located to enable future subdivision and development in the event that reticulated water, stormwater, and wastewater infrastructure become available and a plan change to rezone to a higher density is in place.
- SUB-PI5 Effects of subdivision and development on soils in the GRUZ – General rural zone.
- Subdivision, use and development minimises the fragmentation of productive rural land, particularly where high class soils are located.
- SUB-PI6 Rural subdivision in the GRUZ – General rural zone.
- (1) Protect the productive capacity of land and soils.
  - (2) Maintain an open and spacious rural character.
  - (3) Minimise adverse effects on the safe and efficient operation of infrastructure; by:
    - (a) Avoiding subdivision that creates lots smaller than 0.8ha;
    - (b) Avoiding the creation of new lots that are wholly located on high class soils. For sites that are partially located on high class soils, new lots are to be located primarily on that part of the site that does not include high class soils;
    - (c) Limiting potential reverse sensitivity effects on productive rural activities, intensive farming, rural industry, infrastructure, or extractive activities by ensuring new lots provide adequate setbacks from potential sensitive activities;



Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

- (d) Ensuring that the subdivision does not compromise public access to rivers and water bodies or the quality of these environments; and
- (4) Make only limited provision for small rural lifestyle lots, where in addition to the matters set out in (1), (2), and (3), the subdivision:
- (a) Provides public parks and reserves, located in accordance with a Council Parks Strategy; or
  - (b) Provides a balance lot greater than 40ha; or
  - (c) Involves a boundary relocation to create the same number of lots formed as a large balance lot greater than 40ha and a number of small rural lifestyle lots that are clustered to form a hamlet; and
  - (d) Where (4)(b) and (c) applies, avoids ribbon development and the cumulative effects of multiple small rural residential lots locating on the same road frontage.

SUB-PI7 Subdivision in the RLZ – Rural lifestyle zone.

- (1) Subdivision within the zone ensures that:
- (a) The creation of undersized lots is avoided;
  - (b) New lots are of a size and shape to enable sufficient building setbacks from any boundary;
  - (c) Building platforms are sited to maintain the character of the zone and are appropriately positioned to enable future development;
  - (d) Existing infrastructure is not compromised;
  - (e) Character and amenity are not compromised.

SUB-PI8 Subdivision in the BTZ – Business Tamahere zone.

Subdivision of leasable units provides for the ongoing management and use of common facilities.

SUB-PI9 Manage subdivision and activities within the FUZ – Future urban zone.

- (1) Manage activities to ensure that the ability to develop the area for urban purposes is not compromised; and
- (2) Manage subdivision to ensure that future urban development is not compromised. This can include:
- (a) Avoiding the creation of additional lots that are smaller than 40ha, except where directly associated with utilities, network infrastructure, or a development consolidation lot;
  - (b) Enabling subdivision boundary adjustments and relocations; and
  - (c) Encouraging the consolidation of landholdings into single ownership to facilitate long-term comprehensive urban development by enabling the subdivision of an existing Record of Title to create one new title around an existing dwelling where the balance of the existing lot is subject to a consent notice on the Record of Title preventing further dwellings until such time as the FUZ – Future urban zone is rezoned to a long-term urban zoning.

Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

SUB-P20 Structure plans in the FUZ – Future urban zone.

- (1) Urban subdivision and development is to be in accordance with a structure plan that has been incorporated into the District Plan through a plan change process. The structure plan must include the following elements:
- (a) Key roading connections, collector road alignment, and public transport facilities;
  - (b) Key pedestrian / cycle linkages where these routes are separate from road or open space corridors;
  - (c) Land to be set aside for stormwater basins;
  - (d) The measures necessary to mitigate natural hazards, geotechnical issues, or soil contamination;
  - (e) Land to be set aside for public open space;
  - (f) How any existing natural, ecological, or landscape values will be maintained or enhanced;
  - (g) How any significant historic or cultural values will be maintained or enhanced;
  - (h) The general location of local commercial / community hubs and schools (if proposed);
  - (i) The general location of more intensive pockets of medium density residential development (if any);
  - (j) For residential developments, demonstrate the minimum yield to be achieved;
  - (k) How potential conflicts between new residential areas and existing industry, regional infrastructure, mineral extraction, or intensive farming operations will be mitigated including by the use of setbacks, open space, or large lots to create a buffer area; and
  - (l) Any staging necessary to ensure development achieves a good urban form and is able to be serviced.

SUB-P21 Subdivision in the HOPZ – Hopuhopu zone.

Avoid subdivision except where it is necessary for infrastructure, utilities, reserves, or road vesting.

SUB-P22 Subdivision development and design in the MTZ – Matangi zone.

- (1) Avoid subdivision that does not connect to public reticulated services;
- (2) Ensure subdivision and development provides integrated three waters infrastructure and services to each allotment;
- (3) Ensure subdivision and development maintains the setting of heritage items; and
- (4) Adverse effects of subdivision, use and development activities on the transport network are minimised with particular regard to:
  - (a) Reverse sensitivity effects of land uses sensitive to adverse transport effects (e.g. noise);
  - (b) Protecting strategic and arterial transport networks, rail crossings and associated intersections; and

- (c) Maintaining the safety of pedestrians and cyclists.

**SUB-P23** Subdivision in the MRZ2 – Medium density residential zone 2

- (1) Provide for subdivision that supports the development of medium density residential development as a controlled activity within the MRZ2 – Medium density residential zone 2, except where:
- (a) There is a relevant qualifying matter; or
- (b) The proposed subdivision does not comply with the relevant subdivision standards.
- (2) Require subdivision within the MRZ2 – Medium density residential zone 2 to not compromise any qualifying matters applied to the site.

**Rules**

All applications for subdivision consent, including controlled activities, are subject to section 106 of the Resource Management Act 1991.

Subdivision (zone specified in first column)

MRZ<sub>1</sub> – Medium density residential zone <sub>1</sub>

<b>SUB-R30</b>	Subdivision – general	
MRZ <sub>1</sub> – Medium density residential zone <sub>1</sub>	<p><b>(1) Activity status: CON</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Any subdivision in accordance with an approved land use resource consent must comply with that resource consent.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(b) Subdivision layout;</p> <p>(c) Compliance with the approved land use consent; and</p> <p>(d) Provision of infrastructure.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>SUB-R31</b>	Subdivision – general	
MRZ <sub>1</sub> – Medium density residential zone <sub>1</sub>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Subdivision must comply with all of the following standards:</p> <p>(i) Proposed vacant lots must have a minimum net site area (excluding access legs) of 200m<sup>2</sup>, except where the proposed lot is an access allotment, utility allotment or reserve to vest; and</p> <p>(ii) Proposed vacant lots must be able to connect to public-reticulated water supply and wastewater.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Subdivision layout;</li> <li>(b) Shape of lots and variation in lot sizes;</li> <li>(c) Ability of lots to accommodate a practical building platform including geotechnical stability for building;</li> <li>(d) Likely location of future buildings and their potential effects on the environment;</li> <li>(e) Avoidance or mitigation of natural hazards;</li> <li>(f) Opportunities for streetscape landscaping;</li> <li>(g) Vehicle and pedestrian networks;</li> <li>(h) Consistency with any relevant structure plan or master plan including the provision of neighbourhood parks, reserves and neighbourhood centres; and</li> <li>(i) Provision of infrastructure.</li> </ul>	
<b>SUB-R32</b>	Subdivision – general	
MRZ <sub>1</sub> – Medium density residential zone <sub>1</sub>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Every proposed vacant lot, other than one designed specifically for access or a utility allotment, must be capable of containing a building platform upon which a dwelling and living court could be sited as a permitted activity, with the building platform being contained within the following dimension: <ul style="list-style-type: none"> <li>(i) A rectangle of at least 100m<sup>2</sup> with a minimum dimension of 6m, exclusive of yards.</li> </ul> </li> </ul> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) Subdivision layout;</li> <li>(c) Shape of allotments;</li> <li>(d) Ability of allotments to accommodate a practical building platform;</li> <li>(e) Likely location of future buildings and their potential effects on the environment;</li> <li>(f) Avoidance or mitigation of natural hazards;</li> <li>(g) Geotechnical suitability for building; and</li> <li>(h) Ponding areas and primary overland flow paths.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>SUB-R33</b>	Subdivision – boundary adjustments	
MRZ <sub>1</sub> – Medium density residential zone <sub>1</sub>	<p><b>(1) Activity status: CON</b></p> <p><b>Activity specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Boundary adjustments must comply with all of the following standards:</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

	<p>(b) The standards specified in:                  (i) Rules SUB-R31 to SUB-R32 Subdivision - General;                  (c) Proposed lots must not generate any additional building infringements to those which legally existed prior to the boundary adjustment.</p> <p><b>Council’s control is reserved over the following matters:</b>                  (d) Subdivision layout; and                  (e) Shape of titles and variation in lot sizes.</p>	<p><b>Council’s discretion is restricted to the following matters:</b>                  (a) Subdivision layout; and                  (b) Shape of titles and variation in lot sizes.</p>
<b>SUB-R34</b>	Subdivision – amendments and updates to Cross Lease Flats Plans and Conversion to Freehold	
MRZ1 – Medium density residential zone 1	<p><b>(1) Activity status: CON</b>  <b>Activity specific standards:</b>                  (a) Conversion of a cross lease flats plan to a fee simple title.</p> <p><b>Council’s control is reserved over the following matters:</b>                  (b) Effects on existing buildings;                  (c) Site layout and design; and                  (d) Compliance with permitted building rules.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>SUB-R35</b>	Subdivision – amendments and updates to Cross Lease Flats Plans and Conversion to Freehold	
MRZ1 – Medium density residential zone 1	<p><b>(1) Activity status: CON</b>  <b>Activity specific standards:</b>                  (a) Amendment or update of a cross lease flats plan.</p> <p><b>Council’s control is reserved over the following matters:</b>                  (b) Effects on existing buildings;                  (c) Site layout and design of cross lease or flats plan; and                  (d) Compliance with permitted building rules.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>SUB-R36</b>	Title Boundaries – contaminated land	
MRZ1 – Medium density residential zone 1	<p><b>(1) Activity status: RDIS</b>  <b>Activity specific standards:</b>                  (a) Subdivision of land containing contaminated land (other than where the contaminated land has been confirmed as not being contaminated land for its intended use) must comply with all of the following standards:                  (i) Where an existing building is to be contained within the boundaries of any proposed lot (other than where any non-compliance existed lawfully prior to the</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p>subdivision), compliance is required with the following building rules relating to:</p> <ol style="list-style-type: none"> <li>(1) Height in relation to boundary (MRZ-S4);</li> <li>(2) Building coverage (MRZ-S6 – MRZ-S7); and</li> <li>(3) Building setbacks (MRZ-S11 – MRZ-S12).</li> </ol> <p>(b) Where any proposed subdivision contains one or more of the features listed in 1 – 2, the subdivision must not divide the following:</p> <ol style="list-style-type: none"> <li>(1) A natural hazard area;</li> <li>(2) Contaminated land (other than where the contaminated land has been confirmed as not being contaminated land for its intended use); and</li> </ol> <p>(ii) The boundaries of every proposed lot containing, adjoining or adjacent to the activities listed in 1 – 3 below, must provide the following setbacks:</p> <ol style="list-style-type: none"> <li>(1) 300m from any intensive farming activity;</li> <li>(2) 550m from the boundary of an Aggregate Extraction Area for rock extraction; and</li> <li>(3) 200m from the boundary of an Aggregate Extraction Area for sand excavation.</li> </ol> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ol style="list-style-type: none"> <li>(c) Landscape values;</li> <li>(d) Amenity values and character;</li> <li>(e) Reverse sensitivity effects;</li> <li>(f) Effects on existing buildings;</li> <li>(g) Effects on natural hazard areas;</li> <li>(h) Effects on contaminated land;</li> <li>(i) Effects on an intensive farming activity.</li> </ol>	
<p><b>SUB-R37</b></p>	<p>Subdivision – road frontage</p>	
<p>MRZ<u>1</u> – Medium density residential zone <u>1</u></p>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <ol style="list-style-type: none"> <li>(a) Every proposed vacant lot with a road boundary, other than an access allotment, utility allotment, or a proposed vacant lot containing a ROW or access leg, must have a width along the road boundary of at least 10m.</li> </ol>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p><b>Council's discretion is restricted to the following matters:</b></p> <p>(b) Safety and efficiency of vehicle access and road network.</p>	
<b>SUB-R38</b>	Subdivision creating reserves	
MRZ <u>1</u> – Medium density residential zone <u>1</u>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Every reserve, including where a reserve is identified within a structure plan or master plan (other than an esplanade reserve), proposed for vesting as part of the subdivision, must be bordered by roads along at least 50% of its boundaries.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(b) The extent to which the proposed reserve aligns with the principles of Council's Parks Strategy, Playground Strategy, Public Toilets Strategy and Trails Strategy;</p> <p>(c) Consistency with any relevant structure plan or master plan;</p> <p>(d) Reserve size and location;</p> <p>(e) Proximity to other reserves;</p> <p>(f) The existing reserve supply in the surrounding area;</p> <p>(g) Whether the reserve is of suitable topography for future use and development;</p> <p>(h) Measures required to bring the reserve up to Council standard prior to vesting; and</p> <p>(i) The type and standard of boundary fencing.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>SUB-R39</b>	Subdivision of Esplanade Reserves and Esplanade Strips	
MRZ <u>1</u> – Medium density residential zone <u>1</u>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Subdivision of an esplanade reserve or strip at least 20m wide (or other width stated in APP7 – Esplanade priority areas) that is required to be created shall vest in Council where the following situations apply:</p> <p>(i) The proposed lot is less than 4ha and within 20m of:</p> <p>(ii) mean high water springs;</p> <p>(iii) the bank of any river whose bed has an average width of 3m or more; or</p> <p>(iv) a lake whose bed has an area of 8ha or more; or</p> <p>(v) The proposed lot is more than 4ha or more than 20m from mean high water springs or a water body identified in APP7 – Esplanade priority areas.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) The type of esplanade provided - reserve or strip;</li> <li>(c) Width of the esplanade reserve or strip;</li> <li>(d) Provision of legal access to the esplanade reserve or strip;</li> <li>(e) Matters provided for in an instrument creating an esplanade strip or access strip; and</li> <li>(f) Works required prior to vesting any reserve in the Council, including pest plant control, boundary fencing and the removal of structures and debris.</li> </ul>	
--	---	--

MRZ2 – Medium density residential zone 2

<b>SUB-R152</b>	Subdivision – general	
MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: CON</b></p> <p><b>Activity specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Any subdivision in accordance with an approved land use resource consent must comply with that resource consent.</li> </ul> <p><b>Council's control is reserved over the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) Subdivision layout;</li> <li>(c) Compliance with the approved land use consent; and</li> <li>(d) Provision of infrastructure.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>SUB-R153</b>	Subdivision – general	
MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) <u>Except where SUB-R154 (Subdivision – residential) applies,</u> subdivision must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) Proposed vacant lots must have a minimum net site area (excluding access legs) of 200m<sup>2</sup>, except where the proposed lot is an access allotment, utility allotment or reserve to vest; and</li> <li>(ii) Proposed vacant lots must be able to connect to public-reticulated water supply and wastewater.</li> </ul> </li> </ul> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Subdivision layout;</li> <li>(b) Shape of lots and variation in lot sizes;</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>



	<p>(c) Ability of lots to accommodate a practical building platform including geotechnical stability for building;</p> <p><del>(d) Likely location of future buildings and their potential effects on the environment;</del></p> <p>(e) Avoidance or mitigation of natural hazards;</p> <p>(f) Opportunities for streetscape landscaping;</p> <p>(g) Vehicle and pedestrian networks;</p> <p>(h) Consistency with any relevant structure plan or master plan including the provision of neighbourhood parks, reserves and neighbourhood centres; and</p> <p>(i) Provision of infrastructure.</p>	
<b>SUB-RI54</b>	<u>Subdivision - residential</u>	
<u>MRZ2 – Medium density residential zone 2</u>	<p><b>(1) Activity status: CON</b></p> <p><b><u>Activity specific standards:</u></b></p> <p>(a) <u>Any subdivision around either existing (constructed or approved) residential units or proposed residential units where the subdivision application is accompanied by a land use application that will be determined concurrently.</u></p> <p>(b) <u>Any allotments created under SUB-R152 (1a) must have a minimum net site area (excluding access legs) of 200m<sup>2</sup> except where:</u></p> <p>(i) <u>The subdivision does not increase the degree of non compliance of the residential units with the standards in MRZ2-S2 to S9, or land use consent has been granted, or a concurrent land use application shows that it is practicable to construct on every allotment within the proposed subdivision a residential unit which complies with the standards in MRZ2-S2 to S9; and</u></p> <p>(ii) <u>No vacant allotments are created.</u></p> <p>(c) <u>For the purpose of SUB-R152(1b)(i), if a subdivision is proposed between residential units that share a common wall, the standard in MRZ2-S3 does not apply along the length of the common wall.</u></p> <p><b><u>Council’s control is reserved over the following matters:</u></b></p> <p>(d) <u>Subdivision layout; and</u></p> <p>(e) <u>Provision of infrastructure.</u></p> <p><b><u>Notification</u></b></p>	<b><u>Activity status where compliance not achieved: n/a</u></b>

	<p><u>Any application for a subdivision consent for a controlled activity under this rule will be considered without public or limited notification in the following circumstances:</u></p> <ul style="list-style-type: none"> <li>(a) A subdivision associated with the construction of no more than three residential units that do not comply with the standards in MRZ2-S2 to S9; or</li> <li>(b) A subdivision associated with the construction of four or more residential units that comply with the standards in MRZ2-S2 to S9; and</li> <li>(c) provided that other standards in the district plan are met.</li> </ul>	
<b>SUB-R155</b>	Subdivision – general	
MRZ – Medium density residential zone	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Every proposed vacant lot, other than one designed specifically for access or a utility allotment, must be capable of containing a building platform upon which a dwelling and living court could be sited as a permitted activity, with the building platform being contained within the following dimension: <ul style="list-style-type: none"> <li>(i) A rectangle of at least 100m<sup>2</sup> with a minimum dimension of 6m, exclusive of yards.</li> </ul> </li> </ul> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) Subdivision layout;</li> <li>(c) Shape of allotments;</li> <li>(d) Ability of allotments to accommodate a practical building platform;</li> <li>(e) Likely location of future buildings and their potential effects on the environment;</li> <li>(f) Avoidance or mitigation of natural hazards;</li> <li>(g) Geotechnical suitability for building; and</li> <li>(h) Ponding areas and primary overland flow paths.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>SUB-R156</b>	Subdivision – boundary adjustments	
MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: CON</b></p> <p><b>Activity specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Boundary adjustments must comply with all of the following standards:</li> <li>(b) The standards specified in: <ul style="list-style-type: none"> <li>(i) Rules in SUB-R31 to SUB-R32 <b>SUB-R153</b></li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p>

Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

	<p>(c) Proposed lots must not generate any additional building infringements to those which legally existed prior to the boundary adjustment.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) Subdivision layout; and (b) Shape of titles and variation in lot sizes.</p>	<p>(a) Subdivision layout; and (b) Shape of titles and variation in lot sizes.</p>
<b>SUB-R157</b>	Subdivision – amendments and updates to Cross Lease Flats Plans and Conversion to Freehold	
MR22 – Medium density residential zone 2	<p><b>(1) Activity status: CON</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Conversion of a cross lease flats plan to a fee simple title.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) Effects on existing buildings; (b) Site layout and design; and (c) Compliance with permitted building rules.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>SUB-R158</b>	Subdivision – amendments and updates to Cross Lease Flats Plans and Conversion to Freehold	
MR22 – Medium density residential zone 2	<p><b>(1) Activity status: CON</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Amendment or update of a cross lease flats plan.</p> <p><b>Council’s control is reserved over the following matters:</b></p> <p>(a) Effects on existing buildings; (b) Site layout and design of cross lease or flats plan; and (c) Compliance with permitted building rules.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>SUB-R159</b>	Title Boundaries – contaminated land	
MR22 – Medium density residential zone 2	<p><b>(3) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Subdivision of land containing contaminated land (other than where the contaminated land has been confirmed as not being contaminated land for its intended use) must comply with all of the following standards: (i) Where an existing building is to be contained within the boundaries of any proposed lot (other than where any non-compliance existed lawfully prior to the subdivision), compliance is required with the following building rules relating to:</p>	<p><b>(4) Activity status where compliance not achieved: DIS</b></p>

	<p>(1) Height in relation to boundary (MRZ-S4);</p> <p>(2) Building coverage (MRZ-S6-S7); and</p> <p>(3) Setbacks (MRZ-S10).</p> <p>(b) Where any proposed subdivision contains one or more of the features listed in 1—2, the subdivision must not divide the following:</p> <p>(1) A natural hazard area;</p> <p>(2) Contaminated land (other than where the contaminated land has been confirmed as not being contaminated land for its intended use); and</p> <p>(ii) The boundaries of every proposed lot containing, adjoining or adjacent to the activities listed in 1—3 below, must provide the following setbacks:</p> <p>(1) 300m from any intensive farming activity;</p> <p>(2) 550m from the boundary of an Aggregate Extraction Area for rock extraction; and</p> <p>(3) 200m from the boundary of an Aggregate Extraction Area for sand excavation.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Landscape values;</p> <p>(b) Amenity values and character;</p> <p>(c) Reverse sensitivity effects;</p> <p>(d) Effects on existing buildings;</p> <p>(e) Effects on natural hazard areas;</p> <p>(f) Effects on contaminated land;</p> <p>(g) Effects on an intensive farming activity.</p>	
<p><b>SUB-RI59</b></p>	<p>Subdivision – road frontage</p>	
<p>MRZ2 – Medium density residential zone 2</p>	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Every proposed vacant lot with a road boundary, other than an access allotment, utility allotment, or a proposed vacant lot containing a ROW or access leg, must have a width along the road boundary of at least 10m.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(b) Safety and efficiency of vehicle access and road network.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<b>SUB-RI 60</b>	Subdivision creating reserves	
MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Every reserve, including where a reserve is identified within a structure plan or master plan (other than an esplanade reserve), proposed for vesting as part of the subdivision, must be bordered by roads along at least 50% of its boundaries.</p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the proposed reserve aligns with the principles of Council’s Parks Strategy, Playground Strategy, Public Toilets Strategy and Trails Strategy;</p> <p>(b) Consistency with any relevant structure plan or master plan;</p> <p>(c) Reserve size and location;</p> <p>(d) Proximity to other reserves;</p> <p>(e) The existing reserve supply in the surrounding area;</p> <p>(f) Whether the reserve is of suitable topography for future use and development;</p> <p>(g) Measures required to bring the reserve up to Council standard prior to vesting; and</p> <p>(h) The type and standard of boundary fencing.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>SUB-RI 61</b>	Subdivision of Esplanade Reserves and Esplanade Strips	
MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity specific standards:</b></p> <p>(a) Subdivision of an esplanade reserve or strip at least 20m wide (or other width stated in APP7 – Esplanade priority areas) that is required to be created shall vest in Council where the following situations apply:</p> <p>(i) The proposed lot is less than 4ha and within 20m of:</p> <p>(ii) mean high water springs;</p> <p>(iii) the bank of any river whose bed has an average width of 3m or more; or</p> <p>(iv) a lake whose bed has an area of 8ha or more; or</p> <p>(v) The proposed lot is more than 4ha or more than 20m from mean high water springs or a water body identified in APP7 – Esplanade priority areas.</p> <p><b>Council’s discretion is restricted to the following matters:</b></p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<ul style="list-style-type: none"> <li>(a) The type of esplanade provided - reserve or strip;</li> <li>(b) Width of the esplanade reserve or strip;</li> <li>(c) Provision of legal access to the esplanade reserve or strip;</li> <li>(d) Matters provided for in an instrument creating an esplanade strip or access strip; and</li> <li>(e) Works required prior to vesting any reserve in the Council, including pest plant control, boundary fencing and the removal of structures and debris.</li> </ul>	
<p><b>SUB-RI62</b></p>	<p><u>Subdivision within the National Grid Corridor</u></p>	
<p><u>MRZ2 – Medium density residential zone 2</u></p>	<p><b>(1) Activity status: RDIS</b>  <b><u>Activity specific standards:</u></b></p> <ul style="list-style-type: none"> <li>(a) <u>The subdivision of land in any zone within the National Grid Subdivision Corridor that complies with all of the following standards:</u> <ul style="list-style-type: none"> <li>(i) <u>All resulting allotments must be able to demonstrate that they are capable of accommodating a building platform for the likely principal building(s) and any building(s) for a sensitive land use outside of the National Grid Yard, other than where the allotments are for roads, access ways or infrastructure; and</u></li> <li>(ii) <u>The layout of allotments and any enabling earthworks must ensure that physical access is maintained to any National Grid support structures located on the allotments, including any balance area.</u></li> </ul> </li> </ul> <p><b><u>Council’s discretion is restricted to the following matters:</u></b></p> <ul style="list-style-type: none"> <li>(a) <u>The subdivision layout and design in regard to how this may impact on the operation, maintenance, upgrading and development of, including access to, the National Grid;</u></li> <li>(b) <u>The ability to provide a complying building platform outside of the National Grid Yard;</u></li> <li>(c) <u>The risk of electrical hazards affecting public or individual safety, and the risk of property damage;</u></li> <li>(d) <u>The nature and location of any vegetation to be planted in the vicinity of National Grid transmission lines, and how such landscaping will impact on the operation, maintenance, upgrade and development (including access) of the National Grid;</u></li> <li>(e) <u>The risk to the structural integrity of the National Grid;</u></li> </ul>	<p><b>(2) Activity status where compliance not achieved: NC</b></p>

Part 2: District-wide matters / Subdivision / SUB – Subdivision - IPI

	(f) <u>The extent to which the subdivision design and consequential development will minimise the potential reverse sensitivity on and amenity and nuisance effects of the National Grid asset.</u>	
--	---	--

## EW – Earthworks

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Objectives

- EW-O1 Earthworks in all zones except the MRZ1 – Medium density residential zone 1. Earthworks facilitate subdivision, use and development.
- EW-O2 Earthworks in the MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2. Earthworks facilitate subdivision, use and development while avoiding, mitigating or remedying potential adverse effects.

### Policies

- EW-P1 Earthworks in the GRZ – General residential zone, M MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone or OSZ – Open space zone.
- (1) Manage the effects of earthworks to ensure that:
    - (a) Erosion and sediment loss is avoided or mitigated;
    - (b) Changes to natural water flows and established drainage paths are mitigated;
    - (c) Adjoining properties and public services are protected;
    - (d) The importation of cleanfill is avoided in the zone; and
    - (e) Adverse effects on historic heritage are avoided.
  - (2) Earthworks are designed and undertaken in a manner that ensures the stability and safety of surrounding land, buildings and structures.
  - (3) Manage the amount of land being disturbed at any one time to avoid, remedy or mitigate adverse construction noise, vibration, dust, lighting and traffic effects.
  - (4) Subdivision and development occur in a manner that maintains fundamental shape, contour and landscape characteristics.
  - (5) Manage the geotechnical risks to ensure the ground remains sound, safe and stable for the intended land use.
- EW-P2 Earthworks in the GRUZ – General rural zone, FUZ – Future urban zone, CORZ – Corrections zone or TTZ – TaTa Valley zone.
- (1) Enable earthworks associated with rural or conservation activities including:
    - (a) Ancillary rural earthworks;
    - (b) Farm quarries;
    - (c) The importation of controlled cleanfill material to a site; and
    - (d) Indigenous biodiversity restoration.
  - (2) Manage earthworks to ensure that:



Part 2: District-wide matters / General district-wide matters / EW – Earthworks

- (a) Erosion and sediment loss is avoided or mitigated;
- (b) The ground is geotechnically sound and remains safe and stable for the duration of the intended land use;
- (c) Changes to natural water flows and established drainage paths are avoided or mitigated;
- (d) Adjoining properties and infrastructure are protected;
- (e) Historic heritage and cultural values are recognised and protected; and
- (f) Ecosystem protection, restoration, rehabilitation or enhancement works are encouraged.

EW-P3 Earthworks in the RLZ – Rural lifestyle zone.

- (1) Manage the effects of earthworks to ensure that:
  - (a) Erosion and sediment loss is avoided or mitigated;
  - (b) The ground is geotechnically sound and remains safe and stable for the duration of the intended land use;
  - (c) Changes to natural water flows and established drainage paths is avoided or mitigated.
- (2) Manage the importation of fill material to a site.
- (3) Appropriately manage the importation of cleanfill to a site.
- (4) Manage the amount of land being disturbed at any one time to avoid, remedy or mitigate adverse construction noise, vibration, odour, dust, lighting and traffic effects.
- (5) Subdivision and development occur in a manner that maintains shape, contour and landscape characteristics.

EW-P4 Earthworks in the LCZ – Local centre zone, COM – Commercial zone or TCZ – Town centre zone.

- (1) Manage earthworks in the zone to minimise:
  - (a) The adverse effects and of sediment, of dust and stormwater runoff; and
  - (b) Adverse effects on heritage.

EW-P5 Earthworks in the MAZ – Mercer Airport zone.

Provide for the unique operational requirements of an airport whilst at the same time achieving appropriate levels of amenity for surrounding properties.

## Rules

*Land use – effects (zones specified in the first column)*

<b>EW-R1</b>	Gardening or disturbance of land for the installation of fence posts	
All zones	<b>(1) Activity status: PER</b> <b>Activity specific conditions:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>EW-R2</b>	Earthworks activities within the National Grid Yard	

<p>All zones</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Activity specific conditions:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within the National Grid Yard that comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) Do not exceed a depth (measured vertically) of 300mm within 12m of the outer visible edge of any National Grid support structure foundation.</li> <li>(ii) Do not compromise the stability of a National Grid support structure;</li> <li>(iii) Do not result in the loss of access to any National Grid support structure; and</li> <li>(iv) Do not result in a reduction in the ground to conductor clearance distances of less than 6.5m (measured vertically) from a 110kV National Grid transmission line, or 7.5m (measured vertically) from a 220kV National Grid transmission line.</li> </ul> </li> <li>(b) The following earthworks activities are exempt from Rules EW-R2(1)(a): <ul style="list-style-type: none"> <li>(i) Earthworks that are undertaken by a network utility operator (other than for the reticulation and storage of water for irrigation purposes) as defined by the Resource Management Act 1991;</li> <li>(ii) Earthworks undertaken as part of agricultural or domestic cultivation, or repair, sealing or resealing of a road, footpath, driveway or farm track;</li> <li>(iii) Vertical holes not exceeding 500mm in diameter that: <ul style="list-style-type: none"> <li>(1) Are more than 1.5m from the outer edge of the pole support structure or stay wire; or</li> <li>(2) Are a post hole for a farm fence or horticulture</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status: RDIS</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within the National Grid Yard that do not comply with Standard EW-R2(1)(a)(i) but complies with Standards EW-R2(1)(a)(ii) – (iv).</li> </ul> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) Impacts on the operation, maintenance, upgrading and development of the National Grid;</li> <li>(c) The risk to the structural integrity of the affected National Grid support structure(s);</li> <li>(d) Any impact on the ability of the National Grid owner (Transpower) to access the National Grid;</li> <li>(e) The risk of electrical hazards affecting public or individual safety, and the risk of property damage.</li> <li>(f) Technical advice provided by the National Grid owner (Transpower); and</li> <li>(g) Any effects on National Grid support structures including the creation of an unstable batter.</li> </ul> <p><b>(3) Activity status: NC</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within the National Grid Yard that is not a permitted activity under Rule EW-R2(1) or a restricted discretionary activity under Rule EW-R2(2)</li> </ul>
------------------	---	--

	structure more than 6m from the visible outer edge of a tower support structure foundation.	
--	---	--

LLRZ – Large lot residential zone and SETZ – Settlement zone

<b>EW-R3</b>	Earthworks – general	
LLRZ – Large lot residential zone; and SETZ – Settlement zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks (excluding the importation of fill material) within a site must meet all of the following standards:                             <ul style="list-style-type: none"> <li>(i) Be located more than 1.5 m horizontally from any waterway, open drain or overland flow path;</li> <li>(ii) Not exceed a volume of more than 350m<sup>3</sup>;</li> <li>(iii) Not exceed an area of more than 1,000m<sup>2</sup> over any single consecutive 12 month period;</li> <li>(iv) The total depth of any excavation or filling does not exceed 1.5m above or below ground level;</li> <li>(v) The slope of the resulting cut, filled areas or fill batter face in stable ground, does not exceed a maximum of 1:2 (1 vertical to 2 horizontal);</li> <li>(vi) Earthworks are set back at least 1.5m from all boundaries;</li> <li>(vii) Areas exposed by earthworks are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</li> <li>(viii) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(ix) Do not divert or change the nature of natural water flows,</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation; and</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>

	<p>water bodies or established drainage paths; and</p> <p>(x) Provided they are not within a kauri root zone</p>	
<b>EW-R4</b>	Earthworks – general	
LLRZ – Large lot residential zone; and SETZ – Settlement zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for the purpose of creating a building platform for residential purposes within a site, using imported cleanfill material, must meet the following standards:</p> <p>(b) Be carried out in accordance with NZS 4431:1989 Code of Practice for Earth Fill for Residential Development; and</p> <p>(c) Provided they are not within a kauri root zone</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation; and</p> <p>(l) Provided they are not within a kauri root zone</p>
<b>EW-R5</b>	Earthworks – general	
LLRZ – Large lot residential zone; and SETZ – Settlement zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for purposes other than creating a building platform for residential purposes within a site, using imported fill material, must meet all of the following standards:</p> <p>(i) Not exceed a total volume of 20m<sup>3</sup>;</p> <p>(ii) Not exceed a depth of 1.5m;</p> <p>(iii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p>

Part 2: District-wide matters / General district-wide matters / EW – Earthworks

	<ul style="list-style-type: none"> <li>(iv) Fill material is setback at least 1.5m from all boundaries;</li> <li>(v) Areas exposed by filling are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</li> <li>(vi) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</li> <li>(vii) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</li> <li>(viii) Provided they are not within a kauri root zone.</li> </ul>	<ul style="list-style-type: none"> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation; and</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<b>EW-R6</b>	Earthworks including the importation of cleanfill to a site	
LLRZ – Large lot residential zone; and SETZ – Settlement zone	<p><b>(1) Activity status: NC</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks including the importation of cleanfill to a site.</li> </ul>	

GRZ – General residential zone

<b>EW-R7</b>	Earthworks – general	
GRZ – General residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks (excluding the use of cleanfill material or fill material) within a site must meet all of the following standards:</li> <li>(b) Be located more than 1.5m horizontally from any waterway, open drain or overland flow path;</li> <li>(c) Not exceed a volume of 250m<sup>3</sup> and an area of not more than 1,000m<sup>2</sup> over any consecutive 12 month period;</li> <li>(d) The total depth of any excavation or filling does not exceed 1.5m above or below ground level;</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> </ul>

	<ul style="list-style-type: none"> <li>(e) The slope of the resulting cut, filled areas or fill batter face in stable ground, does not exceed a maximum of 1:2 (1 vertical to 2 horizontal);</li> <li>(f) Earthworks are set back at least 1.5m from all boundaries;</li> <li>(g) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and re-vegetated to achieve 80% ground cover within 6 months of cessation of the earthworks;</li> <li>(h) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(i) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</li> <li>(j) Provided they are not within a kauri root zone</li> </ul>	<ul style="list-style-type: none"> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation; and</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<b>EW-R8</b>	Earthworks – general	
GRZ – General residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks for the purpose of creating a building platform and accessway for residential purposes within a site, including the use of imported cleanfill material or imported fill material, must meet the following standards: <ul style="list-style-type: none"> <li>(i) Be carried out in accordance with NZS 4431:1989 Code of Practice for Earth Fill for Residential Development; and</li> <li>(ii) Provided they are not within a kauri root zone</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> </ul>

		<p>(k) Land instability, erosion and sedimentation; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R9</b>	Earthworks – general	
GRZ – General residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for purposes other than creating a building platform for residential purposes within a site, using imported fill material must meet all of the following standards:</p> <p>(i) Not exceed a total volume of 20m<sup>3</sup>;</p> <p>(ii) Not exceed a depth of 1m;</p> <p>(iii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Fill material is setback at least 1.5m from all boundaries;</p> <p>(v) Areas exposed by filling are revegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(vi) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(i) Amenity values and landscape effects;</p> <p>(ii) Volume, extent and depth of earthworks;</p> <p>(iii) Nature of fill material;</p> <p>(iv) Contamination of fill material;</p> <p>(v) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p> <p>(vi) Compaction of the fill material;</p> <p>(vii) Volume and depth of fill material;</p> <p>(viii) Protection of the Hauraki Gulf Catchment Area;</p> <p>(ix) Geotechnical stability;</p> <p>(x) Flood risk, including natural water flows and established drainage paths;</p> <p>(xi) Land instability, erosion and sedimentation; and</p> <p>(xii) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R10</b>	Earthworks involving the importation of controlled fill material to a site	
GRZ – General residential zone	<p><b>(1) Activity status: NC</b></p> <p><b>Where:</b></p> <p>(a) Earthworks involving the importation of controlled fill material to a site</p>	
<b>EW-R11</b>	Earthworks – general in PREC31- Lakeside Te Kauwhata precinct	

<p>PREC31- Lakeside Te Kauwhata precinct in the GRZ – General residential zone</p>	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <p>(a) Earthworks (excluding the importation of fill, or a CLDC), including earthworks necessary for the construction and maintenance of existing public roads or for construction of new roads in accordance with the Te Kauwhata Lakeside Precinct Plan, must meet all the following standards:</p> <p>(i) do not disturb or move more than 200m<sup>2</sup> within an individual site in a single calendar year except where the maximum area at any one time shall not exceed 400m<sup>2</sup>, and</p> <p>(ii) in relation to the height of any cut or batter face do not exceed 2m, or</p> <p>(iii) are necessary for building works authorised by a building consent and:</p> <p>(1) The area of earthworks is no more than 150% of the area of those building works, or</p> <p>(2) The earthworks occur on land with an average gradient no steeper than 1:8, or</p> <p>(3) Any trenching for network utilities, or on or offsite utilities within PREC31 – Lakeside Te Kauwhata precinct area are backfilled or reinstated to original ground level; or</p> <p>(4) Traffic associated with the works is managed in accordance with a Construction Traffic Management Plan approved by the Waikato District Council as the road controlling authority;</p> <p>(5) Including any cut and batter faces or filled</p>	<p><b>(2) Activity status where compliance not achieved: CON</b> <b>Council control shall be reserved over the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Visual effects;</p> <p>(c) Mitigation measures including sediment control;</p> <p>(d) Effects on land utilization;</p> <p>(e) Effects on erosion;</p> <p>(f) Effects on cultural values;</p> <p>(g) Effects on heritage values;</p> <p>(h) Effects on the Lake Waikare flood plain; and</p> <p>(i) The risk of earthworks exacerbating Kauri dieback disease.</p>
--	---	--



	<p>areas, are revegetated to achieve 80% ground cover within 12 months of the earthworks being commenced; and</p> <p>(6) Retain sediment within the construction area through the implementation and maintenance of sediment controls;</p> <p>(7) Provided they are not within a kauri root zone.</p> <p>(b) Rules EW-R7 – EW-R10 and SASM-R4 do not apply to earthworks within PREC31- Lakeside Te Kauwhata precinct; and</p> <p>Advice note: The Waikato Pest Management Plan addresses the management of identified pest species, including alligator weed. It includes enforceable controls relating to subdivision and land development in infected areas.</p>	
<p><b>EW-R12</b></p>	<p>Earthworks – general in PREC31- Lakeside Te Kauwhata precinct</p>	
<p>PREC31- Lakeside Te Kauwhata precinct in the GRZ – General residential zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks involving imported fill material (other than earthworks approved as part of a CLDC) meets all of the following standards:</p> <p>(i) All material for filling is cleanfill, and</p> <p>(ii) Filling that is not part of building work, or construction of roads, or installation of infrastructure:</p> <p>(1) Does not exceed a volume of 20m<sup>2</sup> and a depth of 1m, and</p> <p>(2) Does not include a building platform, and</p> <p>(3) Does not include placing fill into an area of significant indigenous vegetation or habitat, or</p> <p>(iii) Is for minor upgrading of existing electricity lines and does not exceed 50m<sup>2</sup>, and</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Visual effects;</p> <p>(c) Effects on indigenous vegetation and habitat;</p> <p>(d) Mitigation measures including replacement planting where vegetation removal is involved;</p> <p>(e) Effects on cultural values;</p> <p>(f) Effects on heritage values; and</p> <p>(g) The risk of earthworks exacerbating Kauri dieback disease</p>

	<p>(iv) Where traffic associated with the work uses public roads, is managed in accordance with an approved Construction Traffic Management Plan or authorised in writing by Waikato District Council as the road controlling authority; and</p> <p>(v) Provided they are not within a kauri root zone.</p> <p>(b) Rules EW-R7 – EW-R10 and SASM-R4 do not apply to earthworks within PREC3 I- Lakeside Te Kauwhata precinct.</p> <p>Advice note: The Waikato Pest Management Plan addresses the management of identified pest species, including alligator weed. It includes enforceable controls relating to subdivision and land development in infected areas.</p>	
--	--	--

MRZ1 – Medium density residential zone [1](#) and MRZ2 – Medium density residential zone [2](#)

<p><b>EW-R13</b></p> <p>MRZ1 – Medium density residential zone <a href="#">1</a> and <a href="#">MRZ2 – Medium density residential zone 2</a></p>	<p>Earthworks – general</p> <p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks (excluding the importation of fill material) within a site must meet all of the following standards:</p> <p>(i) Be located more than 1.5 m horizontally from any waterway, open drain or overland flow path;</p> <p>(ii) Not exceed a volume of 1000m<sup>3</sup>;</p> <p>(iii) Not exceed an area of 1ha over any consecutive 12 month period;</p> <p>(iv) The total depth of any excavation or filling does not exceed 1.5m above or below ground level;</p> <p>(v) The slope of the resulting cut, filled areas or fill batter face in stable ground, does not exceed a maximum of 1:2 (1 vertical to 2 horizontal);</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitats;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths;</p> <p>(j) Land instability, erosion and sedimentation; and</p>
---	---	---

	<ul style="list-style-type: none"> <li>(vi) Earthworks must not result in any instability of land or structures at, or beyond, the boundary of the site where the land disturbance occurs;</li> <li>(vii) Areas exposed by earthworks are revegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</li> <li>(viii) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</li> <li>(ix) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</li> <li>(x) Provided they are not within a kauri root zone</li> </ul>	<ul style="list-style-type: none"> <li>(k) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<p><b>EW-RI 4</b></p>	<p>Earthworks – general</p>	
<p>MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks for the purpose of creating a building platform for residential purposes within a site, including the use of imported cleanfill material and imported fill material, must meet the following standards: <ul style="list-style-type: none"> <li>(i) Be carried out in accordance with NZS 4431:1989 Code of Practice for Earth Fill for Residential Development; and</li> <li>(ii) Provided they are not within a kauri root zone</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(i) Amenity values and landscape effects;</li> <li>(ii) Volume, extent and depth of earthworks;</li> <li>(iii) Nature of fill material;</li> <li>(iv) Contamination of fill material;</li> <li>(v) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitats;</li> <li>(vi) Compaction of the fill material;</li> <li>(vii) Volume and depth of fill material;</li> <li>(viii) Geotechnical stability;</li> <li>(ix) Flood risk, including natural water flows and established drainage paths;</li> <li>(x) Land instability, erosion and sedimentation; and</li> </ul>

		(xi) The risk of earthworks exacerbating Kauri dieback disease
<b>EW-RI 5</b>	Earthworks – general	
MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for purposes other than creating a building platform for residential purposes within a site, using imported fill material must meet all of the following standards:</p> <p>(i) Not exceed a total volume of 50m<sup>3</sup>;</p> <p>(ii) Not exceed a depth of 1.5m;</p> <p>(iii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Earthworks must not result in any instability of land or structures at or beyond the boundary of the site where the land disturbance occurs;</p> <p>(v) Areas exposed by filling are revegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(vi) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(viii) Provided they are not within a kauri root zone</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitats;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths;</p> <p>(j) Land instability, erosion and sedimentation; and</p> <p>(k) The risk of earthworks exacerbating Kauri dieback disease</p>
<b>EW-RI 6</b>	Earthworks – general	
MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: NC</b></p> <p><b>Where:</b></p> <p>(a) Earthworks involving the importation of controlled fill material to a site.</p>	

<a href="#">density residential zone 2</a>	
--	--

GRUZ – General rural zone

Advice note: the National Environmental Standards for Freshwater 2020 also contain rules relating to earthworks and apply in addition to the District Plan rules.

<b>EW-RI7</b>	Ancillary rural earthworks	
GRUZ – General rural zone; CORZ – Corrections Zone; FUZ – Future urban zone; and TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Activity specific conditions:</b></p> <p>(a) Provided they are not within a kauri root zone</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The risk of earthworks exacerbating Kauri dieback disease</p>
<b>EW-RI8</b>	A farm quarry	
GRUZ – General rural zone; CORZ – Corrections Zone; FUZ – Future urban zone; and TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Activity specific conditions:</b></p> <p>(a) Where the volume of aggregate extracted does not exceed 1000m<sup>3</sup> in any single consecutive 12 month period;</p> <p>(b) Earthworks are setback 5m horizontally from any waterway, open drain or overland flow path; and</p> <p>(c) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material or cleanfill;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation; and</p> <p>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</p>

		(m) The risk of earthworks exacerbating Kauri dieback disease.
<b>EW-R19</b>	Earthworks required to form a building platform	
GRUZ – General rural zone; CORZ – Corrections Zone; FUZ – Future urban zone; and TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Activity specific conditions:</b></p> <p>(a) Earthworks required to form a building platform that will be subject to a building consent where undertaken in accordance with NZS 4431:1989 Code of Practice for Earth Fill for Residential Development; and</p> <p>(b) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material or cleanfill;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R20</b>	Earthworks ancillary to a conservation activity	
GRUZ – General rural zone; CORZ – Corrections Zone; FUZ – Future urban zone; and TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Activity specific conditions:</b></p> <p>(a) Shall meet the following standards:</p> <p>(i) Sediment resulting from the earthworks is managed on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material or cleanfill;</p>

	<p>(ii) Provided they are not within a kauri root zone</p>	<p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;  (f) Compaction of the fill material;  (g) Volume and depth of fill material;  (h) Protection of the Hauraki Gulf Catchment Area;  (i) Geotechnical stability;  (j) Flood risk, including natural water flows and established drainage paths;  (k) Land instability, erosion and sedimentation;  (l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and  (m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R21</b>	Earthworks – general	
<p>GRUZ – General rural zone;  CORZ – Corrections Zone;  FUZ – Future urban zone;  and TTZ – TaTa Valley zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) With the exception of earthworks for the activities listed in EW-R16 – EW-R20 earthworks within a site must meet all of the following standards:</p> <p>(i) Do not exceed a volume of more than 1000m<sup>3</sup> and an area of more than 2000m<sup>2</sup> over in any single consecutive 12 month period;</p> <p>(ii) The total combined depth of any excavation (excluding drilling) or filling does not exceed 3m above or below natural ground level;</p> <p>(iii) Take place on land with a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Earthworks are setback a minimum of 1.5m from all boundaries;</p> <p>(v) Areas exposed by earthworks are stabilised on completion and any remaining bare ground re-vegetated to achieve 80%</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;  (b) Volume, extent and depth of earthworks;  (c) Nature of fill material;  (d) Contamination of fill material or cleanfill;  (e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;  (f) Compaction of the fill material;  (g) Volume and depth of fill material;  (h) Protection of the Hauraki Gulf Catchment Area;  (i) Geotechnical stability;  (j) Flood risk, including natural water flows and established drainage paths;  (k) Land instability, erosion and sedimentation; and  (l) Effects on the safe, effective and efficient operation, maintenance</p>

	<p>ground cover within 2 months of the completion of the earthworks;</p> <p>(vi) Sediment resulting from the earthworks is managed on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p>and upgrade of infrastructure, including access; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<p><b>EW-R22</b></p>	<p>Earthworks – general</p>	
<p>GRUZ – General rural zone; CORZ – Corrections Zone; FUZ – Future urban zone; and TTZ – TaTa Valley zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) With the exception of earthworks for the activities listed in EW-R16 – EW-R20 using imported cleanfill material, concrete or brick must meet all of the following standards;</p> <p>(i) Do not exceed a total volume of 500m<sup>3</sup> in any single consecutive 12 month period;</p> <p>(ii) Do not exceed a depth of 1m above natural ground level;</p> <p>(iii) The slope of the resulting filled area in stable ground does not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Fill material is setback a minimum of 1.5m from all boundaries;</p> <p>(v) Areas exposed by filling are re-vegetated to achieve 80% ground cover within 2 months of the completion of the filling;</p> <p>(vi) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material or cleanfill;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>



	(vii) Provided they are not within a kauri root zone.	
<b>EW-R23</b>	Earthworks within a Whaanga Coast development specific control area of PREC5 – Whaanga Coast development precinct	
PREC5 – Whaanga Coast development precinct	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks within a Whaanga Coast development specific control area that complies with all of the following standards:</p> <p>(i) Do not exceed a volume of more than 500m<sup>3</sup> and an area of more than 1000m<sup>2</sup>;</p> <p>(ii) The total depth of any excavation or filling does not exceed 1.5m above or below ground level with a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iii) Areas exposed by earthworks are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(iv) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(v) Do not divert or change the nature of natural water flows, water bodies or established drainage; and</p> <p>(vi) Provided they are not within a kauri root zone</p> <p>(b) Rules EW-R17 to EW-R22 do not apply to earthworks within PREC5 – Whaanga Coast development precinct.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

RLZ – Rural lifestyle zone

<b>EW-R24</b>	Earthworks – general
---------------	----------------------

<p>RLZ – Rural lifestyle zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site for: <ul style="list-style-type: none"> <li>(i) Ancillary rural earthworks; or</li> <li>(ii) Construction and/or maintenance of tracks, fences or drains; or</li> <li>(iii) A building platform for a residential activity including an accessory building.</li> </ul> </li> <li>(b) Provided they are not within a kauri root zone.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation;</li> <li>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</li> <li>(m) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<p><b>EW-R25</b></p>	<p>Earthworks – general</p>	
<p>RLZ – Rural lifestyle zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site for purposes other those contained in EW-R24 (excluding the importation of fill material) must meet all of the following standards: <ul style="list-style-type: none"> <li>(i) Do not exceed a volume of more than 500m<sup>3</sup> and an area of more than 1000m<sup>2</sup> within a site over any single consecutive 12 month period;</li> <li>(ii) The total depth of any excavation or filling does not exceed 1.5m above or below ground level;</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> </ul>

	<ul style="list-style-type: none"> <li>(iii) Earthworks are set back at least 1.5m from any boundary;</li> <li>(iv) Areas exposed by earthworks are re-vegetated or otherwise stabilised to achieve 80% ground cover within 2 months of the completion of the earthworks;</li> <li>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</li> <li>(vii) Provided they are not within a kauri root zone.</li> </ul>	<ul style="list-style-type: none"> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation;</li> <li>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</li> <li>(m) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<p><b>EW-R26</b></p>	<p>Earthworks – general</p>	
<p>RLZ – Rural lifestyle zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks for purposes other than creating a building platform for residential purposes within a site, using imported fill material must meet all of the following standards: <ul style="list-style-type: none"> <li>(i) Not exceed a total volume of 50m<sup>3</sup>;</li> <li>(ii) Not exceed a depth of 1.5m;</li> <li>(iii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</li> </ul> </li> <li>(iv) Fill material is set back 1.5m from all boundaries;</li> <li>(v) Areas exposed by filling are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</li> <li>(vi) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation;</li> <li>(l) Effects on the safe, effective and efficient operation, maintenance</li> </ul>

Part 2: District-wide matters / General district-wide matters / EW – Earthworks

	<p>sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	<p>and upgrade of infrastructure, including access; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R27</b>	Earthworks including the importation of cleanfill to a site	
RLZ – Rural lifestyle zone	<p><b>(1) Activity status: NC</b></p> <p><b>Where:</b></p> <p>(a) Earthworks including the importation of cleanfill to a site.</p>	

LCZ – Local centre zone and COMZ – Commercial zone

<b>EW-R28</b>	Earthworks – general	
LCZ – Local centre zone; COMZ – Commercial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks within a site must meet all of the following standards:</p> <p>(i) Be located more than 1.5m from infrastructure including a public sewer, open drain, overland flow path or other public service pipe;</p> <p>(ii) Not exceed a volume of more than 250m<sup>3</sup> and an area of more than 1,000m<sup>2</sup> within a site over any single consecutive 12 month period;</p> <p>(iii) The height of the resulting cut, filled areas or fill batter face in stable ground, does not exceed 1.5m, with a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Earthworks are set back at least 1.5m from all boundaries;</p> <p>(v) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and re-vegetated to achieve 80% ground cover within 2 months of completion of the earthworks or finished with a hardstand surface;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation; and</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>

	<p>(vi) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(viii) Provided they are not within a kauri root zone</p>	
<b>EW-R29</b>	Earthworks – general	
LCZ – Local centre zone; COMZ – Commercial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for the purpose of creating a building platform within a site (including the use of imported fill material) that is:</p> <p>(i) Subject to an approved building consent; and</p> <p>(ii) The earthworks occur wholly within the footprint of the building.</p> <p>(b) For the purposes of this rule, the footprint of the building extends 1.8m from the outer edge of the outside wall.</p> <p>(c) For the purposes of this rule, this exemption does not apply to earthworks associated with retaining walls/structures which are not required for the structural support of the building; and</p> <p>(d) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R30</b>	Earthworks – general	
LCZ – Local centre zone; COMZ – Commercial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks using the importation of fill material to a</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p>

	<p>site must meet all of the following standards:</p> <ul style="list-style-type: none"> <li>(i) Must not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1m (excluding backfill)</li> <li>(ii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1m vertical to 2m horizontal);</li> <li>(iii) Fill material is setback at least 1.5m from all boundaries;</li> <li>(iv) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and revegetated to achieve 80% ground cover within 6 months of the cessation of the earthworks;</li> <li>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</li> <li>(vii) Provided they are not within a kauri root zone.</li> </ul>	<ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths</li> <li>(k) Land instability, erosion and sedimentation; and</li> <li>(l) Proximity to underground services and service connections; and</li> <li>(m) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
--	--	---

TCZ – Town centre zone

<b>EW-R31</b>	Earthworks – general	
TCZ – Town centre zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site must meet all of the following standards:</li> <li>(i) Earthworks must be located more than 1.5m from infrastructure including a public sewer, open drain, overland flow path or other public service pipe;</li> <li>(ii) Earthworks must not exceed a volume of more than</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks in relation to waterways, significant</li> </ul>

	<p>250m<sup>3</sup> and an area of more than 1,000m<sup>2</sup> within a site over any single consecutive 12 month period;</p> <p>(iii) The height of the resulting cut, filled areas or fill batter face in stable ground, , does not exceed 1.5m, with a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Earthworks are set back at least 1.5m from all boundaries;</p> <p>(v) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and re-vegetated to achieve 80% ground cover within 2 months of completion of the earthworks or finished with a hardstand surface;</p> <p>(vi) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Earthworks must not divert or change the nature of natural water flows, waterbodies or established drainage paths;</p> <p>(viii) Earthworks must not result in the site being unable to be serviced by gravity sewers; and</p> <p>(ix) Provided they are not within a kauri root zone.</p>	<p>indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<p><b>EW-R32</b></p>	<p>Earthworks – general</p>	
<p>TCZ – Town centre zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for the purpose of creating a building platform within a site (including the use of imported fill material) that is:</p> <p>(i) Subject to an approved building consent; and</p> <p>(ii) The earthworks occur wholly within the footprint of the building.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p>

	<p>(b) For the purposes of this rule, the footprint of the building extends 1.8m from the outer edge of the outside wall.</p> <p>(c) For the purposes of this rule, this exemption does not apply to earthworks associated with retaining walls/structures which are not required for the structural support of the building; and</p> <p>(d) Provided they are not within a kauri root zone.</p>	<p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R33</b>	Earthworks – general	
TCZ – Town centre zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks using the importation of fill material to a site must meet all of the following standards:</p> <p>(i) Must not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1m (excluding backfill);</p> <p>(ii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1m vertical to 2m horizontal);</p> <p>(iii) Fill material is set back at least 1.5m from all boundaries;</p> <p>(iv) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and revegetated to achieve 80% ground cover within 6 months of the cessation of the earthworks;</p> <p>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p>



	<p>and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
--	--	---

GIZ – General industrial zone

<b>EW-R34</b>	Earthworks – general	
GIZ – General industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks (excluding the importation of fill material) within a site that:</p> <p>(i) Are located at least 1.5 m from any water body, open drain or overland flow path;</p> <p>(ii) Do not exceed a volume of 10,000m<sup>3</sup>;</p> <p>(iii) Do not exceed an area of more than 10,000m<sup>2</sup> within a 12 month period;</p> <p>(iv) Do not exceed a slope in stable ground of 1:2 (1 metre vertical to 2 metre horizontal);</p> <p>(v) Result in exposed areas being re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks, or finished with a hardstand surface;</p> <p>(vi) Result in sediment being retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Do not result in any change to natural water flows, any water body or established drainage path; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) land instability, erosion and sedimentation; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R35</b>	Earthworks – general	

<p>GIZ – General industrial zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site that may, or may not, involve imported cleanfill material, for the purpose of creating a building platform and/or ancillary hardstand area: <ul style="list-style-type: none"> <li>(i) Provided they are not within a kauri root zone.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) land instability, erosion and sedimentation; and</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<p><b>EW-R36</b></p>	<p>Earthworks – general</p>	
<p>GIZ – General industrial zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks involving imported fill material (excluding cleanfill material) for purposes other than creating a building platform for residential purposes within a site, that: <ul style="list-style-type: none"> <li>(i) Are located at least 1.5 metres from any water body, open drain or overland flow path;</li> <li>(ii) Do not exceed a volume of 10,000m<sup>3</sup>;</li> <li>(iii) Do not exceed a slope in stable ground of 1:2 (1 metre vertical to 2 metre horizontal);</li> <li>(iv) Result in exposed areas being re-vegetated to achieve 80% ground cover within 2 months of the completion of</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> </ul>

	<p>the earthworks, or finished with a hardstand surface;</p> <p>(v) Result in sediment being retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vi) Do not result in any change to natural water flows, any water body or established drainage path; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) land instability, erosion and sedimentation; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>
--	---	--

*HIZ – Heavy industrial zone*

<p><b>EW-R37</b></p> <p>HIZ – Heavy industrial zone</p>	<p>Earthworks – general</p>	
	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks (excluding the importation of fill material) within a site that:</p> <p>(i) Are located at least 1.5 m from any water body, open drain or overland flow path;</p> <p>(ii) Do not exceed a volume of 10,000m<sup>3</sup>;</p> <p>(iii) Do not exceed an area of more than 10,000m<sup>2</sup> within a 12 month period;</p> <p>(iv) Do not exceed a slope in stable ground of 1:2 (1 metre vertical to 2 metre horizontal);</p> <p>(v) Result in exposed areas being re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks, or finished with a hardstand surface;</p> <p>(vi) Result in sediment being retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>

	<p>(vii) Do not result in any change to natural water flows, any water body or established drainage path; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	
<b>EW-R38</b>	Earthworks – general	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks within a site that may, or may not, involve imported cleanfill material, for the purpose of creating a building platform and/or ancillary hardstand area:</p> <p>(i) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R39</b>	Earthworks – general	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks involving imported fill material (excluding cleanfill material) for purposes other than creating a building platform for residential purposes within a site, that:</p> <p>(i) Are located at least 1.5 metres from any water body, open drain or overland flow path</p> <p>(ii) Do not exceed a volume of 10,000m<sup>3</sup>;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p>

	<ul style="list-style-type: none"> <li>(iii) Do not exceed a slope in stable ground of 1:2 (1 metre vertical to 2 metre horizontal);</li> <li>(iv) Result in exposed areas being re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks, or finished with a hardstand surface;</li> <li>(v) Result in sediment being retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(vi) Do not result in any change to natural water flows, any water body or established drainage path; and</li> <li>(vii) Provided they are not within a kauri root zone.</li> </ul>	<ul style="list-style-type: none"> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> <li>(k) Land instability, erosion and sedimentation; and</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
--	--	--

OSZ – Open space zone

<b>EW-R40</b>	Earthworks – general	
OSZ – Open space zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks (excluding the importation of fill material) within a site must meet all of the following standards: <ul style="list-style-type: none"> <li>(i) Be located more than 1.5m from a public sewer, open drain, overland flow path or other service pipe;</li> <li>(ii) Not exceed a volume of more than 250m<sup>3</sup> and an area of more than 1,000m<sup>2</sup> over a single consecutive 12-month period;</li> <li>(iii) The height of the resulting cut, filled areas or fill batter face in stable ground, does not exceed 1.5m, with a maximum slope of 1:2 (1 vertical to 2 horizontal);</li> <li>(iv) Areas exposed by earthworks are re-vegetated or otherwise stabilised to</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Protection of the Hauraki Gulf Catchment Area;</li> <li>(i) Geotechnical stability;</li> <li>(j) Flood risk, including natural water flows and established drainage paths;</li> </ul>

	<p>achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(v) Earthworks are set back at least 1.5m from all boundaries;</p> <p>(vi) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vii) Does not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	<p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R4I</b>	Earthworks – general	
OSZ – Open space zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for purposes of creating a building platform within a site, using imported fill material:</p> <p>(i) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p>

		(m) The risk of earthworks exacerbating Kauri dieback disease.
<b>EW-R42</b>	Earthworks – general	
OSZ – Open space zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for purposes other than creating a building platform within a site, using imported fill material (excluding cleanfill) must meet all of the following standards:</p> <p>(i) Must not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1m;</p> <p>(ii) The slope of the resulting in stable ground must not exceed a maximum slope of 1:2 (1m vertical to 2m horizontal);</p> <p>(iii) Fill material is setback at least 1.5m from all boundaries;</p> <p>(iv) Areas exposed by filling are revegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(v) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths;</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R43</b>	Earthworks – general	
OSZ – Open space zone	<p><b>(1) Activity status: NC</b></p> <p>(a) Importation of cleanfill to a site.</p>	

BTZ – Business Tamahere zone

<b>EW-R44</b>	Earthworks – general	
BTZ – Business	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

<p>Tamahere zone</p>	<p>(a) Earthworks within a site must meet all of the following standards:</p> <p>(i) Earthworks must be located more than 1.5m from infrastructure including a public sewer, open drain, overland flow path or other public service pipe;</p> <p>(ii) Earthworks must not exceed a volume of more than 5000m<sup>3</sup> and an area of more than 1000m<sup>2</sup> within a site;</p> <p>(iii) The height of the resulting cut, filled areas or fill batter face in stable ground, does not exceed 1.5m, with a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and re-vegetated to achieve 80% ground cover within 6 months of cessation of the earthworks;</p> <p>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</p> <p>(vi) Provided they are not within a kauri root zone.</p>	<p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<p><b>EW-R45</b></p>	<p>Earthworks – general</p>	
<p>BTZ – Business Tamahere zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks for the purpose of creating a building platform within a site (including the use of imported fill material) that is:</p> <p>(i) Subject to an approved building consent;</p> <p>(ii) The earthworks occur wholly within the footprint of the building;</p> <p>(iii) The earthworks do not within a kauri root zone.</p> <p>(b) For the purposes of this rule, the footprint of the building</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p>



	<p>extends 1.8m from the outer edge of the outside wall.</p> <p>(c) For the purposes of this rule, this exemption does not apply to earthworks associated with retaining walls/structures which are not required for the structural support of the building.</p>	<p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<p><b>EW-R46</b></p>	<p>Earthworks – general</p>	
<p>BTZ – Business Tamahere zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks using the importation of fill material to a site must meet all of the following standards:</p> <p>(i) Must not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1m (excluding backfill);</p> <p>(ii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1m vertical to 2m horizontal);</p> <p>(iii) Fill material is setback at least 1.5m from all boundaries;</p> <p>(iv) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and revegetated to achieve 80% ground cover within 6 months of the cessation of the earthworks;</p> <p>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks in relation to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Protection of the Hauraki Gulf Catchment Area;</p> <p>(i) Geotechnical stability;</p> <p>(j) Flood risk, including natural water flows and established drainage paths</p> <p>(k) Land instability, erosion and sedimentation;</p> <p>(l) Proximity to underground services and service connections;</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>

	<p>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	
--	---	--

HOPZ – Hopuhopu zone


<b>EW-R47</b>	Earthworks – general	
HOPZ – Hopuhopu zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Except as otherwise specified in Advice note 1 and 2 below:</p> <p>(i) Ancillary rural earthworks provided they are not within a kauri root zone;</p> <p>(ii) A farm quarry where the volume of aggregate extracted does not exceed 1000m<sup>3</sup> in any single consecutive 12 month period and provided they are not within a kauri root zone.</p> <p>(b) Earthworks ancillary to a conservation activity must meet the following standards:</p> <p>(i) Sediment resulting from the earthworks is managed on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</p> <p>(ii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material or clean fill;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths;</p> <p>(j) Land instability, erosion and sedimentation;</p> <p>(k) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access;</p> <p>(l) Proximity to underground services and service connections; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R48</b>	Earthworks – general	
HOPZ – Hopuhopu zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) With the exception of earthworks for the activities listed in EW-R47 and EW-R49, earthworks across the whole of the HOPZ – Hopuhopu zone</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p>

	<p>must meet all of the following standards:</p> <ul style="list-style-type: none"> <li>(i) Cumulatively, do not exceed a volume of more than 2000m<sup>3</sup> and an area of more than 4000m<sup>2</sup> over any single consecutive 12 month period of which imported fill material or cleanfill does not exceed a total volume of 1,000m<sup>3</sup> in any single consecutive 12 month period;</li> <li>(ii) The total combined depth of any excavation (excluding drilling) or filling does not exceed 3m above or below natural ground level;</li> <li>(iii) Take place on land with a maximum slope of 1:2 (1 vertical to 2 horizontal);</li> <li>(iv) Earthworks are setback a minimum of 1.5m from all site and zone boundaries;</li> <li>(v) Earthworks are setback 5m horizontally from any waterway, open drain or overland flow path;</li> <li>(vi) Areas exposed by earthworks are stabilised to avoid runoff within 1 month and any remaining bare ground re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks or finished with a hardstand surface;</li> <li>(i) Sediment resulting from the earthworks is managed on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(ii) Do not divert or change the nature of natural water flows, water bodies or established drainage paths;</li> <li>(iii) Earthworks must not result in the site being unable to be</li> </ul>	<ul style="list-style-type: none"> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material or clean fill;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Geotechnical stability;</li> <li>(i) Flood risk, including natural water flows and established drainage paths;</li> <li>(j) Land instability, erosion and sedimentation;</li> <li>(k) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access;</li> <li>(l) Proximity to underground services and service connections; and</li> <li>(m) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
--	--	---

	<p>serviced by gravity sewers; and (iv) Provided they are not within a kauri root zone.</p>	
<b>EW-R49</b>	Earthworks – general	
HOPZ – Hopuhopu zone	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks for the purpose of creating a building platform (including the use of imported fill material) that is: <ul style="list-style-type: none"> <li>(i) Subject to an approved building consent;</li> <li>(ii) The earthworks occur wholly within the footprint of the building;</li> <li>(iii) Provided they are not within a kauri root zone;</li> <li>(iv) For the purposes of this rule, the footprint of the building extends 1.8m from the outer edge of the outside wall; and</li> <li>(v) For the purposes of this rule, this exemption does not apply to earthworks associated with retaining walls/structures which are not required for the structural support of the building.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material or clean fill;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Geotechnical stability;</li> <li>(i) Flood risk, including natural water flows and established drainage paths;</li> <li>(j) Land instability, erosion and sedimentation;</li> <li>(k) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</li> <li>(l) Proximity to underground services and service connections; and</li> <li>(m) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>

*Advice Note 1: The Hopuhopu Archaeological Site map below (Figure 19) indicates an area which contains Maori-made soils and possible borrow pits. Heritage New Zealand Pouhere Taonga should be contacted regarding development in this area and an archaeological assessment to determine the need for an archaeological authority. The Heritage New Zealand Pouhere Taonga Act 2014 protects both recorded and unrecorded archaeological sites.*

*Advice Note 2: The ‘Indicative Borrow Pit and Maori-Made Soils’ area also coincides with an area known to have contained alligator weed. The Waikato Regional Pest Management Plan 2014-2024 contains rules which relate to the management of alligator weed.*



**Figure 19 – Indicative borrow pits and Maaori-made soils**

KLZ – Kimihia lakes zone

<b>EW-R50</b>	Earthwork – general	
KLZ – Kimihia lakes zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Areas exposed by earthworks are re-vegetated must achieve 80% ground cover within 2 months of the completion of the earthworks except where earthworks are for the purposes of creating infrastructure or facilities for recreation, events and access, no re-vegetation is required;</li> <li>(b) Sediment resulting from the earthworks must be retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(c) The importation of fill material to site must meet the following conditions:</li> <li>(d) Does not restrict the ability for land to drain;</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Contamination of fill material;</li> <li>(b) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(c) Flood risk, including natural water flows and established drainage paths;</li> <li>(d) Land instability, erosion and sedimentation; and</li> <li>(e) Proximity to underground services and service connections; and</li> <li>(f) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>

	<p>(e) Is not located within 1.5m of public sewers, utility services or manholes;</p> <p>(f) The sediment from fill material is retained on the site; and</p> <p>(g) Provided they are not within a kauri root zone.</p>	
--	--	--

MAZ – Mercer airport zone

<b>EW-R51</b>	Earthworks – general	
MAZ – Mercer airport zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Earthworks within the MAZ – Mercer Airport zone must meet all of the following standards:</p> <p>(i) Earthworks must not exceed a volume of more than 1,000m<sup>3</sup> in a single calendar year;</p> <p>(ii) Earthworks must not exceed an area of more than 1,000m<sup>2</sup> in a single calendar year;</p> <p>(iii) The height of the resulting cut or batter face does not exceed 1.5 m with a maximum slope of 1:2 (1 metre vertical to 2 m horizontal);</p> <p>(iv) Areas exposed by the earthworks not covered by buildings or other impervious surfaces are revegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(v) Sediment is retained on site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vi) Earthworks must not divert or change natural water flows or established drainage paths; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of earthworks relative to waterways;</p> <p>(f) Compaction of fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability of fill material;</p> <p>(i) Flood risk;</p> <p>(j) Land instability, erosion and sedimentation; and</p> <p>(k) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R52</b>	Earthworks – general	

<p>MAZ – Mercer airport zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The importation of fill material to the site must meet all of the following standards, in addition to the standards in Rule EW-R51:</li> <li>(v) Earthworks do not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1 metre;</li> <li>(vi) Earthworks must be fit for compaction;</li> <li>(vii) The height of the resulting batter face in stable ground must not exceed 1.5 metres with a maximum slope of 1:2 (1m vertical to 2m horizontal);</li> <li>(viii) Earthworks do not restrict the ability of the land to drain;</li> <li>(ix) The sediment from fill material is retained on the site; and</li> <li>(x) Provided they are not within a kauri root zone.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of earthworks relative to waterways;</li> <li>(f) Compaction of fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Geotechnical stability of fill material;</li> <li>(i) Flood risk;</li> <li>(j) Land instability, erosion and sedimentation; and</li> <li>(k) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
----------------------------------	--	--

MSRZ – Motorsport and recreation zone

<p><b>EW-R53</b> MSRZ – Motorsport and recreation zone</p>	<p>Earthworks – all precincts</p> <p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site must meet all of the following standards: <ul style="list-style-type: none"> <li>(i) Do not exceed a volume of more than 1000m<sup>3</sup> and an area of more than 2000m<sup>2</sup> over any single consecutive 12-month period;</li> <li>(ii) The total depth of any excavation or filling does not exceed 3m above or below ground level with a maximum slope of 1:2 (1 vertical to 2 horizontal);</li> <li>(iii) Earthworks are setback 1.5m from all boundaries;</li> <li>(iv) Areas exposed by earthworks are re-vegetated to achieve 80% ground cover</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Geotechnical stability;</li> <li>(i) Flood risk, including natural water flows and established drainage paths</li> </ul>
--	--	--

	<p>within 2 months of the completion of the earthworks;</p> <p>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p>(j) Land instability, erosion and sedimentation;</p> <p>(k) Proximity to underground services and service connections; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R54</b>	Earthworks – all precincts	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The importation of fill material to a site shall meet all of the following standards in addition to Rule EW-R53:</p> <p>(i) Does not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1m;</p> <p>(ii) Is fit for compaction;</p> <p>(iii) The height of the resulting batter face in stable ground must not exceed 1.5m with a maximum slope of 1:2 (1m vertical to 2m horizontal);</p> <p>(iv) Does not restrict the ability for land to drain;</p> <p>(v) Is not located within 1.5m of public sewers, utility services or manholes;</p> <p>(vi) The sediment from fill material is retained on the site; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths</p> <p>(j) Land instability, erosion and sedimentation;</p> <p>(k) Proximity to underground services and service connections; and</p> <p>(l) The risk of earthworks exacerbating Kauri dieback disease.</p>

MTZ – Matangi zone

<b>EW-R55</b>	Earthworks – general
---------------	----------------------



<p>MTZ – Matangi zone</p>	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site must meet the following standards: <ul style="list-style-type: none"> <li>(i) Not exceed a volume of more than 2,500m<sup>3</sup>;</li> <li>(ii) Not exceed an area of more than 10,000m<sup>2</sup> within a 12 month period;</li> <li>(iii) Earthworks associated with any activity requiring building consent (including associated site works) shall not exceed 500m<sup>3</sup>;</li> <li>(iv) any excavation or filling does not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</li> <li>(v) Not be located within 1.5m of the KiwiRail designated corridor;</li> <li>(vi) Areas exposed by earthworks are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks, or finished with a hardstand surface;</li> <li>(vii) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</li> <li>(viii) Do not divert or change the nature of natural water flows, water bodies or onsite disposal systems for wastewater and stormwater; and</li> <li>(ix) Provided they are not within a kauri root zone.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Effects on waterbodies, and significant indigenous vegetation and habitat;</li> <li>(e) Compaction of the fill material;</li> <li>(f) Volume and depth of fill material;</li> <li>(g) Geotechnical stability;</li> <li>(h) Flood risk, including natural water flows and established drainage paths;</li> <li>(i) Land instability, erosion and sedimentation;</li> <li>(j) Proximity to underground services and service connections;</li> <li>(k) Effects on onsite disposal systems for wastewater and stormwater; and</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
<p><b>EW-R56</b></p>	<p>Earthworks – general</p>	
<p>MTZ – Matangi zone</p>	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks for the purpose of creating a building platform within a site, using imported fill material (excluding cleanfill),</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> </ul>

	<p>must meet the following standards:</p> <ul style="list-style-type: none"> <li>(i) Must not exceed a total volume of 500m<sup>3</sup>;</li> <li>(ii) The slope of the resulting filled area in stable ground must not exceed a maximum slope of 1:2 (1 vertical to 2 horizontal);</li> <li>(iii) Areas exposed by filling are revegetated to achieve 80% ground cover within 2 months of the completion of the earthworks, or finished with a hardstand surface;</li> <li>(iv) Sediment resulting from the filling is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</li> <li>(v) Do not divert or change the nature of natural water flows, water bodies or established drainage paths, or onsite disposal systems for wastewater and stormwater; and</li> <li>(vi) Provided they are not within a kauri root zone.</li> </ul>	<ul style="list-style-type: none"> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Effects on waterbodies, and significant indigenous vegetation and habitat;</li> <li>(e) Compaction of the fill material;</li> <li>(f) Volume and depth of fill material;</li> <li>(g) Geotechnical stability;</li> <li>(h) Flood risk, including natural water flows and established drainage paths;</li> <li>(i) Land instability, erosion and sedimentation;</li> <li>(j) Proximity to underground services and service connections; and</li> <li>(k) Effects on onsite disposal systems for wastewater and stormwater;</li> <li>(l) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>
--	---	--

RPZ – Rangitahi Peninsula zone

<b>EW-R57</b>	Earthworks – general	
RPZ – Rangitahi Peninsula zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Earthworks within a site must meet all of the following standards: <ul style="list-style-type: none"> <li>(i) Be located more than 1.5m from a public sewer, open drain, overland flow path or other service pipe;</li> <li>(ii) Not exceed a volume of more than 250m<sup>3</sup> and an area of more than 1,000m<sup>2</sup> within a site;</li> <li>(iii) The height of the resulting cut, filled areas or fill batter face in stable ground, not</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> </ul>

	<p>including any surcharge, does not exceed 2m, with a maximum slope of 1:2 (1 vertical to 2 horizontal);</p> <p>(iv) Areas exposed by earthworks are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</p> <p>(v) Sediment resulting from the earthworks is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths;</p> <p>(vi) Do not divert or change the nature of natural water flows, water bodies or established drainage paths;</p> <p>(vii) Do not result in the site being unable to be serviced by gravity sewers; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	<p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths</p> <p>(j) Land instability, erosion and sedimentation;</p> <p>(k) Proximity to underground services and service connections;</p> <p>(l) Traffic movements to and from the site; and</p> <p>(m) Consistency with the Rangitahi Peninsula Structure Plan; and</p> <p>(n) The risk of earthworks exacerbating Kauri dieback disease.</p>
<b>EW-R58</b>	Earthworks – general	
RPZ – Rangitahi Peninsula zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The importation of fill material to a site must meet the following conditions standards, in addition to the standards in EW-R57:</p> <p>(i) Does not exceed a total volume of 500m<sup>3</sup> per site and a depth of 1m;</p> <p>(ii) Is fit for compaction;</p> <p>(iii) The height of the resulting batter face in stable ground must not exceed 1.5m with a maximum slope of 1:2 (1m vertical to 2m horizontal);</p> <p>(iv) Does not restrict the ability for land to drain;</p> <p>(v) Is not located within 1.5m of public sewers, utility services or manholes; and</p> <p>(vi) The sediment from fill material is retained on the site; and</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths</p> <p>(j) Land instability, erosion and sedimentation;</p>

	<p>(vii) Provided they are not within a kauri root zone.</p>	<p>(k) Proximity to underground services and service connections;                  (l) Traffic movements to and from the site; and                  (m) Consistency with the Rangitahi Peninsula Structure Plan; and                  (n) The risk of earthworks exacerbating Kauri dieback disease.</p>
--	--	--

TKAZ – Te Kowhai airpark zone

<p><b>EW-R59</b></p>	<p>Earthworks – all precincts</p>	
<p>TKAZ – Te Kowhai airpark zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) In all precincts, earthworks within a site must meet all of the following standards:</li> <li>(i) Earthworks must be located more than 1.5m either side of a public sewer, open drain, overland flowpath or other service pipe;</li> <li>(ii) Earthworks must not exceed a volume of more than 1,000m<sup>3</sup> in a single calendar year;</li> <li>(iii) Earthworks must not exceed an area of more than 1,000m<sup>2</sup> in a single calendar year;</li> <li>(iv) The height of the resulting cut or batter face does not exceed 1.5m with a maximum slope of 1:2 (1m vertical to 2m horizontal);</li> <li>(v) Areas exposed by the earthworks not covered by buildings or other impervious surfaces are re-vegetated to achieve 80% ground cover within 2 months of the completion of the earthworks;</li> <li>(vi) Sediment is retained on the site through implementation and maintenance of erosion and sediment controls and does not enter waterways, open drains or overland flow paths; and</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and landscape effects;</li> <li>(b) Volume, extent and depth of earthworks;</li> <li>(c) Nature of fill material;</li> <li>(d) Contamination of fill material;</li> <li>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</li> <li>(f) Compaction of the fill material;</li> <li>(g) Volume and depth of fill material;</li> <li>(h) Geotechnical stability;</li> <li>(i) Flood risk, including natural water flows and established drainage paths;</li> <li>(j) Land instability, erosion and sedimentation;</li> <li>(k) Proximity to underground services and service connections; and.</li> <li>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</li> <li>(m) The risk of earthworks exacerbating Kauri dieback disease.</li> </ul>

	<p>(vii) Earthworks must not divert or change natural water flows or established drainage paths; and</p> <p>(viii) Provided they are not within a kauri root zone.</p>	
<b>EW-R60</b>	Earthworks – all precincts	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) In all precincts, the importation of fill material to a site must meet all of the following standards, in addition to the standards in EW-R59:</p> <p>(i) Earthworks do not exceed a total volume of 20m<sup>3</sup> per site and a depth of 1m;</p> <p>(ii) Earthworks must be fit for compaction;</p> <p>(iii) The height of the resulting batter face in stable ground must not exceed 1.5m with a maximum slope of 1:2 (1m vertical to 2m horizontal);</p> <p>(iv) Earthworks do not restrict the ability for land to drain;</p> <p>(v) Earthworks are not located within 1.5m of public sewers, utility services or manholes; and</p> <p>(vi) The sediment from fill material is retained on the site; and</p> <p>(vii) Provided they are not within a kauri root zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values and landscape effects;</p> <p>(b) Volume, extent and depth of earthworks;</p> <p>(c) Nature of fill material;</p> <p>(d) Contamination of fill material;</p> <p>(e) Location of the earthworks to waterways, significant indigenous vegetation and habitat;</p> <p>(f) Compaction of the fill material;</p> <p>(g) Volume and depth of fill material;</p> <p>(h) Geotechnical stability;</p> <p>(i) Flood risk, including natural water flows and established drainage paths;</p> <p>(j) Land instability, erosion and sedimentation;</p> <p>(k) Proximity to underground services and service connections; and.</p> <p>(l) Effects on the safe, effective and efficient operation, maintenance and upgrade of infrastructure, including access; and</p> <p>(m) The risk of earthworks exacerbating Kauri dieback disease.</p>

## LIGHT – Light

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Policies

LIGHT-PI Artificial outdoor lighting.

- (1) In the GRZ – General residential zone, LLRZ – Large lot residential zone and SETZ – Settlement zone:
  - (a) Provide for artificial outdoor lighting to enable night time work, farming activities, recreation activities, outdoor living, transport and security.
  - (b) Manage the adverse effects of glare and lighting to adjacent sites.
- (2) In the TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone ensure that:
  - (a) Artificial outdoor lighting enables night time work, recreation activities, outdoor living, transport and security (including the role of lighting in supporting CPTED);
  - (b) The intensity and direction of artificial lighting is managed so that significant glare and light spill to adjacent sites is minimised; and
- (3) In the BTZ – Business Tamahere zone:
  - (a) Provide for artificial outdoor lighting to enable night time work, recreation activities, outdoor dining, transport and security.
  - (b) Control the intensity and direction of artificial lighting to avoid significant glare and light spill on adjacent sites.
- (4) In the GRUZ – General rural zone, FUZ – Future urban zone, COR – Corrections zone and TTZ – TaTa Valley zone:
  - (a) Enable the use of artificial outdoor lighting for night-time work while minimising to the extent practicable effects on neighbouring sites.
  - (b) Ensure glare and light spill from permanently fixed artificial lighting does not compromise the amenity of adjacent sites.
- (5) In the RLZ – Rural lifestyle zone:
  - (a) Provide for artificial outdoor lighting to enable night time work, farming activities, recreation activities, outdoor living, transport and security.
  - (b) Control the intensity and direction of artificial lighting to avoid significant glare and light spill to adjacent sites.

LIGHT-P2 Artificial outdoor in all zones.

Ensure artificial outdoor lighting is installed and operated so that light spill does not compromise the safe operation of the transport network.

### Rules

*Land use – activities (zones as specified in the first column)*

<b>LIGHT-RI</b>	Glare and artificial light spill	
<ul style="list-style-type: none"> <li>• LLRZ – Large lot residential zone;</li> <li>GRZ – General residential zone;</li> <li>• MRZ1 – Medium density residential zone 1;</li> <li>• <u>MRZ2 – Medium density residential zone 2;</u></li> <li>• SETZ – Settlement zone;</li> <li>• BTZ – Business Tamahere zone;</li> <li>• MAZ – Mercer Airport zone;</li> <li>• MTZ – Matangi Zone;</li> <li>• RPZ – Rangitahi Peninsula zone; and</li> <li>• TKAZ – Te Kowhai Airpark zone.</li> </ul>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Illumination from glare and artificial light spill shall not exceed 10 lux measured horizontally and vertically within any other site.</li> <li>(b) In the LLRZ – Large lot residential, SETZ – Settlement zone and RPZ – Rangitahi Peninsula zone: <ul style="list-style-type: none"> <li>(i) LIGHT-RI(1)(a) does not apply to streetlights, navigation lights, traffic signals or from vehicles or equipment used in farming activities.</li> </ul> </li> <li>(c) In the MAZ – Mercer Airport zone: <ul style="list-style-type: none"> <li>(i) LIGHT-RI(1)(a) does not apply to runway lighting.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on other sites;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source; and</li> <li>(f) Mitigation measures.</li> </ul>
<b>LIGHT-R2</b>	Glare and artificial light spill	
<ul style="list-style-type: none"> <li>• GRUZ – General rural zone;</li> <li>• CORZ – Corrections zone;</li> <li>• FUZ – Future urban zone; and</li> <li>• TTZ – TaTa Valley zone.</li> </ul>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Illumination from glare and artificial light spill shall not exceed 10 lux measured horizontally and vertically at the notional boundary on any other site in the GRUZ – General Rural Zone; at any road boundary or within any other site in the GRZ – General residential zone, MRZ – Medium density residential zone, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large lot residential zone, SETZ – Settlement zone or RLZ – Rural lifestyle zone;</li> <li>(b) LIGHT-R2(1)(a) does not apply to vehicles used in farming activities and agricultural equipment.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Effects of light spill levels on other sites;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source;</li> <li>(f) Mitigation measures; and</li> <li>(g) Location and orientation of the light source.</li> </ul>
<b>LIGHT-R3</b>	Glare and artificial light spill	
<ul style="list-style-type: none"> <li>• LCZ – Local centre zone;</li> </ul>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Illumination from glare and artificial light spill must not</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

<ul style="list-style-type: none"> <li>• COMZ – Commercial zone; and</li> <li>• TCZ – Town centre zone</li> </ul>	<p>exceed 10 lux measured horizontally and vertically at any site zoned GRZ – General residential zone, MRZ – Medium density residential zone, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone, SETZ - Settlement Zone or RLZ – Rural Lifestyle Zone.</p>	<p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on other sites;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source; and</li> <li>(f) Mitigation measures.</li> </ul>
<p><b>LIGHT-R4</b> Glare and artificial light spill</p>		
<ul style="list-style-type: none"> <li>• GIZ – General industrial zone; and</li> <li>• HIZ – Heavy industrial zone</li> </ul>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Glare and artificial light spill that does not exceed 10 lux measured horizontally and vertically within any other site not located in the GIZ – General industrial zone or HIZ – Heavy industrial zone.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on another site;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source; and</li> <li>(f) Mitigation measures.</li> </ul>
<p><b>LIGHT-R5</b> Glare and artificial light spill</p>		
<ul style="list-style-type: none"> <li>• OSZ – Open space zone</li> </ul>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Illumination from glare and artificial light spill must not exceed 10 lux measured horizontally and vertically at any site zoned GRZ – General residential zone, MRZ – Medium density residential zone, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large Lot Residential zone, SETZ – Settlement zone, RPZ – Rangitahi Peninsula zone or RLZ – Rural Lifestyle zone.</li> <li>(b) LIGHT-R5(1)(a) does not apply to streetlights, navigation lights or from vehicles or equipment used in farming activities.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on other sites;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source; and</li> <li>(f) Mitigation measures.</li> </ul>
<p><b>LIGHT-R6</b> Glare and artificial light spill</p>		



<ul style="list-style-type: none"> <li>• HOPZ – Hopuhopu zone</li> </ul>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Illumination from glare and artificial light spill must not exceed 10 lux measured horizontally and vertically at the zone boundary;</li> <li>(b) LIGHT-R6(1)(a) does not apply to vehicles used in farming activities and agricultural equipment.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on other sites;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source;</li> <li>(f) Mitigation measures.</li> </ul>
<p><b>LIGHT-R7</b>      Glare and artificial light spill</p>		
<ul style="list-style-type: none"> <li>• KLZ – Kimihia Lakes zone</li> </ul>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Illumination from glare and artificial light spill must not exceed 10 lux measured horizontally and vertically from the boundary of a site that is within a separate zone; and</li> <li>(b) LIGHT-R7(1)(a) does not apply to streetlights, navigation lights or from vehicles or equipment used in farming activities.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on other sites;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source;</li> <li>(f) Mitigation measures.</li> </ul>
<p><b>LIGHT-R8</b>      Glare and artificial light spill</p>		
<ul style="list-style-type: none"> <li>• MSRZ – Motorsport and recreation zone</li> </ul>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Glare and artificial light spill must not exceed 20 lux measured horizontally and vertically outside the zone boundary.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Light spill levels on another site;</li> <li>(c) Road safety;</li> <li>(d) Duration and frequency;</li> <li>(e) Location and orientation of the light source; and</li> <li>(f) Mitigation measures.</li> </ul>

## NOISE – Noise

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Policies

NOISE-PI Noise.

- (I) Adverse effects of noise generated within the zone on sensitive land uses are minimised by:
- (a) In the GRZ – General residential zone, LLRZ – Large lot residential zone, SETZ – Settlement zone, TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone:
    - (i) Ensuring that the maximum sound levels are compatible with the amenity values of any adjacent GRZ – General residential zone, MRZ1 – Medium density residential zone 1, [MRZ2 – Medium density residential zone 2](#), LLRZ – Large lot residential zone or SETZ – Settlement zone;
    - (ii) Limiting the timing and duration of noise-generating activities, including construction and demolition activities;
    - (iii) Maintaining appropriate setback distances between high noise environments and sensitive land uses; and
  - (b) In GRZ – General residential zone, LLRZ – Large lot residential zone, SETZ – Settlement zone and RLZ – Rural lifestyle zone:
    - (i) Managing the location of sensitive land uses, particularly in relation to lawfully established high noise generating activities; and
    - (ii) Requiring acoustic insulation where sensitive land uses and noise-sensitive activities are located within high noise environments.
  - (c) In the TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone:
    - (i) Limiting the timing and duration of servicing and operation of commercial activities; and
    - (ii) Requiring acoustic insulation for dwellings within the zone.

NOISE-P2 Noise in the RLZ – Rural lifestyle zone.

- (I) The adverse effects of noise on the character and amenity of the RLZ – Rural lifestyle zone are minimised by:
- (a) Ensuring that the maximum sound levels are compatible with the surrounding land uses;
  - (b) Limiting the timing and duration of noise-generating activities, including construction and demolition activities;
  - (c) Maintaining appropriate setback distances between high noise environments and noise-sensitive activities.

**NOISE-P3** Noise and vibration in the GRUZ – General rural zone.

- (1) Manage the adverse effects of noise and vibration by:
- (a) Ensuring that noise and vibration levels do not compromise rural amenity;
  - (b) Limiting the timing and duration of noise-generating activities to the extent practicable and appropriate;
  - (c) Maintaining appropriate separation between high noise environments and noise sensitive activities;
  - (d) Ensuring frost fans are located and operated to minimise to the extent practicable noise effects on other sites;
  - (e) Managing the location of sensitive land uses, particularly in relation to lawfully-established activities;
  - (f) Requiring acoustic insulation where sensitive land uses are located within high noise environments, including the Airport Noise Outer Control Boundary, Huntly Power Station, and the Gun Club Noise Control Boundary;
  - (g) Managing the adverse effects of vibration from quarrying activities by limiting the timing and duration of blasting activities and maintaining sufficient setback distances from residential units or identified building platforms on another site; and
  - (h) Managing noise to minimise as far as practicable effects on existing noise sensitive activities.

**NOISE-P4** Noise in the BTZ – Business Tamahere zone.

- (1) Adverse effects of noise on sensitive land uses are minimised by:
- (a) Ensuring that the maximum sound levels are compatible with activities permitted in the BTZ – Business Tamahere zone and the adjacent RLZ – Rural lifestyle zone;
  - (b) Limiting the timing and duration of noise-generating activities, including construction and demolition activities; and
  - (c) Limiting the timing and duration of servicing and operation of commercial activities.

**Rules**

*Land use – activities (zones specified in first column)*

<p><b>NOISE-RI</b></p> <ul style="list-style-type: none"> <li>• LLRZ – Large lot residential zone;</li> <li>• GRZ – General residential zone;</li> <li>• RLZ – Rural lifestyle zone (including the Tamahere Commercial Areas A and B);</li> <li>• SETZ – Settlement zone; and</li> <li>• RPZ – Rangitahi Peninsula zone.</li> </ul>	<p>Noise – general</p>	
	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Farming noise, and noise generated by emergency generators and emergency sirens.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

<b>NOISE-R2</b>	Noise – general	
<ul style="list-style-type: none"> <li>• GRUZ – General rural zone;</li> <li>• CORZ – Corrections zone; and</li> <li>• FUZ – Future urban zone.</li> </ul>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Farming noise, and noise generated by hunting, emergency generators and emergency sirens.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NOISE-R3</b>	Noise – general	
<ul style="list-style-type: none"> <li>• MRZ<sup>1</sup> – Medium density residential zone <sup>1</sup>;</li> <li>• <a href="#">MRZ2 – Medium density residential zone 2</a>;</li> <li>• LCZ – Local centre zone;</li> <li>• COMZ – Commercial zone;</li> <li>• TCZ – Town centre zone;</li> <li>• GIZ – General industrial zone (including PREC6 – Horotiu industrial park precinct);</li> <li>• HIZ – Heavy industrial zone (including Huntly Power Station);</li> <li>• BTZ – Business Tamahere zone;</li> <li>• MTZ – Matangi zone; and</li> <li>• TKAZ – Te Kowhai Airpark zone.</li> </ul>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise generated by emergency generators and emergency sirens.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>NOISE-R4</b>	Noise – construction	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise from any construction, maintenance, or demolition activity that is measured, assessed and managed in accordance with the requirements of NZS6803:1999 ‘Acoustics – Construction Noise’.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Hours and days of construction;</p> <p>(c) Noise levels;</p> <p>(d) Timing and duration; and</p> <p>(e) Methods of construction.</p>

LLRZ – Large lot residential zone

<b>NOISE-R5</b>	Noise – general	
LLRZ – Large lot residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any other site in the LLRZ – Large lot residential zone must not exceed:</p> <p>(i) 50dB (L<sub>Aeq</sub>), 7am to 7pm, every day;</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>(ii) 45dB (L<sub>Aeq</sub>), 7pm to 10pm, every day; and</p> <p>(iii) 40dB (L<sub>Aeq</sub>) and 65dB (L<sub>Amax</sub>), 10pm to 7am the following day.</p> <p>(b) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 “Acoustics Measurement of Environmental Sound”; and</p> <p>(c) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustic Environmental noise”.</p>	
--	---	--

GRZ – General residential zone

<b>NOISE-R6</b>	Noise – general	
GRZ – General residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any other site in the GRZ – General residential zone must not exceed:</p> <p>(i) 50dB L<sub>Aeq(15min)</sub>, 7am to 7pm, every day;</p> <p>(ii) 45dB L<sub>Aeq(15min)</sub>, 7pm to 10pm, every day; and</p> <p>(iii) 40dB L<sub>Aeq(15min)</sub>, 10pm to 7am the following day; and</p> <p>(iv) 65dB L<sub>Amax</sub>, 10pm to 7am the following day.</p> <p>(b) Noise levels shall be measured in accordance with the requirements of NZS6801:2008 “Acoustics - Measurement of Environmental Sound”; and</p> <p>(c) Noise levels shall be assessed in accordance with the requirements of NZS6802:2008 “Acoustic - Environmental noise”.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

MRZ<sub>1</sub> – Medium density residential zone 1 and MRZ<sub>2</sub> – Medium density residential zone 2

<b>NOISE-R7</b>	Noise – general	
MRZ <sub>1</sub> – Medium density residential	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<p>zone <u>1</u> and <u>MRZ2</u> – <u>Medium density residential zone 2</u></p>	<p>(a) Noise measured within any other site in the <u>MRZ1</u> – <u>Medium density residential zone 1</u> or <u>MRZ2 – Medium density residential zone 2</u> must not exceed:</p> <ul style="list-style-type: none"> <li>(i) 50dB <math>L_{Aeq(15min)}</math>, 7am to 7pm, every day;</li> <li>(ii) 45dB <math>L_{Aeq(15min)}</math> 7pm to 10pm every day;</li> <li>(iii) 40dB <math>L_{Aeq(15min)}</math> 10pm to 7am the following day; and</li> <li>(iv) 65dB <math>L_{Amax(15min)}</math>, 10pm to 7am the following day.</li> </ul> <p>(b) Noise levels shall be measured in accordance with the requirements of NZS 6801:2008 ‘Acoustics Measurement of Environmental Sound’; and</p> <p>(c) Noise levels shall be assessed in accordance with the requirements of NZS6802:2008 ‘Acoustics – Environmental Noise’.</p>	
---	---	--

GRUZ – General rural zone

<b>NOISE-R8</b>	Noise – general	
<p>GRUZ – General rural zone</p>	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Noise measured at the notional boundary on any other site in the GRUZ – General Rural Zone must not exceed:                             <ul style="list-style-type: none"> <li>(i) 50dB <math>L_{Aeq}</math>, 7am to 7pm every day;</li> <li>(ii) 45dB <math>L_{Aeq}</math>, 7pm to 10pm every day;</li> <li>(iii) 40dB <math>L_{Aeq}</math> and 65dB <math>L_{Amax}</math>, 10pm to 7am the following day.</li> </ul> </li> <li>(b) Noise measured within any site in any zone, other than the GRUZ – General rural zone, must meet the permitted noise levels for that zone.</li> <li>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p>“Acoustics – Measurement of Environmental Sound”.</p> <p>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustic – Environmental noise”.</p>	
<b>NOISE-R9</b>	Frost fans	
GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise generated by a frost fan must not exceed 55dB <math>L_{Aeq}</math> when measured at the notional boundary on any site in the GRUZ – General rural zone and within any site in the MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, RLZ – Rural lifestyle zone, SETZ - Settlement zone or GRZ – General residential zone.</p> <p>(b) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</p> <p>(c) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 Acoustic- Environmental noise.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) The location and proximity of the fans to sensitive activities;</p> <p>(c) Noise levels;</p> <p>(d) The adequacy of any mitigation.</p>
<b>NOISE-R10</b>	Noise – extractive activity	
GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise generated by extractive activity from a facility existing or operating under resource consent at 17 January 2022, shall be measured at the notional boundary of any residential unit existing at 25 September 2004, or at any site in a GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ –</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p>Settlement zone or RLZ – Rural lifestyle zone;</p> <p>(b) Noise generated by new extractive activity located within a Coal Mining Area, Aggregate Extraction Area, or Extractive Resource Area shall be measured at the notional boundary of any residential, or at any site in a GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone or RLZ – Rural lifestyle zone;</p> <p>(c) Noise generated from extractive activity subject to clause (a) or (b) shall not exceed:</p> <p>(i) 55dB L<sub>Aeq</sub>, 7am to 7pm Monday to Friday;</p> <p>(ii) 55dB L<sub>Aeq</sub>, 7am to 6pm Saturday;</p> <p>(iii) 50dB L<sub>Aeq</sub>, 7pm to 10pm Monday to Friday;</p> <p>(iv) 50dB L<sub>Aeq</sub>, 7am to 6pm Sundays and Public Holidays;</p> <p>(v) 45dB L<sub>Aeq</sub> and 70dB L<sub>AFmax</sub> at all other times including Public Holidays;</p> <p>(d) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 “Acoustics – Measurement of Environmental Sound”;</p> <p>(e) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustic – Environmental noise”.</p>	
--	---	--

RLZ – Rural lifestyle zone

<b>NOISE-RI I</b>	Noise – general	
RLZ – Rural lifestyle zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured in accordance with NZS 6801:2008 and assessed in accordance with</p>	<p><b>(2) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) Noise that is outside the scope of NZS 6802:2008; or</p>



Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>NZS 6802:2008 must not exceed the following noise limits at any point within a notional boundary on any other site in the RLZ – Rural lifestyle zone:</p> <p>(i) 50dB L<sub>Aeq</sub> (15min), 7am to 7pm every day;</p> <p>(ii) 45dB L<sub>Aeq</sub> (15min), 7pm to 10pm every day;</p> <p>(iii) 40dB L<sub>Aeq</sub> (15min) 10pm to 7am the following day;</p> <p>(iv) 65dB L<sub>AFmax</sub>, 10pm to 7am the following day.</p> <p>(b) The permitted activity noise limits for the zone of any other site where sound is received.</p>	<p>(b) A permitted activity standard; or</p> <p>(c) Does not comply with NOISE-R11(1)(a)</p>
<b>NOISE-R12</b>	Noise – Tamahere Commercial Areas A and B	
RLZ – Rural lifestyle zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured in accordance with NZS 6801:2008 and assessed in accordance with NZS 6802:2008 must not exceed:</p> <p>(i) The following noise limits at any point within any other site in Tamahere Commercial Areas A and B:</p> <p>(1) 65dB L<sub>Aeq</sub>(15min), 7am to 10pm;</p> <p>(2) (ii)50dB L<sub>Aeq</sub>(15min), 10pm to 7am;</p> <p>(3) (iii)75 dB L<sub>AFmax</sub>, 10pm to 7am the following day.</p> <p>(ii) The following noise limits at any point within any site outside the Tamahere Commercial Areas A and B:</p> <p>(1) 55dB L<sub>Aeq</sub>(15min), 7am to 10pm;</p> <p>(2) 40dB L<sub>Aeq</sub>(15min), 10pm to 7am;</p> <p>(3) 70dB L<sub>AFmax</sub>, 10pm to 7am the following day.</p>	<p><b>(2) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) Noise that is outside the scope of NZS 6802:2008; or</p> <p>(b) A permitted activity standard; or</p> <p>(c) Does not comply with NOISE-R12(1)(a)</p>

SETZ – Settlement zone

<b>NOISE-R13</b>	Noise – general
------------------	-----------------

<p>SETZ – Settlement zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Noise measured within any other site in the SETZ – Settlement zone must not exceed:</p> <p>(i) 50dB (<math>L_{Aeq}</math>), 7am to 7pm, every day;</p> <p>(ii) 45dB (<math>L_{Aeq}</math>), 7pm to 10pm, every day; and</p> <p>(iii) 40dB (<math>L_{Aeq}</math>) and 65dB (<math>L_{Amax}</math>), 10pm to 7am the following day.</p> <p>(b) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 “Acoustics Measurement of Environmental Sound”; and</p> <p>(c) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustic Environmental noise”.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
-------------------------------	--	--

LCZ – Local centre zone rules

<p><b>NOISE-RI4</b> Noise – general</p>		
<p>LCZ – Local centre zone rules</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Noise measured within any:</p> <p>(i) In the LCZ – Local centre zone must not exceed:</p> <p>(1) 65dB <math>L_{Aeq (15min)}</math>, 7am to 11pm every day; and</p> <p>(2) 55dB <math>L_{Aeq (15min)}</math>, 11pm to 7am the following day; and</p> <p>(3) 85dB <math>L_{Amax}</math>, 11pm to 7am the following day; or</p> <p>(ii) In the GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone and SETZ - Settlement Zone must not exceed:</p> <p>(1) 55dB <math>L_{Aeq (15min)}</math>, 7am to 7pm; and</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>(2) 50dB <math>L_{Aeq (15min)}</math>, 7pm to 10pm; and</p> <p>(3) 40dB <math>L_{Aeq (15min)}</math>, 10pm to 7am the following day; and</p> <p>(4) 65dB <math>L_{Amax}</math>, 10pm to 7am the following day.</p> <p>(iii) Noise measured within any site in any zone other than the LCZ – Local centre zone, GRZ – General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone or SETZ - Settlement Zone must meet the permitted noise levels for that zone.</p> <p>(b) Noise levels must be measured in accordance with the requirements of NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</p> <p>(c) Noise levels must be assessed in accordance with the requirements of NZS 6802:2008 Acoustics - Environmental.</p>	
--	--	--

COMZ – Commercial zone

<b>NOISE-RI5</b>	Noise – general	
COMZ – Commercial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any:</p> <p>(i) In the COMZ – Commercial zone must not exceed:</p> <p>(1) 65dB <math>L_{Aeq (15min)}</math>, 7am to 11pm every day; and</p> <p>(2) 55dB <math>L_{Aeq (15min)}</math>, 11pm to 7am the following day; and</p> <p>(3) 85dB <math>L_{Amax}</math>, 11pm to 7am the following day; or</p> <p>(ii) In the GRZ – General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone and SETZ - Settlement Zone must not exceed:</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p>(1) 55dB <math>L_{Aeq(15min)}</math>, 7am to 7pm; and</p> <p>(2) 50dB <math>L_{Aeq(15min)}</math>, 7pm to 10pm; and</p> <p>(3) 40dB <math>L_{Aeq(15min)}</math>, 10pm to 7am the following day; and</p> <p>(4) 65dB <math>L_{Amax}</math>, 10pm to 7am the following day.</p> <p>(iii) Noise measured within any site in any zone other than the LCZ – Local centre zone, GRZ – General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone or SETZ - Settlement Zone must meet the permitted noise levels for that zone.</p> <p>(b) Noise levels must be measured in accordance with the requirements of NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</p> <p>(c) Noise levels must be assessed in accordance with the requirements of NZS 6802:2008 Acoustics - Environmental.</p>	
--	---	--

TCZ – Town centre zone

<b>NOISE-RI 6</b>	Noise – general	
TCZ – Town centre zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any</p> <p>(i) In the TCZ – Town Centre zone must not exceed:</p> <p>(1) 65dB <math>L_{Aeq(15min)}</math>, 7am to 11pm every day; and</p> <p>(2) 55dB <math>L_{Aeq(15min)}</math>, 11pm to 7am the following day; and</p> <p>(3) 85dB <math>L_{Amax}</math>, 11pm to 7am the following day; or</p> <p>(ii) In the GRZ – General residential zone, MRZ – Medium density residential zone, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p>zone and SETZ – Settlement zone must not exceed:</p> <p>(1) 55dB L<sub>Aeq</sub> (15min), 7am to 7pm; and</p> <p>(2) 50dB L<sub>Aeq</sub> (15min), 7pm to 10pm; and</p> <p>(3) 40dB L<sub>Aeq</sub> (15min), 10pm to 7am the following day; and</p> <p>(4) 65dB L<sub>Amax</sub>, 10pm to 7am the following day.</p> <p>(iii) Noise measured within any site in any zone other than the TCZ – Town Centre zone, GRZ – General Residential Zone, MRZ<sub>1</sub> – Medium density residential zone 1, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large Lot Residential Zone or SETZ - Settlement Zone must meet the permitted noise levels for that zone.</p> <p>(iv) Noise levels must be measured in accordance with the requirements of NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</p> <p>(v) Noise levels must be assessed in accordance with the requirements of NZS 6802:2008 Acoustics - Environmental.</p>	
--	--	--

*GIZ – General industrial zone*

<b>NOISE-RI7</b>	Noise – general	
GIZ – General industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any other site:</p> <p>(i) In a GIZ – General industrial zone or HIZ – Heavy industrial zone that does not exceed 75dB L<sub>Aeq</sub> at any time.</p> <p>(b) Noise measured within any site in any zone, other than the General Industrial Zone and the Heavy Industrial Zone, that does</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values</p> <p>(b) Hours and days of operation</p> <p>(c) Location of noise sources in relation to any boundary</p> <p>(d) Frequency or other special characteristics of noise</p> <p>(e) Mitigation measures</p> <p>(f) Noise levels and duration.</p>

	<p>not exceed the permitted noise levels for that zone.</p> <p>(c) Noise levels that are measured in accordance with the requirements of NZS 6801:2008 “Acoustics - Measurement of Environmental Sound”.</p> <p>(d) Noise levels that are assessed in accordance with the requirements of NZS 6802:2008 “Acoustics - Environmental noise”.</p>	
<p><b>NOISE-RI8</b></p>	<p>Noise in Pokeno</p>	
<p>GIZ – General industrial zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Noise measured within any other site:</p> <p>(i) In the HIZ – Heavy industrial zone in Pokeno that does not exceed:</p> <p style="padding-left: 40px;">(I) 70dB <math>L_{Aeq}</math> at any time</p> <p>(ii) In the GIZ – General industrial zone in Pokeno that does not exceed:</p> <p style="padding-left: 40px;">(I) 65dB <math>L_{Aeq}</math> at any time.</p> <p>(b) Noise measured within any site in any zone, other than the GIZ – General industrial zone and HIZ – Heavy industrial zone, that does not exceed the permitted noise limits for that zone. For sites adjoining PREC4 – Havelock precinct (refer APPI4 – Havelock precinct plan), the noise rating level from any activity must not exceed:</p> <p>(i) 55dB <math>L_{Aeq}</math> 7am to 10pm every day, 45 dB <math>L_{Aeq}</math> 10pm to 7am the following day and 75 dB <math>L_{AFmax}</math> from 10pm to 7am the following day measured from any site outside of the Pōkeno Industry Buffer illustrated on the planning maps (compliance with the noise standard must not be measured from the GRZ – General residential zone boundary for PREC4 – Havelock precinct).</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;          (b) Hours and days of operation;          (c) Location of noise sources in relation to any boundary;          (d) Frequency or other special characteristics of noise;          (e) Mitigation measures; and          (f) Noise levels and duration.</p>

	<p>(ii) Until the acoustic barrier has been constructed and made acoustically effective in accordance with Rule SUB-R21(1)(a)(v), the noise rating level from activities on Lots 3 and 4 DP 492007 must not exceed 55dB L<sub>Aeq</sub> 7am to 10pm every day, 45 dB L<sub>Aeq</sub> 10pm to 7am the following day and 75 dB L<sub>AFmax</sub> from 10pm to 7am the following day measured from the unmitigated 45 dB L<sub>Aeq</sub> noise contour illustrated in APP14 – Havelock precinct plan. When Rule SUB-R21(1)(a)(v) has been satisfied, clause (b)(i) above applies.</p> <p>(c) Noise levels that are measured in accordance with the requirements of NZS 6801:2008 “Acoustics Measurements of Environmental Sound”;</p> <p>(d) Noise levels that are assessed in accordance with the requirements of NZS 6802:2008 “Acoustics Environmental Noise”.</p>	
<p><b>NOISE-RI9</b></p>	<p>Noise – general in PREC6 – Horotiu industrial park precinct</p>	
<p>PREC6 – Horotiu industrial park precinct</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Noise from an activity in the Horotiu Industrial Park that does not exceed:</p> <p>(i) 75dBA L<sub>Aeq</sub> at any time measured within any other site.</p> <p>(b) Noise from an activity in the Horotiu Industrial Park that does not exceed the following limits when measured within a GRZ – General residential zone:</p> <p>(i) 55dBA L<sub>Aeq</sub> 7am to 10pm; or</p> <p>(ii) 45dBA L<sub>Aeq</sub> and 70dBA L<sub>Amax</sub> 10pm to 7am the following day.</p> <p>(c) Noise from an activity in the Horotiu Industrial Park that does not exceed the following limits when measured within the notional boundary of any</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Hours of operation;</p> <p>(c) Location of noise sources in relation to boundaries;</p> <p>(d) Frequency or other special characteristics of noise;</p> <p>(e) Noise levels and duration; and</p> <p>(f) Mitigation measures.</p>

	<p>building containing a noise-sensitive activity existing at 17 January 2022 within any zone outside of the Horotiu Industrial Park and HIZ – Heavy industrial zone (except the GRZ – General residential zone):</p> <p>(i) 55dBA <math>L_{Aeq}</math> 7am to 10pm;</p> <p>(ii) 45dBA <math>L_{Aeq}</math> and 70dBA <math>L_{Amax}</math> 10pm to 7am the following day.</p> <p>(d) Noise levels that is measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 “Acoustics - Measurement of Environmental Sound”.</p> <p>(e) Noise levels that is assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustics- Environmental noise”.</p> <p>(f) NOISE-R17 does not apply.</p>	
--	---	--

*HIZ – Heavy industrial zone*

<b>NOISE-R20</b>	Noise – general	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any other site:</p> <p>(i) In the HIZ – Heavy industrial zone or GIZ – General industrial zone must that does not exceed 75dB <math>L_{Aeq}</math> at any time.</p> <p>(b) Noise measured within a site in any zone, other than the HIZ – Heavy industrial zone and the GIZ – General industrial zone, that does not exceed the permitted noise levels for that zone;</p> <p>(c) Noise levels that are measured in accordance with the requirements of NZS 6801:2008 “Acoustics – Measurement of Environmental Sound”; and</p> <p>(d) Noise levels that are assessed in accordance with the requirements of NZS 6802:2008</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Hours and days of operation;</p> <p>(c) Location of noise sources in relation to any boundary;</p> <p>(d) Frequency or other special characteristics of noise;</p> <p>(e) Mitigation measures; and</p> <p>(f) Noise levels and duration.</p>



	“Acoustics – Environmental Noise”.	
<b>NOISE-R21</b>	Noise – Pokeno	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any other site:</p> <p>(i) In the HIZ – Heavy industrial zone in Pokeno that does not exceed 70dB L<sub>Aeq</sub> at any time; or</p> <p>(ii) In the GIZ – General industrial zone in Pokeno that does not exceed 65dB L<sub>Aeq</sub> at any time.</p> <p>(b) Noise measured within any site in any zone, other than the GIZ – General industrial zone and HIZ – Heavy industrial zone, that does not exceed the permitted noise limits for that zone. For sites adjoining PREC4 – Havelock precinct (refer APPI4 – Havelock precinct plan), the noise rating level from any activity must not exceed:</p> <p>(i) 55dB L<sub>Aeq</sub> 7am to 10pm every day, 45 dB L<sub>Aeq</sub> 10pm to 7am the following day and 75 dB L<sub>AFmax</sub> from 10pm to 7am the following day measured from any site outside of the Pokeno Industry Buffer illustrated on the planning maps (compliance with the noise standard must not be measured from the GRZ – General residential zone boundary for PREC4 – Havelock precinct).</p> <p>(ii) Until the acoustic barrier has been constructed and made acoustically effective in accordance with Rule SUB-R21(1)(a)(v), the noise rating level from activities on Lots 3 and 4 DP 492007 must not exceed 55dB L<sub>Aeq</sub> 7am to 10pm every day, 45 dB L<sub>Aeq</sub> 10pm to 7am the following day and 75 dB L<sub>AFmax</sub> from 10pm to 7am the following</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Hours of operation;</p> <p>(c) Location of noise sources in relation to any boundary;</p> <p>(d) Frequency or other special characteristics of noise;</p> <p>(e) Mitigation measures; and</p> <p>(f) Noise levels and duration.</p>

	<p>day measured from the unmitigated 45 dB L<sub>Aeq</sub> noise contour illustrated in APP14 – Havelock precinct plan. When Rule SUB-R21(1)(a)(v), has been satisfied, clause (b)(i) above applies.</p> <p>(c) Noise levels that are measured in accordance with the requirements of NZ 6801:2008 “Acoustics Measurements of Environmental Sound”; and</p> <p>(d) Noise levels that are assessed in accordance with the requirements of NZS 6802:2008 “Acoustics Environmental Noise”.</p>	
<p><b>NOISE-R22</b></p>	<p>Noise – Huntly Power Station</p>	
<p>HIZ – Heavy industrial zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within the notional boundary of any residential unit that has existed since 25 September 2004 in the General Rural Zone that does not exceed:</p> <p>(i) 55dB L<sub>Aeq</sub> 7am to 10pm; and</p> <p>(ii) 45dB L<sub>Aeq</sub> and 75dB L<sub>Amax</sub> 10pm to 7am the following day.</p> <p>(b) Noise measured within any site in the GRZ – General residential zone, or <u>MRZ1 – Medium density residential zone 1</u> or <u>MRZ2 – Medium density residential zone 2</u>, where a residential unit has existed since 25 September 2004, that does not exceed:</p> <p>(i) 50dB L<sub>Aeq</sub> 7am to 7pm;</p> <p>(ii) 45dB L<sub>Aeq</sub> 7pm to 10pm; and</p> <p>(iii) 40 dB L<sub>Aeq</sub> and 65 dB L<sub>Amax</sub> 10pm to 7am the following day.</p> <p>(c) Noise levels that are measured in accordance with the requirements of NZS 6801:2008 “Acoustics Measurement of Environmental Sound”; and</p> <p>(d) Noise levels that are assessed in accordance with the requirements of NZS 6802:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Hours and days of operation;</p> <p>(c) Location of noise sources in relation to any boundary;</p> <p>(d) Frequency or other special characteristics of noise;</p> <p>(e) Mitigation measures; and</p> <p>(f) Noise levels and duration.</p>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	2008 “Acoustics Environmental Noise”.	
--	---------------------------------------	--

OSZ – Open space zone

<b>NOISE-R23</b>	Noise – general	
OSZ – Open space zone	<b>(1) Activity status: PER</b> <b>Where:</b> (a) Crowd noise, noise generated by emergency generator and emergency sirens.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NOISE-R24</b>	Noise – general	
OSZ – Open space zone	<b>(1) Activity status: PER</b> <b>Where:</b> (a) Noise measured in accordance with NZS 6801:2008 and assessed in accordance with NZS 6802:2008 must not exceed the permitted activity noise limits for the zone of any other site where sound is received.	<b>(2) Activity status where compliance not achieved: DIS</b>

BTZ – Business Tamahere zone

<b>NOISE-R25</b>	Noise – general	
BTZ – Business Tamahere zone	<b>(1) Activity status: PER</b> <b>Where:</b> (a) Noise measured within the BTZ – Business Tamahere zone must not exceed: (i) 65dB L <sub>Aeq(15min)</sub> , 7am to 11 pm every day; and (ii) 55dB L <sub>Aeq(15min)</sub> , 11pm Friday to 1am Saturday; and (iii) 55dB L <sub>Aeq(15min)</sub> , 11pm Saturday to 1am Sunday; and (iv) 45dB L <sub>Aeq(15min)</sub> 1am to 7am every day, and (v) 75dB L <sub>Amax</sub> , 11pm to 7am every day. (b) Noise measured at the notional boundary within any site in the RLZ – Rural lifestyle zone, must not exceed: (c) 50dB L <sub>Aeq(15min)</sub> , 7am to 7pm every day; (d) 45dB L <sub>Aeq(15min)</sub> , 7pm to 10pm every day; and	<b>(2) Activity status where compliance not achieved: DIS</b>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>(e) 40dB <math>L_{Aeq(15min)}</math>, 10pm to 7am every day; and</p> <p>(f) 65dB <math>L_{Amax}</math>, 10pm to 7am every day.</p> <p>(g) Noise levels must be measured in accordance with the requirements of NZS 6801:2008 'Acoustics Measurement of Environmental Sound'; and</p> <p>(h) Noise levels must be assessed in accordance with the requirements of NZS 6802:2008 'Acoustic Environmental noise'.</p>	
--	---	--

*CORZ – Corrections zone*

<b>NOISE-R26</b>	Noise – general	
CORZ – Corrections zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured at the notional boundary on any other site in the CORZ – Corrections zone must not exceed:</p> <p>(i) 50dB <math>L_{Aeq}</math>, 7am to 7pm every day;</p> <p>(ii) 45dB <math>L_{Aeq}</math>, 7pm to 10pm every day;</p> <p>(iii) 40dB <math>L_{Aeq}</math> and 65dB <math>L_{Amax}</math>, 10pm to 7am the following day.</p> <p>(b) Noise measured within any site in any zone, other than the CORZ – Corrections zone, must meet the permitted noise levels for that zone.</p> <p>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 "Acoustics – Measurement of Environmental Sound".</p> <p>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 "Acoustic – Environmental noise".</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

*FUZ – Future urban zone*

<b>NOISE-R27</b>	Noise – general	
------------------	-----------------	--

<p>FUZ – Future urban zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Noise measured at the notional boundary on any other site in the FUZ – Future urban zone must not exceed: <ul style="list-style-type: none"> <li>(i) 50dB L<sub>Aeq</sub>, 7am to 7pm every day;</li> <li>(ii) 45dB L<sub>Aeq</sub>, 7pm to 10pm every day;</li> <li>(iii) 40dB L<sub>Aeq</sub> and 65dB L<sub>Amax</sub>, 10pm to 7am the following day.</li> </ul> </li> <li>(b) Noise measured within any site in any zone, other than the FUZ – Future, urban zone must meet the permitted noise levels for that zone.</li> <li>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 “Acoustics – Measurement of Environmental Sound”.</li> <li>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustic – Environmental noise”.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>NOISE-R28</b> Frost fans</p>		
<p>FUZ – Future urban zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Noise generated by a frost fan must not exceed 55dB L<sub>Aeq</sub> when measured at the notional boundary on any site in the FUZ – Future urban zone and within any site in the MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, RLZ – Rural lifestyle zone, SETZ - Settlement zone or GRZ – General residential zone.</li> <li>(b) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) The location and proximity of the fans to sensitive activities;</li> <li>(c) Noise levels;</li> <li>(d) The adequacy of any mitigation.</li> </ul>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	(c) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 Acoustic- Environmental noise.	
--	--	--

HOPZ – Hopuhopu zone

<b>NOISE-R29</b>	Noise – general	
HOPZ – Hopuhopu zone	<b>(1) Activity status: PER</b> <b>Where:</b> (a) Farming noise, crowd noise, and noise generated by hunting, emergency generators and emergency sirens.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>NOISE-R30</b>	Noise – general	
HOPZ – Hopuhopu zone	<b>(1) Activity status: PER</b> <b>Where:</b> (a) Noise generated within the HOPZ – Hopuhopu zone when measured at the zone boundary must meet the permitted noise levels for the neighbouring zone. (b) Noise levels shall be measured in accordance with the requirements of NZS 6801:2008 Acoustics - Measurement of Environmental Sound; and (c) Noise levels shall be assessed in accordance with the requirements of NZS 6802:2008 Acoustic- Environmental noise.	<b>(2) Activity status where compliance not achieved: DIS</b>

KLZ – Kimihia lakes zone

<b>NOISE-R31</b>	Noise – general	
KLZ – Kimihia lakes zone	<b>(1) Activity status: PER</b> <b>Where:</b> (a) All activities must comply with the following noise standards: (i) Noise measured within the notional boundary on any site in the GRZ – General residential zone or the GRUZ - General rural zone must not exceed: (1) 55dB L <sub>Aeq</sub> , 7am to 7pm every day; (2) 45dB L <sub>Aeq</sub> , 7pm to 10pm every day; and	<b>(2) Activity status where compliance not achieved: DIS</b>

	<p>(3) 40dB <math>L_{Aeq}</math> and 65dB <math>L_{Amax}</math>, 10pm to 7am the following day.</p> <p>(b) Noise measured within any site in any other zone not specified above must meet the noise levels permitted for that zone.</p> <p>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 Acoustics - Measurement of environmental sound.</p> <p>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 Acoustics - Environmental noise.</p>	
<b>NOISE-R32</b> Noise – Noise Management Plan		
<p>KLZ – Kimihia lakes zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Prior to development, a Noise Management Plan must be prepared and in place at all times that details the measures to be implemented to ensure that noise within the site does not exceed the limits specified in Rule NOISE-R31.</p> <p>(i) The Noise Management Plan must as a minimum, provide details of the following measures:</p> <p>(ii) Procedures and protocols for the setting up, installation and monitoring responsibilities (including reporting) of the noise monitoring device (microphone) located within the Kimihia Lakes development;</p> <p>(iii) Procedures for the ongoing testing and calibration of the noise monitoring device (microphone);</p> <p>(iv) The erection of any necessary barriers for the purpose of reducing noise emissions;</p> <p>(v) The design and operation of any public address system</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>with respect to management of noise emissions;</p> <p>(vi) Procedures to monitor all activities and events that may meet the noise levels specified in Rule NOISE-31.</p>	
--	--	--

MAZ – Mercer airport zone

<b>NOISE-R33</b>	Noise – non-aviation related	
MAZ – Mercer airport zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise from any non-aviation related activity in the MAZ – Mercer Airport zone must not exceed the following noise limits when measured at the notional boundary of a site within the GRUZ – General Rural zone:</p> <p>(i) 55 dB L<sub>Aeq</sub>, 7am to 10pm every day; and</p> <p>(ii) 40 dB L<sub>Aeq</sub> and 70 dB L<sub>afmax</sub>, 10pm to 7am the following day.</p> <p>(b) NOISE-R33(1)(a) does not apply to:</p> <p>(i) Construction noise; or</p> <p>(ii) Noise from emergency sirens.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>NOISE-R34</b>	Noise – aircraft operations	
MAZ – Mercer airport zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise from aircraft operations in the MAZ – Mercer Airport zone shall not exceed 65 dBA L<sub>dn</sub> outside the Air Noise Boundary and 55 dBA L<sub>dn</sub> outside the Outer Control Boundary as shown on the planning maps. For the purpose of this rule aircraft noise shall be assessed in accordance with NZS6805:1992 “Airport Noise Management and Land Use Planning” and logarithmically averaged over a three month period. The following operations are excluded from the calculation of noise for compliance with noise limits:</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>



Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>(i) Aircraft engine testing and maintenance;</p> <p>(ii) Aircraft landing or taking off in an emergency; and</p> <p>(iii) Air Show (for one air show per year).</p> <p>(b) Aircraft movements shall be recorded monthly and noise contours for the purpose of assessing compliance with rule NOISE-R34(1)(a) shall be calculated no later than 12 months from the date the rule becomes legally operative and thereafter once every two years. When the calculated noise level is within 1 decibel of the limit noise contours for the purpose of assessing compliance with Rule NOISE-R34(1)(a) shall be calculated annually and verified with infield monitoring once every two years.</p> <p>(i) A report detailing the noise contours and calculations and in-field noise levels in the years that these are monitored, shall be prepared and forwarded to the Council on an annual basis by the airport operator.</p>	
--	---	--

*MSRZ – Motorsport and recreation zone*

<b>NOISE-R35</b>	Noise – motor sport and recreation activity in PREC14, PREC17 and PREC18	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The noise level from activities within PREC14, PREC17 and PREC18 shall not exceed the following limits measured beyond the ‘Hampton Downs Noise Control Boundary’ shown in APP12 – Hampton Downs motorsport and recreation:</p> <p>(i) 65dBA <math>L_{Aeq}</math> on no more than 27 days per year (with no more than 10 of the 27 days to be on a Sunday or public holiday) between the hours of 9:00am – 6:00pm. Except that in any year where a V8 Supercars event is not held</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<p>then a noise level of up to 65dBA <math>L_{Aeq}</math> will be permitted between the hours of 9.00am to 6.00pm on up to 30 days per year (not more than 11 days to be on a Sunday or public holiday); and</p> <p>(ii) 55 dBA <math>L_{Aeq}</math> on no more than 40 days per year between the hours of 9:00am – 6:00pm; and</p> <p>(iii) 50 dBA <math>L_{Aeq}</math> between the hours of 7am to 6pm any other days of the year; and</p> <p>(iv) 45 dBA <math>L_{Aeq}</math> between the hours of 6pm to 10pm every day of the year; and</p> <p>(v) 40 dBA <math>L_{Aeq}</math>, and 65dBA <math>L_{max}</math> at all other times</p> <p>(b) The motor racing activities in NOISE-R35(1)(a)(i) and (ii) are exclusive of each other and the activities are considered to be on separate days.</p> <p>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</p> <p>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802</p>	
<b>NOISE-R36</b>	Noise – motor sport and recreation activity in PREC14, PREC17 and PREC18	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The use of a public address system shall only occur between the hours of 7:00am and 7:00pm and shall not exceed a limit of 50dBA <math>L_{Aeq}</math> measured at the zone boundary.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p> <p>(a)</p>
<b>NOISE-R37</b>	Noise – PREC15 and PREC16	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The noise level from activities, other than motor racing activities within PREC15 and PREC16, shall not exceed the following limits when measured</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	at the notional boundary of any dwelling:		
	Monday to Friday	7:00am to 7:00pm	50 dBA L <sub>Aeq</sub>
	Saturday	7:00am to 6:00pm	50 dBA L <sub>Aeq</sub>
	All other times including public holidays		40 dBA L <sub>Aeq</sub>
	Monday to Sunday	10:00pm to 7:00am	75 dBA L <sub>max</sub>
<p>(b) Noise levels shall be measured and assessed in accordance with the requirements of NZS 6801:2008 'Acoustics - Measurement of environmental sound' and NZS 6802:2008 'Acoustics – environmental noise'.</p>			

MTZ – Matangi zone rules

<b>NOISE-R38</b>	Noise – general	
MTZ – Matangi zone rules	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise generated within the MTZ – Matangi zone when measured at the zone boundary must meet the permitted noise levels for the neighbouring zone;</p> <p>(b) Noise measured within any new or relocated building must not exceed:</p> <p>(i) 75dB L<sub>Aeq</sub>, (7am to 10pm);</p> <p>(ii) 55dB L<sub>Aeq</sub>, and 85Db L<sub>Amax</sub> 10pm to 7am the following day; and</p> <p>(iii) Rule NOISE-R38(1)(b) does not apply to buildings within 20m of the Rail Corridor.</p> <p>(c) Noise levels shall be measured in accordance with the requirements of NZS 6801:2008 Acoustics - Measurement of Environmental Sound; and</p> <p>(d) Noise levels shall be assessed in accordance with the requirements of NZS 6802:2008 Acoustic- Environmental noise.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Hours and days of operation;</p> <p>(c) Noise levels;</p> <p>(d) Timing and duration; and</p> <p>(e) Methods of construction.</p>

RPZ – Rangitahi Peninsula zone

<b>NOISE-R39</b>	Noise – general	
RPZ – Rangitahi Peninsula zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise measured within any other site must not exceed:</p> <p>(i) 50dB L<sub>Aeq</sub> (15min), 7am to 7pm, every day, and</p> <p>(ii) 45dB L<sub>Aeq</sub> (15min), 7pm to 10pm, every day, and</p> <p>(iii) 40dB L<sub>Aeq</sub> (15min), 10pm to 7am the following day. and</p> <p>(iv) 65dB (L<sub>AFmax</sub>), 10pm to 7am the following day.</p> <p>(b) Noise levels must be measured in accordance with the requirements of NZS 6801:2008 “Acoustics - Measurement of Environmental Sound.</p> <p>(c) Noise levels must be assessed in accordance with the requirements of NZS 6802:2008 “Acoustic- Environmental noise”.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

TKAZ – Te Kowhai airpark zone

<b>NOISE-R40</b>	Noise – other than aircraft operations	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise, other than noise from aircraft operations, measured within any site in any zone, other than the Te Kowhai Airpark Zone, must meet the permitted noise levels for that zone.</p> <p>(b) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</p> <p>(c) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 Acoustic - Environmental noise.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>NOISE-R41</b>	Noise – aircraft operations	

<p>TKAZ – Te Kowhai airpark zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Noise from aircraft operations in all precincts, including aircraft movements on taxiways, shall not exceed 65dB L<sub>dn</sub> outside the Air Noise Boundary and 55dB L<sub>dn</sub> outside the Outer Control Boundary as shown on the planning maps when assessed in PREC29 and PREC30 and on receiving sites outside of the TKAZ – Te Kowhai Airpark zone. For the purpose of this rule aircraft noise shall be assessed in accordance with NZS6805:1992 "Airport Noise Management and Land Use Planning" and logarithmically averaged over a three month period. The following operations are excluded from the calculation of noise for compliance with noise limits:</p> <ul style="list-style-type: none"> <li>(i) Aircraft engine testing and maintenance</li> <li>(ii) Aircraft landing or taking off in an emergency</li> <li>(iii) Emergency flights required to rescue persons from life threatening situations or to transport patients, human vital organs or medical personnel in a medical emergency</li> <li>(iv) Flights required to meet the needs of a national or civil defence emergency declared under the Civil Defence Emergency Management Act 2002</li> <li>(v) Aircraft using the aerodrome due to unforeseen circumstances as an essential alternative to landing at a scheduled airport elsewhere</li> <li>(vi) Aircraft undertaking firefighting duties</li> <li>(vii) Air Show (for one air show per calendar year)</li> </ul> <p>(b) Aircraft movements shall be recorded monthly and noise</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p> <p>(a)</p>
--------------------------------------	---	---

Part 2: District-wide matters / General district-wide matters / NOISE – Noise

	<p>contours for the purpose of assessing compliance with NOISE-R41(1)(a) shall be calculated no later than 12 months from the date when the rule becomes legally operative and thereafter once every two years. When the calculated noise level is within 1 decibel of the 65dB L<sub>dn</sub> and / or 55dB L<sub>dn</sub> limit/s, noise contours for the purpose of assessing compliance with NOISE-R41 shall be calculated annually and verified with infield monitoring once every two years.</p>	
<b>NOISE-R42</b>	Noise – aircraft operations	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Aircraft engine testing and maintenance in all precincts must: <ul style="list-style-type: none"> <li>(i) Take place only between: <ul style="list-style-type: none"> <li>(1) 0800 hours and 2000 hours in the Summer Period; or</li> <li>(2) 0800 hours and 1900 hours in the Winter Period</li> </ul> </li> </ul> </li> <li>(b) Meet the receiving site relevant zone permitted noise levels when measured at the notional boundary of any site outside the TKAZ – Te Kowhai Airpark zone.</li> <li>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 Acoustics - Measurement of Environmental Sound.</li> <li>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 Acoustic - Environmental noise.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

TTZ – TaTa Valley zone

<b>NOISE-R43</b>	Noise – general	
TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

	<p>(a) The noise rating level must not exceed:</p> <ul style="list-style-type: none"> <li>(i) 50dB L<sub>Aeq</sub>, 7am to 7pm every day;</li> <li>(ii) 45dB L<sub>Aeq</sub>, 7pm to 10pm every day;</li> <li>(iii) 40dB L<sub>Aeq</sub> and 65dB L<sub>Amax</sub>, 10pm to 7am the following day when measured at or within any Notional Boundary in the GRUZ – General Rural Zone.</li> </ul> <p>(b) No noise limits apply between sites in the TTZ – TaTa Valley zone.</p> <p>(c) Noise levels must be measured in accordance with the requirements of New Zealand Standard NZS 6801:2008 “Acoustics – Measurement of Environmental Sound”.</p> <p>(d) Noise levels must be assessed in accordance with the requirements of New Zealand Standard NZS 6802:2008 “Acoustic – Environmental noise”.</p>	<p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The extent to which proposed hours of operation and/or duration (of the activity causing the noise infringement) will give rise to adverse noise effects on the surrounding environment and adequacy of proposed measures to manage these effects.</li> </ul>
--	---	---

## SIGN – Signs

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Policies

SIGN-PI Signage.

- (1) In GRZ – General residential zone, LLRZ – Large lot residential zone and SETZ – Settlement zone:
  - (a) Provide for the establishment of signs where they are directly associated with the activity carried out on the site on which they are located; and
  - (b) Recognise that public information signs provide a benefit to community well-being and support infrastructure and commercial and community activities.
  - (c) Provide for signage that is compatible with the character and sensitivity of the residential environment.
- (2) In the TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone provide for:
  - (a) The establishment of signs where they are associated with the activity carried out on the site on which they are located;
  - (b) Public information signs that are of benefit to community well-being; and
  - (c) Establishment of signage to support the commercial function and vibrancy of the zones with controls on the size, location, appearance and number of signs to ensure they do not detract from the visual amenity of the surrounding environment.
- (3) In the RLZ – Rural lifestyle zone:
  - (a) Signage contributes to the social and economic wellbeing of communities by:
    - (i) Supporting infrastructure and commercial and community activities;
    - (ii) Providing information, including for public safety;
    - (iii) Identifying places;
  - (b) Provide for the establishment of signs where they are directly associated with the activity carried out on the site on which they are located;
  - (c) Recognise that public information signs provide a benefit to community well-being; and
  - (d) Provide for temporary signage subject to meeting limits on duration.

SIGN-P2 Managing the adverse effects of signs.

- (1) In GRZ – General residential zone, LLRZ – Large lot residential zone and SETZ – Settlement zone:
  - (a) The location, colour, content, and appearance of signs are controlled to ensure signs do not adversely affect the safety of road users;



Part 2: District-wide matters / General district-wide matters / SIGN – Signs

- (b) Discourage signs that generate adverse effects from illumination, light spill, flashing, moving or reflection.
- (2) In the TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone ensure that:
- (a) The location, colour, content, and appearance of signs are controlled to ensure signs do not adversely affect the safety of road users;
  - (b) Signs that generate adverse effects from illumination, light spill, flashing, movement or reflection are avoided; and
  - (c) The placement of signs do not obstruct the free movement of:
    - (i) Pedestrians along the footpath; and
    - (ii) Vehicle use of the road carriageway.
- (3) In the GRUZ – General rural zone:
- (a) Manage the scale, location, appearance and number of signs to ensure they do not compromise visual amenity.
  - (b) Ensure that signs directed at or visible to road or rail users do not adversely affect the safety of land transport users.
  - (c) Limit the duration of temporary signage.
  - (d) Recognise that public information signs provide value to the wider community.
  - (e) Provide for appropriate signage on historic heritage items, notable trees and Sites and areas of significance to Maori for the purpose of identification or interpretation.
- (4) In the RLZ – Rural lifestyle zone:
- (a) The location, colour, content, and appearance of signs are controlled to ensure signs do not adversely affect the safety of road users.
  - (b) Maintain the visual amenity and character of the RLZ – Rural lifestyle zone through controls on the size, location, appearance and number of signs.
  - (c) Avoid signs that generate adverse effects from illumination, light spill, flashing or reflection.

**SIGN-P3** Signs in the BTZ – Business Tamahere zone.

- (1) Provide for the establishment of signs where they are directly associated with the activity carried out on the site on which they are located;
- (2) Recognise that public information signs provide a benefit to community well-being; and
- (3) Enable the establishment of signage to support the commercial function of the BTZ – Business Tamahere zone with controls on the size, location, appearance and number of signs to ensure they do not detract from the visual amenity and character of the neighbourhood centre.

**SIGN-P4** Managing the adverse effects of signs in the BTZ – Business Tamahere zone.

- (1) The location, colour, content, and appearance of signs are controlled to ensure signs do not adversely affect the safety of road users.

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

- (2) Enable signs in the BTZ – Business Tamahere zone that contribute to an efficient, attractive and vibrant neighbourhood centre.
- (3) Avoid signs that generate adverse effects from illumination, light spill, flashing or reflection.
- (4) Ensure that the placement of signs do not obstruct the free movement of:
  - (a) Pedestrians along the footpath; and
  - (b) Vehicle use of the road carriageway.

SIGN-P5 Managing the adverse effects of signs in the OSZ – Open space zone.

Ensure that signs do not adversely affect amenity, traffic safety, heritage or Maaori cultural values.

## Rules

*Land use – activities (zones specified in the first column)*

<b>SIGN-R1</b>	Signs – general	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A public information sign erected by a government agency;</li> <li>(b) Official sign; or</li> <li>(c) Signs that are located within a building or that are not visible from a road or adjoining site.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

*LLRZ – Large lot residential zone*

<b>SIGN-R2</b>	Signs – general	
LLRZ – Large lot residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with the following standards:                             <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) The sign does not exceed 0.25m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 2m;</li> <li>(v) The sign is not illuminated;</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign; and</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any Maaori site of significance; and</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</p> <p>(viii) The sign is not attached to a tree identified in SCHED2 – Notable trees, except for the purpose of identification; and</p> <p>(ix) The sign is not attached to a heritage item listed in SCHED I – Historic heritage items except for the purpose of identification and interpretation;</p> <p>(x) The sign is not attached to a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori except for the purpose of identification and interpretation; and</p> <p>(xi) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign.</p>	<p>(i) Effects on notable architectural features of the building.</p>
<b>SIGN-R3</b>	Signs – general	
LLRZ – Large lot residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There is no more than 3 signs per site of which;</p> <p>(1) There is no more than 1 sign per agency measuring 600mm x 900mm;</p> <p>(2) There is no more than 1 sign measuring 1800mm x 1200mm; and</p> <p>(3) There is no more than 1 real estate header sign measuring 1800mm x 1200mm.</p> <p>(ii) The sign is not illuminated; and</p> <p>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign; and</p> <p>(f) Effects on notable trees;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any Maaori site of significance; and</p> <p>(i) Effects on notable architectural features of the building.</p>
<b>SIGN-R4</b>	Signs – effects on traffic	

<p>LLRZ – Large lot residential zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road or rail users must comply with the following standards: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and any other sign;</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections or at a level rail crossing;</li> <li>(iv) Contain no more than 40 characters and no more than 6 symbols;</li> <li>(v) Have lettering that is at least 150mm high; and</li> <li>(vi) Be located at least 130m from a site entrance, where the sign directs traffic to the entrance.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
--	---	--

GRZ – General residential zone

<p><b>SIGN-R5</b></p>	<p>Signs – general</p>	
<p>GRZ – General residential zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained within the site;</li> <li>(iii) The sign does not exceed 0.25m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 2m in height above the ground;</li> <li>(v) The sign is not illuminated;</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vii) The sign is set back at least 50m from the designated</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) Amenity values;</li> <li>(c) Character of the locality;</li> <li>(d) Effects on traffic safety;</li> <li>(e) Glare and artificial light spill;</li> <li>(f) Content, colour and location of the sign;</li> <li>(g) Effects on a notable tree;</li> <li>(h) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(i) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(j) Effects on notable architectural features of a building.</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>boundary of a state highway and the Waikato Expressway;</p> <p>(viii) The sign is not attached to a tree identified in SCHED2 – Notable trees, except for the purpose of identification and interpretation;</p> <p>(ix) The sign is not attached to a heritage item listed in SCHED I – Historic heritage items, except for the purpose of identification and interpretation;</p> <p>(x) The sign is not attached to a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori, except for the purpose of identification and interpretation;</p> <p>(xi) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign.</p>	
<b>SIGN-R6</b>	Signs – general	
GRZ – General residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate 'for sale' sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There is no more than 1 sign per agency;</p> <p>(ii) The sign is not illuminated; and</p> <p>(b) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign;</p> <p>(f) Effects on a notable tree;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</p> <p>(i) Effects on notable architectural features of a building.</p>
<b>SIGN-R7</b>	Signs – effects on traffic	
GRZ – General residential zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at land transport users must:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p>

	<ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and any other sign;</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections or at a level crossing;</li> <li>(iv) Contain no more than 40 characters and no more than 6 words, symbols or graphics;</li> <li>(v) Have lettering that is at least 150mm high;</li> <li>(vi) Be at least 130m from a site entrance, where the sign directs traffic to the entrance.</li> </ul>	<ul style="list-style-type: none"> <li>(a) Amenity;</li> <li>(b) Character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on a notable tree;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of a building.</li> </ul>
--	--	--

MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2

<b>SIGN-R8</b>	Signs – general	
<p>MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained within the site;</li> <li>(iii) The sign does not exceed 1m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 2m in height above the ground;</li> <li>(v) The sign is not illuminated;</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vii) The sign is set back at least 50m from the designated boundary of a state highway and the Waikato Expressway;</li> <li>(viii) The sign is not attached to a tree identified in SCHED2 – Notable trees, except for the</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on a notable tree;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of a building.</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>purpose of identification and interpretation;</p> <p>(ix) The sign is not attached to a heritage item listed in SCHED I – Historic heritage items, except for the purpose of identification and interpretation;</p> <p>(x) The sign is not attached to a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori, except for the purpose of identification and interpretation;</p> <p>(xi) The sign relates to:</p> <p>(1) goods or services available on the site; or</p> <p>(2) a property name sign.</p>	
<b>SIGN-R9</b>	Signs – general	
MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate 'for sale' sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There is no more than 1 sign per agency;</p> <p>(ii) The sign is not illuminated; and</p> <p>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign;</p> <p>(f) Effects on a notable tree;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</p> <p>(i) Effects on notable architectural features of a building.</p>
<b>SIGN-R10</b>	Signs – effects on traffic	
MRZ1 – Medium density residential zone 1 and MRZ2 – Medium density residential zone 2	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at land transport users must:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign;</p> <p>(ii) Be located at least 60m from controlled intersections,</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill;</p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>pedestrian crossings and any other sign;</p> <p>(iii) Not obstruct sight lines of drivers turning into, or out of, a site entrance and intersections or at a level crossing;</p> <p>(iv) Contain no more than 40 characters and no more than 6 words and/or symbols;</p> <p>(v) Have lettering that is at least 150mm high; and</p> <p>(vi) Be at least 130m from a site entrance, where the sign directs traffic to the entrance.</p>	<p>(e) Content, colour and location of the sign;</p> <p>(f) Effects on a notable tree;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori;</p> <p>(i) Effects on notable architectural features of a building.</p>
--	---	--

GRUZ – General rural zone

<b>SIGN-RI I</b>	Signs – general	
GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A sign must comply with all of the following standards:</p> <p>(i) It is the only sign on the site;</p> <p>(ii) The sign is wholly contained on the site;</p> <p>(iii) The sign does not exceed 3m<sup>2</sup>;</p> <p>(iv) The sign height does not exceed 3m;</p> <p>(v) The sign is not illuminated,</p> <p>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</p> <p>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</p> <p>(viii) The sign is not attached to a notable tree identified in SCHED2 – Notable trees, except for the purpose of identification;</p> <p>(ix) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Rural character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Effects of glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign;</p> <p>(f) Effects on notable trees;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</p> <p>(i) Effects on notable architectural features of the building.</p>



	<p>(x) The sign is for the purpose of identification and interpretation of a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori;</p> <p>(xi) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign.</p>	
<b>SIGN-R12</b>	Signs – general	
GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) Have no more than 3 signs per site;</p> <p>(ii) The sign is not illuminated;</p> <p>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</p> <p>(iv) The sign does not exceed 3m<sup>2</sup>;</p> <p>(v) Any real estate sign shall be removed within 20 working days of the sale or lease being settled.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Rural character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Effects of glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign;</p> <p>(f) Effects on notable trees;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</p> <p>(i) Effects on notable architectural features of the building.</p>
<b>SIGN-R13</b>	Signs - effects on traffic	
GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at road users must meet the following standards:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign;</p> <p>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and railway crossings</p> <p>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections;</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(iv) Contain no more than 40 characters and no more than 6 words, symbols, or graphics;</li> <li>(v) Have lettering that is at least 200mm high; and</li> <li>(vi) Where the sign directs traffic to a site entrance, it must be at least:</li> <li>(vii) 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(viii) 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul>	
--	---	--

RLZ – Rural lifestyle zone

<b>SIGN-RI4</b>	Signs – general	
RLZ – Rural lifestyle zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards:                             <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) The sign does not exceed an area of 1m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 3m;</li> <li>(v) The sign is not illuminated;</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</li> <li>(viii) The sign is not attached to a tree identified in SCHED2 – Notable trees, except for the purpose of identification;</li> <li>(ix) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</li> <li>(x) Where the sign is on a site with a site and area of</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Rural character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on any notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori it must be for the purpose of identification and interpretation;</p> <p>(xi) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign.</p>	
<b>SIGN-RI5</b>	Signs – general	
RLZ – Rural lifestyle zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate 'for sale' sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There are no more than 3 signs per site;</p> <p>(ii) The sign is not illuminated;</p> <p>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</p> <p>(iv) The sign does not project into or over a road reserve;</p> <p>(v) The sign does not exceed an area of 1m<sup>2</sup>.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Rural character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Effects of glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign;</p> <p>(f) Effects on any notable trees;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</p> <p>(i) Effects on notable architectural features of the building.</p>
<b>SIGN-RI6</b>	Signs – effects on traffic	
RLZ – Rural lifestyle zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at road users must meet the following standards:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign; and</p> <p>(ii) Be located at least 60m from controlled intersections, pedestrian crossings, railway crossings and any other sign associated with roads and traffic management; and</p> <p>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>intersections or at a level crossing; and</p> <p>(iv) Contain no more than 40 characters and no more than 6 symbols; and</p> <p>(v) Have lettering that is at least 200mm high; and</p> <p>(vi) Where the sign directs traffic to a site entrance the sign must be at least:</p> <p>(vii) 175m from the site entrance on any road with a speed limit of 80 km/hr or less; or</p> <p>(viii) 250m from the site entrance on any road with a speed limit of more than 80km/hr.</p>	
--	--	--

SETZ – Settlement zone

<b>SIGN-RI7</b>	Signs – general	
SETZ – Settlement zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A sign must comply with the following standards:</p> <p>(i) It is the only sign on the site;</p> <p>(ii) The sign is wholly contained on the site;</p> <p>(iii) The sign does not exceed 0.25m<sup>2</sup>;</p> <p>(iv) The sign height does not exceed 2m;</p> <p>(v) The sign is not illuminated;</p> <p>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</p> <p>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</p> <p>(viii) The sign is not attached to a tree identified in SCHED2 – Notable trees, except for the purpose of identification; and</p> <p>(ix) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign; and</p> <p>(f) Effects on notable trees;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any Maaori site of significance; and</p> <p>(i) Effects on notable architectural features of the building.</p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>of identification and interpretation;</p> <p>(x) The sign is not attached to a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori except for the purpose of identification and interpretation; and</p> <p>(xi) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign.</p>	
<b>SIGN-R18</b>	Signs – general	
SETZ – Settlement zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There is no more than 3 signs per site of which;</p> <p>(1) There is no more than 1 sign per agency measuring 600mm x 900mm;</p> <p>(2) There is no more than 1 sign measuring 1800mm x 1200mm; and</p> <p>(3) There is no more than 1 real estate header sign measuring 1800mm x 1200mm.</p> <p>(ii) The sign is not illuminated; and</p> <p>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill;</p> <p>(e) Content, colour and location of the sign; and</p> <p>(f) Effects on notable trees;</p> <p>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(h) Effects on cultural values of any Maaori site of significance; and</p> <p>(i) Effects on notable architectural features of the building.</p>
<b>SIGN-R19</b>	Signs – effects on traffic	
SETZ – Settlement zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at road or rail users must comply with the following standards:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign;</p> <p>(ii) Be located at least 60m from controlled intersections,</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>pedestrian crossings and any other sign;</p> <p>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections or at a level rail crossing;</p> <p>(iv) Contain no more than 40 characters and no more than 6 symbols;</p> <p>(v) Have lettering that is at least 150mm high; and</p> <p>(vi) Be located at least 130m from a site entrance, where the sign directs traffic to the entrance.</p>	
--	---	--

LCZ – Local centre zone and COMZ – Commercial zone

<b>SIGN-R20</b>	Signs – general	
<p>LCZ – Local centre zone; and COMZ – Commercial zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A sign must comply with all of the following standards:</p> <p>(i) The sign is wholly contained on the site;</p> <p>(ii) The sign height must not exceed 10m;</p> <p>(iii) Where the sign is illuminated it must:</p> <p>(1) Not have a light source that flashes or moves;</p> <p>(2) Not contain moving parts or reflective materials; and</p> <p>(3) Be focused to ensure that it does not spill light beyond the site;</p> <p>(iv) Where the sign is attached to a building, it must:</p> <p>(1) Not extend more than 300mm from the building wall; and</p> <p>(2) Not exceed the height of the building;</p> <p>(v) Where the sign is a freestanding sign, it must:</p> <p>(1) Not exceed an area of 3m<sup>2</sup> for one sign per site, and 1m<sup>2</sup> for any other</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Effects of glare and artificial light spill;</p> <p>(d) Content, colour and location of the sign;</p> <p>(e) Effects on notable trees;</p> <p>(f) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(g) Effects on cultural values of any SASM – Sites and areas of significance to Maaori Site;</p> <p>(h) Effects on notable architectural features of the building.</p>

	<p>freestanding sign on the site; and</p> <p>(2) Be set back at least 5m from the boundary of the GRZ – General residential zone, or MRZ1 – Medium density residential zone 1 or MRZ2 – Medium density residential zone 2;</p> <p>(vi) The sign is not attached to a notable tree identified in SCHED2 – Notable trees, except for the purpose of identification;</p> <p>(vii) The sign is on the site of and for the purpose of identification and interpretation of a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</p> <p>(viii) The sign is not attached to a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori except for the purpose of identification and interpretation;</p> <p>(ix) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign.</p>	
<p><b>SIGN-R2I</b></p>	<p>Signs – general</p>	
<p>LCZ – Local centre zone; and COMZ – Commercial zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate 'for sale' or 'for rent' sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(b) There is no more than 3 signs per site;</p> <p>(c) The sign is not illuminated; and</p> <p>(d) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Effects of glare and artificial light spill;</p> <p>(d) Content, colour and location of the sign;</p> <p>(e) Effects on notable trees;</p> <p>(f) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

		(g) Effects on cultural values of any SASM – Sites and areas of significance to Maaori Site; (h) Effects on notable architectural features of the building.
<b>SIGN-R22</b>	Signs - effects on traffic	
LCZ – Local centre zone; and COMZ – Commercial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at land transport users must meet all of the following standards: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections or at a level crossing, pedestrian crossings and any other sign;</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections or at a level crossing; and</li> <li>(iv) Contain no more than 40 characters and no more than 6 words and/or symbols;</li> <li>(v) Have lettering that is at least 150mm high;</li> </ul> </li> <li>(b) Rule SIGN-R22(1)(a) does not apply to site identification signs</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

TCZ – Town centre zone

<b>SIGN-R23</b>	Signs – general	
TCZ – Town centre zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) The sign height does not exceed 10m;</li> <li>(ii) Where the sign is illuminated it must: <ul style="list-style-type: none"> <li>(1) Not have a light source that flashes or moves; and</li> <li>(2) Not contain moving parts or reflective materials; and</li> <li>(3) Be directed to ensure it does not spill light beyond the site;</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Effects on traffic safety;</li> <li>(c) Effects of glare and artificial light spill;</li> <li>(d) Content, colour and location of the sign;</li> <li>(e) Effects on notable trees;</li> <li>(f) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> </ul>



	<p>(iii) Where the sign is attached to a building, it must:</p> <ol style="list-style-type: none"> <li>(1) Not extend more than 300mm from the building wall; and</li> <li>(2) Not exceed the height of the building;</li> </ol> <p>(iv) Where the sign is attached to a verandah, it must:</p> <ol style="list-style-type: none"> <li>(1) Be set back at least 500mm from the road carriageway; and</li> <li>(2) Not be more than 500mm high; and</li> <li>(3) Not project beyond the roof or fascia of the verandah more than 100mm in any direction; and</li> <li>(4) Allow clearance of at least 2.4m above a footpath;</li> </ol> <p>(v) Where the sign is a freestanding sign, it must:</p> <ol style="list-style-type: none"> <li>(1) Not exceed an area of 3m<sup>2</sup> for one sign, and 1m<sup>2</sup> for any other freestanding sign on the site; and</li> <li>(2) Be set back at least 5m from the boundary of the GRZ – General residential zone, or MRZ1 – Medium density residential zone 1 or MRZ2 – Medium density residential zone 2;</li> </ol> <p>(vi) The sign must be wholly contained on the site except where it is attached to a verandah;</p> <p>(vii) The sign is not attached to a notable tree identified in SCHED2 – Notable trees, except for the purpose of identification;</p> <p>(viii) The sign is on the site of and for the purpose of identification and interpretation of a heritage item listed in SCHED1 – Historic heritage items;</p> <p>(ix) The sign is not attached to a site and area of significance</p>	<p>(g) Effects on cultural values of any SASM – Sites and areas of significance to Maaori;</p> <p>(h) Effects on notable architectural features of the building.</p>
--	---	--

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>to Maaori listed in SCHED3 – Sites and areas of significance to Maaori, except for the purpose of identification and interpretation;</p> <p>(x) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign</p>	
<b>SIGN-R24</b>	Signs – general	
TCZ – Town centre zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate 'for sale' or 'for rent' sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There is no more than 3 signs per site;</p> <p>(ii) The sign is not illuminated;</p> <p>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Effects of glare and artificial light spill;</p> <p>(d) Content, colour and location of the sign;</p> <p>(e) Effects on notable trees;</p> <p>(f) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</p> <p>(g) Effects on cultural values of any SASM – Sites and areas of significance to Maaori;</p> <p>(h) Effects on notable architectural features of the building.</p>
<b>SIGN-R25</b>	Signs – effects on traffic	
TCZ – Town centre zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at land transport users must meet all of the following standards:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign;</p> <p>(ii) Be located at least 60m from controlled intersections or at a level crossing, pedestrian crossings and any other sign;</p> <p>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections or at a level crossing;</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	<ul style="list-style-type: none"> <li>(iv) Contain no more than 40 characters and no more than 6 words and/or symbols;</li> <li>(v) Have lettering that is at least 150mm high; and</li> <li>(b) SIGN-R25(1)(a) does not apply to site identification signs.</li> </ul>	
--	--	--

GIZ – General industrial zone

<b>SIGN-R26</b>	Signs – general	
GIZ – General industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign that: <ul style="list-style-type: none"> <li>(i) Does not exceed a sign height of 10 metres;</li> <li>(ii) Is wholly contained within the site;</li> <li>(iii) Relates to goods and services available on the site or the property name;</li> <li>(iv) Is set back at least 15 metres from a state highway or Waikato Expressway</li> </ul> </li> <li>(b) If illuminated: <ul style="list-style-type: none"> <li>(i) Does not have a light source that flashes or moves; and</li> <li>(ii) Does not contain moving parts or reflective materials.</li> </ul> </li> <li>(c) A sign attached to a building that: <ul style="list-style-type: none"> <li>(i) Does not extend more than 300mm from the building wall; and</li> <li>(ii) Does not exceed the height of the building.</li> </ul> </li> <li>(d) Freestanding signs that: <ul style="list-style-type: none"> <li>(i) Do not exceed an area of 3m<sup>2</sup> for one sign per site, and 1m<sup>2</sup> for any other freestanding sign on the site;</li> <li>(ii) Are set back at least 5m from the boundary of any site in a GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone or</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Visual amenity;</li> <li>(b) Effects on traffic safety;</li> <li>(c) Glare and artificial light spill;</li> <li>(d) Content, colour and location of the sign;</li> <li>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign; and</li> <li>(f) Effects on notable architectural features of a heritage item.</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>RLZ – Rural lifestyle zone; and</p> <p>(ii) Are set back at least 15 metres from a state highway or Waikato Expressway.</p> <p>(e) A sign attached to a heritage item listed in SCHED1 – Historic heritage items for the express purpose of identification and interpretation.</p>	
<b>SIGN-R27</b>	Signs – general	
GIZ – General industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate sign that:</p> <p>(i) Relates to the sale of the site on which it is located;</p> <p>(ii) Does not result in more than 3 signs per site;</p> <p>(iii) Is not illuminated;</p> <p>(iv) Does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials; and</p> <p>(v) Does not exceed dimensions of 1800mm x 1200mm.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Visual amenity;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Glare and artificial light spill;</p> <p>(d) Content, colour and location of the sign;</p> <p>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign; and</p> <p>(f) Effects on notable architectural features of a heritage item.</p>
<b>SIGN-R28</b>	Signs – effects on traffic	
GIZ – General industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at road users that:</p> <p>(i) Does not imitate the content, colour or appearance of any traffic control sign; and</p> <p>(ii) Is located at least 60 metres from controlled intersections, pedestrian crossings and another advertising sign; and</p> <p>(iii) Does not obstruct sight lines of drivers turning into or out of a site entrance and intersections; and</p> <p>(iv) Does not contain more than 40 characters or more than 6 symbols; and</p> <p>(v) Has lettering that is at least 150mm high; and</p> <p>(vi) Is at least 130 metres from a site entrance, where the sign</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the safety of road users is maintained.</p>

	directs traffic to the entrance.	
--	----------------------------------	--

HIZ – Heavy industrial zone

<b>SIGN-R29</b>	Signs – general	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A sign that:</p> <p>(i) Does not exceed a sign height of 15 metres;</p> <p>(ii) Is wholly contained within the site;</p> <p>(iii) Relates to goods and services available on the site or a property name;</p> <p>(iv) Is set back at least 15 metres from a state highway or Waikato Expressway; and</p> <p>(v) If illuminated:</p> <p>(1) Does not have a light source that flashes or moves; and</p> <p>(2) Does not contain moving parts or reflective materials. and</p> <p>(vi) A sign attached to a building that:</p> <p>(1) Does not extend more than 300 millimetres from the building wall; and</p> <p>(2) Does not exceed the height of the building.</p> <p>(vii) Freestanding signs that:</p> <p>(1) Do not exceed an area of 3m<sup>2</sup> for one sign per site, and 1m<sup>2</sup> for any other freestanding sign on the site;</p> <p>(2) Are set back at least 5 metres from the boundary of any site in any GRZ – General residential zone, SETZ – Settlement zone or RLZ – Rural lifestyle zone; and</p> <p>(3) Are set back at least 15 metres from a state highway or Waikato Expressway.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Glare and artificial light spill;</p> <p>(d) Content, colour and location of the sign; and</p> <p>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign.</p>

	(viii) A sign attached to a heritage item listed in SCHED I – Historic heritage items, for the express purpose of identification and interpretation.	
<b>SIGN-R30</b>	Signs – general	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A real estate 'for sale' sign that: <ul style="list-style-type: none"> <li>(i) Relates to the sale of the site on which it is located;</li> <li>(ii) Does not result in more than 3 signs per site</li> <li>(iii) Is not illuminated;</li> <li>(iv) Does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials; and</li> <li>(v) does not exceed dimensions of 1800mm x 1200mm.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity;</li> <li>(b) Effects on traffic safety;</li> <li>(c) Glare and artificial light spill;</li> <li>(d) Content, colour and location of the sign; and</li> <li>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign.</li> </ul>
<b>SIGN-R31</b>	Signs – effects on traffic	
HIZ – Heavy industrial zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road users that: <ul style="list-style-type: none"> <li>(i) Does not imitate the content, colour or appearance of any traffic control sign; and</li> <li>(ii) Is located at least 60 metres from controlled intersections, pedestrian crossings and another advertising sign; and</li> <li>(iii) Does not obstruct sight lines of drivers turning into or out of a site entrance and intersections; and</li> <li>(iv) Does not contain more than 40 characters or more than 6 symbols; and</li> <li>(v) Has lettering that is at least 150 millimetres high; and</li> <li>(vi) Is at least 130 metres from a site entrance, where the sign directs traffic to the entrance.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The extent to which the safety of road users is maintained.</li> </ul>

OSZ – Open space zone

<b>SIGN-R32</b>	Signs – general
-----------------	-----------------

<p>OSZ – Open space zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) The sign does not exceed: <ul style="list-style-type: none"> <li>(1) 3m<sup>2</sup> for one sign per site, and</li> <li>(2) 1m<sup>2</sup> for any other sign;</li> </ul> </li> <li>(ii) The sign height does not exceed 3m;</li> <li>(iii) The sign does not exceed the height of the building;</li> <li>(iv) The sign is not illuminated;</li> <li>(v) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vi) The sign is not attached to a tree identified in Schedule SCHED2 – Notable trees, except for the purpose of identification and interpretation;</li> <li>(vii) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</li> <li>(viii) On a site with a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori, the sign is for the purpose of identification and interpretation;</li> <li>(ix) The sign is set back at least 5m from the boundary of the GRZ – General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone, SETZ – Settlement zone or RLZ Rural lifestyle zone.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees.</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>
<p><b>SIGN-R33</b></p>	<p>Signs – effects on traffic</p>	
<p>OSZ – Open space zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>(a) Any sign directed at road or rail users must:</p> <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and any other sign;</li> <li>(iii) Not obstruct sight lines of drivers: turning into or out of a site entrance and intersections; or at a railway level crossing;</li> <li>(iv) Contain no more than 40 characters and no more than 6 symbols;</li> <li>(v) Have lettering that is at least 200mm high; and</li> <li>(vi) Comply with the following where the sign directs traffic to a site entrance: <ul style="list-style-type: none"> <li>(1) Located at least 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(2) Located at least 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul> </li> </ul>	
<p><b>SIGN-R34</b></p>	<p>Signs – Tamahere Village Green (Tamahere Village Green specific control, refer to the planning maps)</p>	
<p>Tamahere Village Green specific control within the OSZ – Open space zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any advertising sign visible from a public place must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) Where the sign is attached to a building: <ul style="list-style-type: none"> <li>(1) Does not exceed an area of 2m<sup>2</sup>;</li> <li>(2) Does not extend more than 300mm from the building wall;</li> <li>(3) Does not exceed the height of the building.</li> </ul> </li> <li>(ii) Where the sign is attached to a verandah; <ul style="list-style-type: none"> <li>(1) Is no deeper than 400mm;</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and streetscape</li> <li>(b) Traffic safety</li> <li>(c) Glare and light spill</li> <li>(d) Number of signs; and</li> <li>(e) Design and location of sign.</li> </ul>



	<ul style="list-style-type: none"> <li>(2) Does not obscure any notable architectural feature of the building;</li> <li>(3) Does not project beyond the roof or fascia of the verandah more than 100mm in any direction;</li> <li>(4) Allows clearance of at least 2.5m above any pedestrian access, or</li> <li>(iii) Where the sign is free standing;             <ul style="list-style-type: none"> <li>(1) Does not exceed 1.5m in height;</li> <li>(2) Does not exceed an area of 1m<sup>2</sup>, or</li> </ul> </li> <li>(iv) Where a sign is a signage wall;             <ul style="list-style-type: none"> <li>(1) Does not exceed 1.2m in height;</li> <li>(2) Does not exceed an area of 4m<sup>2</sup>;</li> </ul> </li> <li>(v) Where it is an illuminated sign, it:             <ul style="list-style-type: none"> <li>(1) Is not a neon sign;</li> <li>(2) Does not have a light source that flashes or moves;</li> <li>(3) Does not contain moving parts or reflective materials;</li> <li>(4) Does not spill light beyond the sign.</li> </ul> </li> </ul>	
<b>SIGN-R35</b>	Signs – Tamahere Village Green (Tamahere Village Green specific control, refer to the planning maps)	
<p>Tamahere Village Green specific control within the OSZ – Open space zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign advertising a community event must comply with all of the following standards:             <ul style="list-style-type: none"> <li>(i) It is a free standing sign;</li> <li>(ii) Be on display for no more than one month prior to the event;</li> <li>(iii) It does not exceed 1.5m in height, and</li> <li>(iv) It does not exceed an area of 1m<sup>2</sup>.</li> </ul> </li> <li>(b) Where it is an illuminated sign, it must not:</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values and streetscape</li> <li>(b) Traffic safety</li> <li>(c) Glare and light spill</li> <li>(d) Number of signs; and</li> <li>(e) Design and location of sign.</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(i) Be a neon sign;</li> <li>(ii) Have a light source that flashes or moves;</li> <li>(iii) Contain moving parts or reflective materials;</li> <li>(iv) Spill light beyond the sign.</li> </ul>	
--	--	--

BTZ – Business Tamahere zone

<b>SIGN-R36</b>	Signs – general	
BTZ – Business Tamahere zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) There are no more than two signs per leasable area;</li> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) Where the sign is attached to a building, it must not exceed: <ul style="list-style-type: none"> <li>(1) An area of 2m<sup>2</sup>; and</li> <li>(2) More than 300mm from the building wall; and</li> <li>(3) The height of the building;</li> </ul> </li> <li>(iv) Where the sign is attached to a verandah, it must: <ul style="list-style-type: none"> <li>(1) Be no deeper than 400mm; and</li> <li>(2) Not obscure any notable architectural feature of a building; and</li> <li>(3) Not project beyond the roof or fascia of the verandah more than 100mm in any direction; and</li> <li>(4) Allow clearance of at least 2.5m above any pedestrian access;</li> </ul> </li> <li>(v) Where it is a freestanding sign, it must not exceed: <ul style="list-style-type: none"> <li>(1) 1.5m in height; and</li> <li>(2) An area of 1m<sup>2</sup>;</li> </ul> </li> <li>(vi) Where it is a signage wall, it must not exceed: <ul style="list-style-type: none"> <li>(1) 1.2m in height; and</li> <li>(2) An area of 4m<sup>2</sup>;</li> </ul> </li> <li>(vii) Where it is an illuminated sign, it must:</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(1) Not be a neon sign; and</li> <li>(2) Not have a light source that flashes or moves; and</li> <li>(3) Not contain moving parts or reflective materials; and</li> <li>(4) Be focused to ensure it does not spill light beyond the site.</li> </ul>	
<b>SIGN-R37</b>	Signs – general	
BTZ – Business Tamahere zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A real estate 'for sale' or 'for rent' sign relating to the site on which it is located must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) There is no more than 3 signs per site;</li> <li>(ii) The sign is not illuminated;</li> <li>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials; and</li> <li>(iv) The sign does not project into or over road reserve.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>SIGN-R38</b>	Signs – effects on traffic	
BTZ – Business Tamahere zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road users must: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be at least 60m from controlled intersections, pedestrian crossings and another sign;</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections;</li> <li>(iv) Contain no more than 40 characters and no more than 6 symbols; and</li> <li>(v) Have lettering that is at least 150mm high.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

CORZ – Corrections zone

<b>SIGN-R39</b>	Signs – general	
CORZ – Corrections zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) The sign does not exceed 3m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 3m;</li> <li>(v) The sign is not illuminated,</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</li> <li>(viii) The sign is not attached to a notable tree identified in SCHED2 – Notable trees, except for the purpose of identification;</li> <li>(ix) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</li> <li>(x) The sign is for the purpose of identification and interpretation of a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori;</li> <li>(xi) The sign relates to: <ul style="list-style-type: none"> <li>(1) Goods or services available on the site; or</li> <li>(2) A property name sign.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Rural character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>
<b>SIGN-R40</b>	Signs – general	
CORZ – Corrections zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A real estate sign relating to the site on which it is located must comply with all of the following standards:</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Rural character of the locality;</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(i) Have no more than 3 signs per site;</li> <li>(ii) The sign is not illuminated;</li> <li>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(iv) The sign does not exceed 3m<sup>2</sup>;</li> <li>(v) Any real estate sign shall be removed within 20 working days of the sale or lease being settled.</li> </ul>	<ul style="list-style-type: none"> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>
<b>SIGN-R41</b>	Signs - effects on traffic	
CORZ – Corrections zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road users must meet the following standards: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and railway crossings</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections;</li> <li>(iv) Contain no more than 40 characters and no more than 6 words, symbols, or graphics;</li> <li>(v) Have lettering that is at least 200mm high; and</li> <li>(vi) Where the sign directs traffic to a site entrance, it must be at least: <ul style="list-style-type: none"> <li>(vii) 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(viii) 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

FUZ – Future urban zone

<b>SIGN-R42</b>	Signs – general
-----------------	-----------------

<p>CORZ – Corrections zone</p>	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) The sign does not exceed 3m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 3m;</li> <li>(v) The sign is not illuminated,</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</li> <li>(viii) The sign is not attached to a notable tree identified in SCHED2 – Notable trees, except for the purpose of identification;</li> <li>(ix) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</li> <li>(x) The sign is for the purpose of identification and interpretation of a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori;</li> <li>(xi) The sign relates to: <ul style="list-style-type: none"> <li>(1) Goods or services available on the site; or</li> <li>(2) A property name sign.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Rural character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>
<p><b>SIGN-R43</b></p>	<p>Signs – general</p>	
<p>CORZ – Corrections zone</p>	<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A real estate sign relating to the site on which it is located must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) Have no more than 3 signs per site;</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Rural character of the locality;</li> <li>(c) Effects on traffic safety;</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(ii) The sign is not illuminated;</li> <li>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(iv) The sign does not exceed 3m<sup>2</sup>;</li> <li>(v) Any real estate sign shall be removed within 20 working days of the sale or lease being settled.</li> </ul>	<ul style="list-style-type: none"> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>
<b>SIGN-R44</b>	Signs - effects on traffic	
CORZ – Corrections zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road users must meet the following standards: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and railway crossings</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections;</li> <li>(iv) Contain no more than 40 characters and no more than 6 words, symbols, or graphics;</li> <li>(v) Have lettering that is at least 200mm high; and</li> <li>(vi) Where the sign directs traffic to a site entrance, it must be at least: <ul style="list-style-type: none"> <li>(vii) 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(viii) 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

HOPZ – Hopuhopu zone

<b>SIGN-R45</b>	Signs – general
-----------------	-----------------

<p>HOPZ – Hopuhopu zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) The sign is not illuminated,</li> <li>(iv) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> </ul> </li> <li>(v) The sign relates to: <ul style="list-style-type: none"> <li>(1) Goods or services available on the site; or</li> <li>(2) A property name sign.</li> </ul> </li> <li>(b) In PREC8 – Hopuhopu residential precinct, PREC9 – Hopuhopu education and conference precinct, PREC11 – Hopuhopu open space precinct, PREC12 – Hopuhopu mixed use precinct: <ul style="list-style-type: none"> <li>(i) The sign does not exceed 3m<sup>2</sup>; and</li> <li>(ii) The sign height does not exceed 3m;</li> </ul> </li> <li>(c) In PREC10 – Hopuhopu business precinct: <ul style="list-style-type: none"> <li>(i) The sign height must not exceed 10m;</li> <li>(ii) Where the sign is attached to a building, it must: <ul style="list-style-type: none"> <li>(1) Not extend more than 300mm from the building wall; and</li> <li>(2) Not exceed the height of the building;</li> </ul> </li> <li>(iii) Where the sign is a freestanding sign, it must: <ul style="list-style-type: none"> <li>(1) Not exceed an area of 3m<sup>2</sup>; and</li> <li>(2) Be set back at least 5m from the zone boundary.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any Historic heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maori;</li> </ul>
<p><b>SIGN-R46</b></p>	<p>Signs – effects on traffic</p>	
<p>HOPZ – Hopuhopu zone</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at land transport users must meet all of the following standards:</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on traffic safety;</li> </ul>



Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and level crossings;</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections or at a level crossing;</li> <li>(iv) Contain no more than 40 characters and no more than 6 words, symbols, or graphics;</li> <li>(v) Have lettering that is at least 200mm high; and</li> <li>(vi) Where the sign directs traffic to a site entrance, it must be at least: <ul style="list-style-type: none"> <li>(vii) 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(viii) 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>(b) Glare and artificial light spill; and</li> <li>(c) Content, colour and location of the sign.</li> </ul>
--	--	--

KLZ – Kimihia lakes zone

<p><b>SIGN-R47</b> KLZ – Kimihia lakes zone</p>	<p>Signs – general</p> <p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must not exceed 3m<sup>2</sup>;</li> <li>(b) The sign height must not exceed 10m;</li> <li>(c) Illuminated signs visible from the outside of the site must not: <ul style="list-style-type: none"> <li>(i) Have a light source that flashes or moves;</li> </ul> </li> <li>(d) Contain moving parts or reflective materials;</li> <li>(e) Signs must be set back at least 7.5m from an external zone boundary;</li> <li>(f) Signs must be set back at least 15m from the designation of the Waikato Expressway;</li> <li>(g) Any sign visible from the outside of the site must relate to:</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Effects on traffic safety;</li> <li>(c) Effects of glare and light spill;</li> <li>(d) Content, colour and location of the sign; and</li> <li>(e) Proximity to the road.</li> </ul>
---	--	---

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(i) An event within the KLZ – Kimihia Lakes zone; or</li> <li>(ii) A property name sign.</li> </ul> <p>(h) No more than one sign shall be directed at users of the Waikato Expressway and must:</p> <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign; or</li> <li>(ii) Contain no more than 40 characters and no more than 6 symbols; and</li> <li>(iii) Have lettering that is at least 200mm high</li> </ul>	
--	---	--

MSRZ – Motorsport and recreation zone

<b>SIGN-R48</b>	Signs – general – all precincts	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign visible from a public place shall comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) It does not exceed 5m<sup>2</sup> in area;</li> <li>(ii) The sign height does not exceed 10m in height;</li> <li>(iii) Illuminated signs shall not:</li> <li>(iv) Have a light source that flashes or moves;</li> <li>(v) Contain moving parts or reflective materials;</li> <li>(vi) It is set back at least 7.5m from the boundary of Hampton Downs Road;</li> <li>(vii) It is set back at least 15m from State Highway 1;</li> <li>(viii) Is orientated to be internally facing or it is setback a minimum of 500m from State Highway 1 and have a font height no greater than 300 mm and have symbols, parts of symbols, images and/or parts of images of a height no greater than 300 mm, or cannot be seen from State Highway 1;</li> <li>(ix) It relates to: <ul style="list-style-type: none"> <li>(1) Any motor sport and recreation activity or</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Effects on traffic safety;</li> <li>(c) Effects of glare and light spill;</li> <li>(d) Content, colour and location of the sign; and</li> <li>(e) Proximity to the road.</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>events within the Motorsport and Recreation Zone; or</p> <p>(2) A property name sign.</p> <p>Advice note: the above does not apply to “temporary traffic management” signs.</p>	
<b>SIGN-R49</b>	Signs – general – all precincts	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate sign relating to the site on which it is located shall comply with all of the following standards:</p> <p>(i) There is no more than 3 signs per site of which;</p> <p>(1) There is no more than 1 sign per agency measuring 600mm x 900mm;</p> <p>(2) There is no more than 1 sign measuring 1800mm x 1200mm: and</p> <p>(3) There is no more than 1 real estate header sign measuring 1800mm x 1200mm;</p> <p>(ii) It is not illuminated;</p> <p>(iii) It does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</p> <p>(iv) It does not project into or over road reserve.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Effects of glare and light spill;</p> <p>(d) Content, colour and location of the sign; and</p> <p>(e) Proximity to the road.</p>
<b>SIGN-R50</b>	Signs – effects on traffic – all precincts	
MSRZ – Motorsport and recreation zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at road users shall:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign;</p> <p>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and any other signs;</p> <p>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections;</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(iv) Be able to be viewed by drivers for at least 250m;</li> <li>(v) Contain no more than 40 characters and no more than 6 symbols;</li> <li>(vi) Have lettering that is at least 200mm high;</li> <li>(vii) Where the sign directs traffic to a site entrance, the sign must be at least: <ul style="list-style-type: none"> <li>(viii) 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(ix) 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul> </li> </ul>	
--	--	--

MTZ – Matangi zone

<b>SIGN-R51</b>	Signs – general	
MTZ – Matangi zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards (excluding where not visible from outside of the site on which they are located): <ul style="list-style-type: none"> <li>(i) The sign is wholly contained on the site;</li> <li>(ii) The sign height must not exceed 10m;</li> <li>(iii) Where the sign is illuminated it must: <ul style="list-style-type: none"> <li>(1) Not have a light source that flashes or moves;</li> <li>(2) Not contain moving parts or reflective materials; and</li> <li>(3) Be focused to ensure that it does not spill light beyond the site.</li> </ul> </li> <li>(iv) Where the sign is attached to a building, it must: <ul style="list-style-type: none"> <li>(1) Not extend more than 400mm from the building wall; and</li> <li>(2) Not exceed the height of the building.</li> <li>(3) Where the sign is a freestanding sign and can</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Effects on traffic safety;</li> <li>(c) Effects of glare and artificial light spill;</li> <li>(d) Content, colour and location of the sign;</li> <li>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign; and</li> <li>(f) Effects on notable architectural features of the building.</li> </ul>

	<p>be viewed from a public space, it must:</p> <p>(4) Not exceed an area of 3m<sup>2</sup> for one sign per site, and 1m<sup>2</sup> for one additional freestanding sign on the site; and</p> <p>(5) Be set back at least 5m from the boundary of any adjoining RLZ – Rural lifestyle zone.</p> <p>(v) The sign is not attached to a heritage item listed in SCHED I – Historic heritage items) except for the purpose of identification and interpretation; and</p> <p>(vi) The sign relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) A property name sign (which includes tenants of the site).</p>	
<b>SIGN-R52</b>	Signs – general	
MTZ – Matangi zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate sign must comply with all of the following standards:</p> <p>(i) It relates to the sale of the site on which it is located;</p> <p>(ii) There is no more than 3 signs per site;</p> <p>(iii) The sign is not illuminated; and</p> <p>(iv) The sign does not contain any moving parts, florescent, flashing or revolving lights or reflective materials.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Effects of glare and artificial light spill;</p> <p>(d) Content, colour and location of the sign;</p> <p>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign; and</p> <p>(f) Effects on notable architectural features of the building.</p>
<b>SIGN-R53</b>	Signs – effects on traffic	
MTZ – Matangi zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign directed at road users must meet the following standards:</p> <p>(i) Not imitate the content, colour or appearance of any traffic control sign;</p> <p>(ii) Be located at least 60m from controlled intersections,</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Effects on traffic safety;</p> <p>(c) Effects of glare and artificial light spill;</p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>pedestrian crossings and any other sign;</p> <p>(iii) Not obstruct sight lines of drivers turning into, or out of, a site entrance and intersections or at a railway level crossing; and</p> <p>(iv) Contain no more than 40 characters and no more than 6 symbols; and</p> <p>(v) Have lettering that is at least 150mm high.</p>	<p>(d) Content, colour and location of the sign;</p> <p>(e) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign; and</p> <p>(f) Effects on notable architectural features of the building.</p>
--	---	---

RPZ – Rangitahi Peninsula zone

<b>SIGN-R54</b>	Signs – general	
RPZ – Rangitahi Peninsula zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A sign visible from a public place must comply with all of the following standards:</p> <p>(i) It is the only sign on the site;</p> <p>(ii) It is wholly contained on the site;</p> <p>(iii) It does not exceed 0.25m<sup>2</sup>;</p> <p>(iv) The sign height does not exceed 2m;</p> <p>(v) It is not illuminated;</p> <p>(vi) It does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</p> <p>(vii) It relates to:</p> <p>(1) Goods or services available on the site; or</p> <p>(2) It is a property name sign; or</p> <p>(3) It is a public information sign erected by a public authority; or</p> <p>(4) It is a temporary sign on display for no more than 3 months.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p> <p>(c) Effects on traffic safety;</p> <p>(d) Glare and artificial light spill; and</p> <p>(e) Content, colour and location of the sign.</p>
<b>SIGN-R55</b>	Signs – general	
RPZ – Rangitahi Peninsula zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A real estate 'for sale' sign relating to the site on which it is located must not:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Amenity values;</p> <p>(b) Character of the locality;</p>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(i) Have more than 3 signs per site; and</li> <li>(ii) Be illuminated; and</li> <li>(iii) Contain any moving parts, fluorescent, flashing or revolving lights or reflective materials; and</li> <li>(iv) Project into or over road reserve.</li> </ul>	<ul style="list-style-type: none"> <li>(c) Effects on traffic safety;</li> <li>(d) Glare and artificial light spill; and</li> <li>(e) Content, colour and location of the sign.</li> </ul>
<b>SIGN-R56</b>	Signs – effects on traffic	
RPZ – Rangitahi Peninsula zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road users must: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign; and</li> <li>(ii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections; and</li> <li>(iii) Contain maximum 40 characters and 6 symbols; and</li> <li>(iv) Have lettering that is at least 150mm high; and</li> <li>(v) Where the sign directs traffic to a site entrance, the sign must be at least 130m from the entrance.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

TKAZ – Te Kowhai airpark zone

<b>SIGN-R57</b>	Signs – general	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where</b></p> <ul style="list-style-type: none"> <li>(a) Any sign located in PREC27 or PREC28 that is visible from a public place or site in another zone must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) The sign height does not exceed 10m;</li> <li>(ii) Where the sign is attached to a building, it must not: <ul style="list-style-type: none"> <li>(1) Extend more than 300mm from the external wall of the building; and</li> <li>(2) Exceed the height of the building,</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Visual impact of the sign;</li> <li>(c) Nature, scale and location;</li> <li>(d) Streetscape;</li> <li>(e) Effects on any other site in the locality;</li> <li>(f) Glare and light spill; and</li> <li>(g) Traffic safety.</li> </ul>

	<p>(iii) Where the sign is a free-standing sign, it must:</p> <p>(1) Not exceed an area of 3m<sup>2</sup> for one sign per site; and 1m<sup>2</sup> for any other free-standing sign on the site; and</p> <p>(2) Be set back at least 5m from the boundary of any site in the Village LLRZ – Large lot Residential zone or SETZ – Settlement zone,</p> <p>(iv) Where the sign is illuminated, it must:</p> <p>(1) Not have a light source that flashes or moves; and</p> <p>(2) Not contain moving parts or reflective materials; and</p> <p>(3) Be directed to ensure it does not spill light beyond the site.</p>	
<p><b>SIGN-R58</b></p>	<p>Signs – general</p>	
<p>TKAZ – Te Kowhai airpark zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any sign located in PREC29 or PREC30 that is visible from a public place or site in another zone must:</p> <p>(i) Relate to goods or services available on the site; or</p> <p>(ii) Be a property name sign; and</p> <p>(iii) Be the only sign on the site; and</p> <p>(iv) Not be illuminated, flashing or moving; and</p> <p>(v) Not exceed 0.25m<sup>2</sup>; and</p> <p>(vi) Not exceed 2m in height.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Visual impact of the sign;</p> <p>(c) Nature, scale and location;</p> <p>(d) Streetscape;</p> <p>(e) Effects on any other site in the locality;</p> <p>(f) Glare and light spill; and</p> <p>(g) Traffic safety.</p>
<p><b>SIGN-R59</b></p>	<p>Signs – general</p>	
<p>TKAZ – Te Kowhai airpark zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) In all precincts, a real estate sign relating to the site on which it is located must comply with all of the following standards:</p> <p>(i) There are no more than 3 signs per site of which:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Visual impact of the sign;</p> <p>(c) Nature, scale and location;</p> <p>(d) Streetscape;</p> <p>(e) Effects on any other site in the locality;</p>



Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<ul style="list-style-type: none"> <li>(ii) There is no more than 1 sign per agency measuring 600mm x 900mm;</li> <li>(iii) There is no more than 1 sign measuring 1800mm x 1200mm; and</li> <li>(iv) There is no more than 1 real estate header sign measuring 1800mm x 1200mm.</li> </ul>	<ul style="list-style-type: none"> <li>(f) Glare and light spill; and</li> <li>(g) Traffic safety.</li> </ul>
<b>SIGN-R60</b>	Signs – general	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) In all precincts, a sign advertising a community event or temporary event must: <ul style="list-style-type: none"> <li>(i) Be on display for no more than 3 months prior to the event; and</li> <li>(ii) Be removed no later than 5 days after the event.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Visual impact of the sign;</li> <li>(c) Nature, scale and location;</li> <li>(d) Streetscape;</li> <li>(e) Effects on any other site in the locality;</li> <li>(f) Glare and light spill; and</li> <li>(g) Traffic safety.</li> </ul>
<b>SIGN-R61</b>	Signs – effects on traffic	
TKAZ – Te Kowhai airpark zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) In all precincts, any sign directed at road users must: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign; and</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and any other sign; and</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections; and</li> <li>(iv) Contain no more than 40 characters and no more than 6 words and / or symbols; and</li> <li>(v) Have lettering that is at least 150mm high; and</li> <li>(vi) Where the sign directs traffic to a site entrance, the sign must be at least 130m from the entrance.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values, including cumulative effects;</li> <li>(b) Effects on the safe and efficient operation of the road land transport</li> <li>(c) Size and number of characters, words and symbols;</li> <li>(d) Size of sign and support structure;</li> <li>(e) Visual appearance.</li> </ul>

TTZ – TaTa Valley zone

<b>SIGN-R62</b>	Signs – general	
TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A sign must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) It is the only sign on the site;</li> <li>(ii) The sign is wholly contained on the site;</li> <li>(iii) The sign does not exceed 5m<sup>2</sup>;</li> <li>(iv) The sign height does not exceed 3m;</li> <li>(v) If illuminated, the sign meets the lighting standards of Rule LIGHT-R2,</li> <li>(vi) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(vii) The sign is set back at least 50m from a state highway and the Waikato Expressway;</li> <li>(viii) The sign is not attached to a notable tree identified in SCHED2 – Notable trees, except for the purpose of identification;</li> <li>(ix) The sign is not attached to a heritage item listed in SCHED1 – Historic heritage items except for the purpose of identification and interpretation;</li> <li>(x) The sign is for the purpose of identification and interpretation of a site and area of significance to Maaori listed in SCHED3 – Sites and areas of significance to Maaori;</li> <li>(xi) The sign relates to: <ul style="list-style-type: none"> <li>(1) Goods or services available on the site; or</li> <li>(2) A property name sign.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> <li>(b) Rural character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(i) Effects on notable architectural features of the building.</li> </ul>
<b>SIGN-R63</b>	Signs – general	
TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A real estate sign relating to the site on which it is located must</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity values;</li> </ul>

Part 2: District-wide matters / General district-wide matters / SIGN – Signs

	<p>comply with all of the following standards:</p> <ul style="list-style-type: none"> <li>(i) Have no more than 3 signs per site;</li> <li>(ii) The sign is not illuminated;</li> <li>(iii) The sign does not contain any moving parts, fluorescent, flashing or revolving lights or reflective materials;</li> <li>(iv) The sign does not exceed 3m<sup>2</sup>;</li> <li>(v) Any real estate sign shall be removed within 20 working days of the sale or lease being settled.</li> </ul>	<ul style="list-style-type: none"> <li>(b) Rural character of the locality;</li> <li>(c) Effects on traffic safety;</li> <li>(d) Effects of glare and artificial light spill;</li> <li>(e) Content, colour and location of the sign;</li> <li>(f) Effects on notable trees;</li> <li>(g) Effects on the heritage values of any heritage item due to the size, location, design and appearance of the sign;</li> <li>(h) Effects on cultural values of any SASM – Sites and areas of significance to Maaori; and</li> <li>(b) Effects on notable architectural features of the building.</li> </ul>
<b>SIGN-R64</b>	Signs - effects on traffic	
TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any sign directed at road users must meet the following standards: <ul style="list-style-type: none"> <li>(i) Not imitate the content, colour or appearance of any traffic control sign;</li> <li>(ii) Be located at least 60m from controlled intersections, pedestrian crossings and railway crossings</li> <li>(iii) Not obstruct sight lines of drivers turning into or out of a site entrance and intersections;</li> <li>(iv) Contain no more than 40 characters and no more than 6 words, symbols, or graphics;</li> <li>(v) Have lettering that is at least 200mm high; and</li> <li>(vi) Where the sign directs traffic to a site entrance, it must be at least: <ul style="list-style-type: none"> <li>(vii) 175m from the entrance on roads with a speed limit of 80 km/hr or less; or</li> <li>(viii) 250m from the entrance on roads with a speed limit of more than 80km/hr.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

## TEMP – Temporary activities

*The relevant area specific zone chapter provisions apply in addition to this chapter.*

### Overview

Temporary activities are short term activities and events that contribute to the social, economic and cultural wellbeing of the community.

Temporary activities have the potential to generate adverse effects, particularly resulting from noise and traffic.

### Objective

TEMP-O1 Temporary events in the OSZ – Open space zone.

Temporary events remain ancillary to, and promote the purpose of, the reserve.

### Policies

TEMP-P1 Temporary events in the GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, LLRZ – Large lot residential zone, SETZ – Settlement zone or RLZ – Rural lifestyle zone.

(1) Enable temporary events and associated temporary structures, provided any adverse effects on the residential environment are managed by:

- (a) Limiting the timing, number and duration of temporary events; and
- (b) Limiting noise generated by the temporary events to the permitted noise limits for the zone.

TEMP-P2 Temporary events in the GRUZ – General rural zone

(1) Enable temporary events and associated structures, provided adverse effects are managed by:

- (a) Limiting the timing, and duration of any temporary event; and
- (b) Limiting noise generated by the temporary events to the permitted noise limits for the zone.

TEMP-P3 Temporary events in the LCZ – Local centre zone, TCZ – Town centre zone or COMZ – Commercial zone.

(1) Enable temporary events and associated temporary structures within the zone, provided any adverse effects on amenity are managed through:

- (a) Limits on the timing, number and duration of events; and
- (b) Meeting the permitted noise limits for the zone.

TEMP-P4 Temporary events in the OSZ – Open space zone.

(1) Enable temporary events and associated temporary structures on reserves, appropriate to the size and purpose of the reserve.

- (2) Manage the scale and extent of temporary events on reserves so that any significant adverse effects on people in the surrounding community are minimised by:
- (a) Limits on the timing, number and duration of events;
  - (b) Meeting the permitted noise limits for the zone; and
  - (c) Managing the effects of traffic on the road transport network.

TEMP-P5 Cultural events and temporary events in the HOPZ – Hopuhopu zone.

Enable cultural events, and temporary events and associated temporary structures provided any adverse effects are managed.

## Rules

*Land use – effects*

*Zone as specified in first column*

<b>TEMP-RI</b>	Temporary event	
<ul style="list-style-type: none"> <li>• LLRZ – Large lot residential zone;</li> <li>• GRZ – General residential zone;</li> <li>• MRZ1 – Medium density residential zone 1;</li> <li>• MRZ2 – Medium density residential zone 2;</li> <li>• RLZ – Rural lifestyle zone;</li> <li>• SETZ – Settlement zone;</li> <li>• LCZ – Local centre zone;</li> <li>• COMZ – Commercial zone;</li> <li>• TCZ – Town centre zone;</li> <li>• BTZ – Business Tamahere zone; and</li> <li>• PREC31 – Lakeside Te Kauwhata Precinct in the GRZ – General residential zone.</li> </ul>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The event occurs no more than 3 times per consecutive 12 month period;</li> <li>(b) The duration of each temporary event is less than 72 hours;</li> <li>(c) It may operate between 7.30am and 8:30pm Monday to Sunday;</li> <li>(d) Temporary structures are:                             <ul style="list-style-type: none"> <li>(i) Erected no more than 2 days before the temporary event occurs;</li> <li>(ii) Removed no more than 3 days after the end of the event;</li> </ul> </li> <li>(e) The site is returned to its previous condition no more than 3 days after the end of the temporary event;</li> <li>(f) There is no direct site access from a national route or regional arterial road.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>TEMP-R2</b>	Temporary military training activities	

<p>All zones</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) The activity must comply with the permitted activity noise standards for Temporary Military Training Activities:                  (i) The duration must be less than 31 days (excluding set up and pack down);                  (ii) The site must be returned to its original condition no more than 3-days after the end of the Temporary Military Training Activity, unless provided for elsewhere in this plan as a permitted activity.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b>                  (a) Effects on amenity values;                  (b) Timing and duration; and                  (c) Hours and days of Temporary Military Training Activities.</p>
<p><b>TEMP-R3</b></p>	<p>Noise – Temporary military training activities (other than the firing of weapons or use of explosives)</p>	
<p>All zones</p>	<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) Mobile noise sources, including personnel and light and heavy vehicles, self-propelled equipment, earthmoving equipment, shall comply with the noise limits set out in Tables 2 and 3 of NZS6803:1999 Acoustics – Construction Noise (with reference to ‘construction noise’ taken to refer to mobile noise sources).                  (b) Fixed (stationary) noise sources including power generation, heating, ventilation or air conditioning systems, or water or wastewater pumping/treatment systems, shall comply with the noise limits set out below when measured at the notional boundary of any building housing a noise sensitive activity:                  (i) 55dB L<sub>Aeq</sub>, 7am to 7pm every day.                  (ii) 50dB L<sub>Aeq</sub>, 7pm to 10pm every day.                  (iii) 45dB L<sub>Aeq</sub> and 75dB (L<sub>max</sub>), 10pm to 7am the following day</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b>                  (a) Effects on amenity values;                  (b) Timing and duration; and                  (c) Hours and days of Temporary Military Training Activities.</p>

	(c) Helicopter landing areas shall comply with NZS6807:1994 Noise Management and Land Use Planning for Helicopter Landing Areas. Noise levels shall be measured in accordance with NZS6801:2008 Acoustics – Measurement of Sound.	
<b>TEMP-R4</b>	Noise – Temporary military training activities (which involve the firing of weapons or use of explosives)	
All zones	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Notice is provided to the Council at least 5 working days prior to the commencement of the activity.</p> <p>(b) The activity complies with the following minimum separation distances to the notional boundary of any building housing a noise sensitive activity:</p> <p>(i) 0700 to 1900 hours: 500m</p> <p>(ii) 900 to 0700 hours: 1,250m</p> <p>(c) Where the minimum separation distances specified above cannot be met, then the activity shall comply with the following peak sound pressure level when measured at the notional boundary of any building housing a noise sensitive activity:</p> <p>(i) 0700 to 1900 hours: 95 dBC</p> <p>(ii) 1900 to 0700 hours: 85 dBC</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values;</p> <p>(b) Timing and duration; and</p> <p>(c) Hours and days of Temporary Military Training Activities.</p>

*GRUZ – General rural zone*

<b>TEMP-R5</b>	Temporary event	
GRUZ – General rural zone; FUZ – Future urban zone; CORZ – Corrections zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The event occurs no more than 6 times per consecutive 12 month period;</p> <p>(b) The duration of each event is less than 72 hours;</p> <p>(c) It may operate between 7.30am to 8:30pm Monday to Sunday;</p> <p>(d) Temporary structures are:</p> <p>(i) erected no more than 2 days before the event occurs;</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

Part 2: District-wide matters / General district-wide matters / TEMP – Temporary activities

	<ul style="list-style-type: none"> <li>(ii) removed no more than 3 days after the end of the event;</li> <li>(e) The site is returned to its previous condition no more than 3 days after the end of the event;</li> <li>(f) There is no direct site access from a national route or regional arterial road.</li> </ul>	
<b>TEMP-R6</b>	Temporary event within a Whaanga Coast development specific control area of PREC5 – Whaanga Coast development precinct	
PREC5 – Whaanga Coast development precinct	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The duration of each event is less than 72 hours;</li> <li>(i) It may operate between 7:30am to 8:30pm Monday to Sunday;</li> <li>(ii) Temporary structures are: <ul style="list-style-type: none"> <li>(1) erected no more than 2 days before the event occurs;</li> <li>(2) removed no more than 3 days after the end of the event</li> </ul> </li> <li>(b) Rule TEMP-R5 does not apply.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>TEMP-R7</b>	Temporary event within PREC31 – Lakeside Te Kauwhata precinct	
PREC31 – Lakeside Te Kauwhata precinct in the GRUZ – General rural zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The event occurs no more than 3 times per consecutive 12 month period;</li> <li>(b) The duration of each event is less than 72 hours;</li> <li>(c) It may operate between 7.30am to 8:30pm Monday to Sunday;</li> <li>(d) Temporary structures are: <ul style="list-style-type: none"> <li>(i) Erected no more than 2 days before the event occurs;</li> <li>(ii) Removed no more than 3 days after the end of the event;</li> </ul> </li> <li>(e) The site is returned to its previous condition no more than 3 days after the end of the event;</li> <li>(f) There is no direct site access from a national route or regional arterial road.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>



	(g) Rule TEMP-R5 does not apply.	
--	----------------------------------	--

OSZ – Open space zone

<b>TEMP-R8</b>	Temporary event	
OSZ – Open space zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The event occurs no more than 15 times per consecutive 12-month period;</li> <li>(b) It operates between the hours of 7.30am and 8:30pm Monday to Sunday;</li> <li>(c) Temporary structures are:                             <ul style="list-style-type: none"> <li>(i) Erected no more than 2 days before the event occurs;</li> <li>(ii) Removed no more than 3 days after the end of the event;</li> </ul> </li> <li>(d) The site is returned to its previous condition no more than 3 days after the end of the event;</li> <li>(e) There is no direct site access from a national route or regional arterial road.</li> <li>(f) Consistency with the relevant Reserve Management Plan.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

HOPZ – Hopuhopu zone

<b>TEMP-R9</b>	Temporary event	
HOPZ – Hopuhopu zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The event occurs no more than 15 times per consecutive 12 month period;                             <ul style="list-style-type: none"> <li>(i) The duration of each event is less than 72 hours;</li> <li>(ii) It may only operate between 7.30am to 8:30pm Monday to Sunday;</li> <li>(iii) Temporary structures are:                                     <ul style="list-style-type: none"> <li>(1) Erected no more than 7 days before the event occurs;</li> <li>(2) Removed no more than 3 days after the end of the event;</li> </ul> </li> <li>(iv) The site of the event is returned to its previous</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Duration and frequency;</li> <li>(b) Effects on traffic;</li> <li>(c) Traffic safety; and</li> <li>(d) Effects on amenity values.</li> </ul>

	condition no more than 3 days after the end of the event; and (v) There is no direct site access from a national route or regional arterial road.	
--	--	--

KLZ – Kimihia lakes zone

<b>TEMP-R10</b>	Temporary event	
KLZ – Kimihia lakes zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The duration of each event must be less than 72 hours;</li> <li>(b) The event may operate between 7.30am to 8:30pm Monday to Sunday;</li> <li>(c) Temporary structures must be removed no more than 3 days after the end of the event;</li> <li>(d) The site must be returned to its previous condition no more than 3 days after the end of the event;</li> <li>(e) Any activity attracting more than 1,100 people in any given hour must provide a Traffic Management Plan (TMP) for approval by the Road Controlling Authority. The TMP must include, but is not limited to:                             <ul style="list-style-type: none"> <li>(i) Proposed timing and scale of activities, including the contact details for the event organiser;</li> <li>(ii) Consideration of potential conflict with events at the Huntly Speedway;</li> <li>(iii) Details of active traffic management at the Great South Road / East Mine Road intersection;</li> <li>(iv) Details of journey management initiatives reducing traffic demand at the Great South Road / East Mine Road intersection;</li> <li>(v) Details of temporary on-site parking provision; and</li> <li>(vi) Details of how off-site parking is to be controlled to</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

	avoid parking occurring on the local road network.	
--	--	--

MAZ – Mercer airport zone

TEMP-RI1	Temporary event	
MAZ – Mercer airport zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The temporary event must comply with all of the following standards:                             <ul style="list-style-type: none"> <li>(i) The event occurs no more than 3 times per consecutive 12-month period;</li> <li>(ii) It does not involve motorised outdoor recreation (except flying);</li> <li>(iii) It does not involve outdoor musical events or concerts; and</li> <li>(iv) It operates within the hours of:                                     <ul style="list-style-type: none"> <li>(1) 7.00am to 10pm Monday to Saturday; and</li> <li>(2) 7.00am to 6pm Sunday.</li> </ul> </li> </ul> </li> <li>(b) An air show event occurs only once per consecutive 12 month period.</li> <li>(c) Temporary structures are:                             <ul style="list-style-type: none"> <li>(i) Erected no more than 7 days before the event occurs; and</li> <li>(ii) Removed no more than 7 days after the end of the event.</li> </ul> </li> <li>(d) The site is returned to its original condition no more than 7 days after the end of the event.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity;</li> <li>(b) Noise levels;</li> <li>(c) Timing and duration of the event; and</li> <li>(d) Effects on the safe and efficient operation of the land transport network.</li> </ul>

MTZ – Matangi zone

TEMP-RI2	Temporary event	
MTZ – Matangi zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The event occurs no more than 4 times per consecutive 12 month period;</li> <li>(b) The event may operate between 7.30am and 8:30pm Monday to Sunday; and</li> <li>(c) Temporary structures are:</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Adverse effects of non-compliance with activity-specific standards;</li> </ul>

	<ul style="list-style-type: none"> <li>(i) Erected no more than 2 days before the event occurs; and</li> <li>(ii) Removed no more than 3 days after the end of the event;</li> <li>(d) The site is returned to its previous condition no more than 3 days after the end of the event.</li> </ul>	<ul style="list-style-type: none"> <li>(b) Positive effects on the community or the natural environment;</li> <li>(c) The extent to which the activity is able to avoid, remedy or mitigate adverse effects on the existing and foreseeable future amenity of the area, particularly in relation to noise, traffic generation, material deposited on roads, dust, odour and lighting; and</li> <li>(d) The extent to which the proposal, development, excavation or subdivision of a historic heritage site or place is consistent with the identified heritage values, including scale, design, form, style, bulk, height, materials and colour, and retains, protects or enhances the historic setting.</li> </ul>
--	--	--

RPZ – Rangitahi Peninsula zone

<b>TEMP-R13</b>		
<p>RPZ – Rangitahi Peninsula zone</p>	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Is located within Plan 1 Structure Plan Area - Development Precincts shown on the Rangitahi Peninsula Structure Plan (APP9 – Rangitahi Structure Plan) or any approved subdivision; and</li> <li>(b) The event occurs no more than 3 times per calendar year; and</li> <li>(c) It operates between 7.30am to 8:30pm Monday to Sunday; and</li> <li>(d) Temporary structures are:                             <ul style="list-style-type: none"> <li>(i) Erected no more than 2 days before the event occurs; and</li> <li>(ii) Removed no more than 3 days after the end of the event; and</li> </ul> </li> <li>(e) The site is returned to its original condition no more than 3 days after the end of the event; and</li> <li>(f) There is no direct site access from a national route or regional arterial road.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

TKAZ – Te Kowhai airpark zone

<b>TEMP-RI 4</b>	Temporary events in PREC27, PREC28 or PREC29	
TKAZ – Te Kowhai airpark zone	<p><b>(3) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A temporary event must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) The event occurs no more than 3 times per calendar year;</li> <li>(ii) It does not involve motorised outdoor recreation (except flying);</li> <li>(iii) It does not involve outdoor musical events or concerts;</li> <li>(iv) It operates within the hours of: <ul style="list-style-type: none"> <li>(1) 7.30am to 10pm Monday to Saturday; and</li> <li>(2) 7.30am to 6pm Sunday; and</li> </ul> </li> <li>(v) An air show event occurs only once per calendar year.</li> <li>(vi) Temporary structures are: <ul style="list-style-type: none"> <li>(1) Erected no more than 2 days before the event occurs; and</li> <li>(2) Removed no more than 3 days after the end of the event;</li> </ul> </li> <li>(vii) The site is returned to its original condition no more than 3 days after the end of the event; and</li> <li>(viii) There is no direct site access from a national route or regional arterial road.</li> </ul> </li> </ul>	<p><b>(4) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Amenity;</li> <li>(b) Noise levels;</li> <li>(c) Timing and duration of the event; and</li> <li>(d) Effects on the safe and efficient operation of the land transport network.</li> </ul>
<b>TEMP-RI 5</b>	Temporary events in PREC30	
TKAZ – Te Kowhai airpark zone	<b>(1) Activity status: DIS</b>	

TTZ – TaTa Valley zone

<b>TEMP-RI 6</b>	Temporary events	
TTZ – TaTa Valley zone	<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The duration of the event must not exceed 72 hours;</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p>

	<ul style="list-style-type: none"> <li>(b) Noise levels for temporary events must comply with the limits specified in Rule NOISE-R43;</li> <li>(c) The number of people at the event must not exceed 500;</li> <li>(d) Temporary buildings must:             <ul style="list-style-type: none"> <li>(i) Not exceed a height of 15m, measured from the natural ground level immediately below that part of the structure;</li> <li>(ii) Be erected no more than 2 days before the event occurs;</li> <li>(iii) Be removed no more than 3 days after the end of the event.</li> </ul> </li> <li>(e) The site must be returned to its previous condition no more than 3 days after the end of the event.</li> <li>(f) If taking place outside of the Hotel Area, the event must only occur between the hours of 7:30am and 8:30pm Monday – Sunday.</li> </ul>	<ul style="list-style-type: none"> <li>(a) Traffic effects on the local road network and the adequacy of proposed measures to manage these effects; and</li> <li>(b) Effects on the amenity of surrounding properties.</li> </ul>
--	--	---

## GRZ – General residential zone

*The relevant district-wide chapter provisions apply in addition to this chapter.*

### Purpose

The purpose of the GRZ – General residential zone is to provide predominantly for residential activities with a mix of building types, and other compatible activities. The zone applies to the residential areas within the District's main towns (Tuakau, Pokeno, Te Kauwhata, Raglan, Huntly and Ngaaruawaahia) and the smaller towns (Meremere, Taupiri, Gordonton, Horotiu, Te Kowhai, Whatawhata, Matangi and Rangiriri).

### Objectives

- GRZ-O1 Residential character.  
The low-density residential character of the zone is maintained.
- GRZ-O2 Residential built form and amenity.  
Maintain neighbourhood residential amenity values and facilitate safety in the zone.
- GRZ-O3 On-site residential amenity.  
Maintain amenity values within and around dwellings and sites in the zone.
- GRZ-O4 Housing options.  
A range of housing options occurs in the zone to meet the needs of the community in a suburban setting.
- GRZ-O5 Maintain residential purpose.  
Residential activities remain the dominant activity in the zone.
- GRZ-O6 Adverse effects of land use and development.  
The health, safety and well-being of people, communities and the environment are protected from the adverse effects of land use and development.

### Policies

- GRZ-P1 Character.
- (1) Ensure residential development in the zone:
- (a) Provides road patterns that follow the natural contour of the landform;
  - (b) Promotes views and vistas from public spaces of the hinterland beyond; and
  - (c) Is an appropriate scale and intensity, and setback from the road frontages to provide sufficient open space for the planting of trees and private gardens.
- GRZ-P2 Front setback.
- (1) Ensure buildings are designed and set back from roads by:

Part 3: Area-specific matters / Zones / Residential zones / GRZ – General residential zone

- (a) Maintaining the existing street character including the predominant building setback from the street;
- (b) Allowing sufficient space for the establishment of gardens and trees on the site; and
- (c) Providing for passive surveillance to roads and avoiding windowless walls to the street.

GRZ-P3 Setback side boundaries.

(1) Require development to have sufficient side boundary setbacks to provide for:

- (a) Planting;
- (b) Privacy; and
- (c) Sunlight and daylight.

(2) Reduced side boundary setbacks occur only where it:

- (a) Enables effective development of sites where on-site topographic constraints occur; or
- (b) Retains trees on the site.

GRZ-P4 Height.

Ensure building height is complementary to the low rise character of the zone.

GRZ-P5 Site coverage and permeable surfaces.

(1) Ensure all sites have sufficient open space to provide for landscaping, on-site stormwater disposal, parking, and vehicles manoeuvring by maintaining maximum site coverage requirements for buildings in the zone.

(2) Ensure a proportion of each site is maintained in permeable surfaces in order to ensure there is sufficient capacity to enable disposal of stormwater.

GRZ-P6 Building scale.

Facilitate quality development by ensuring buildings are a complementary height, bulk and form for the site, and are in keeping with the amenity values of the street.

GRZ-P7 Reverse sensitivity.

(1) Avoid or minimise the potential for reverse sensitivity by managing the location and design of sensitive activities through:

- (a) The use of building setbacks;
- (b) The design of subdivisions and development; and
- (c) Acoustic insulation requirements for noise sensitive activities.

GRZ-P8 Daylight and outlook.

(1) Maintain adequate daylight and enable opportunities for passive solar gain.

(2) Require the height, bulk and location of development to maintain sunlight access and privacy, and to minimise visual dominance effects on adjoining sites.



Part 3: Area-specific matters / Zones / Residential zones / GRZ – General residential zone

- (3) Maintain and enhance attractive open space character of residential areas by ensuring that development is compatible in scale to surrounding activities and structures and has on-site landscaping, screening and street planting.

GRZ-P9 Outdoor living space – residential units.  
Require outdoor living spaces to be accessible and usable.

GRZ-P10 Outdoor living space – retirement villages.  
Require outdoor living spaces or communal outdoor living spaces to be usable and accessible.

GRZ-P11 Housing types.  
Enable a variety of housing types in the zone where it is connected to public reticulation, including minor residential units and retirement villages.

GRZ-P12 Retirement villages.

- (1) Provide for the establishment of new retirement villages and care facilities that:

- (a) Offer a diverse range of housing types, including care facilities, for the particular needs and characteristics of older people;
- (b) Promote visual integration with the street scene, neighbourhoods and adjoining sites;
- (c) Are comprehensively designed and managed and offer a variety of accommodation and accessory services that meet the needs of residents, including those requiring care or assisted living;
- (d) Recognise that housing and care facilities for older people can require higher densities;
- (e) Provide high quality on-site amenity;
- (f) Integrate with local services and facilities, including public transport; and
- (g) Connect to alternative transport modes to the LLRZ – Large lot residential zone, SETZ – Settlement zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2, GRZ – General residential zone, TCZ – Town centre zone, LCZ – Local centre zone or COMZ – Commercial zone.

- (2) Enable alterations and additions to existing retirement villages that:

- (a) Promote visual integration with the street scene, neighbourhoods and adjoining sites;
- (b) Recognise that housing and care facilities for older people can require higher densities;
- (c) Provide high quality on-site amenity; and
- (d) Integrate with local services and facilities, including public transport and alternative transport modes.

GRZ-PI3 Maintain residential purpose.

Restrict the establishment of commercial or industrial activities, unless the activity has a strategic or operational need to locate within a residential zone, and the effects of such activities on the character and amenity of residential zones are insignificant.

GRZ-PI4 Bankart Street and Wainui.

Provide for the ongoing change in the mixture of residential and commercial activities bordering identified commercial areas at Raglan.

GRZ-PI5 Non-residential activities.

(1) Maintain the zone for residential activities by:

- (a) Ensuring the number of non-residential activities are not dominant within a residential block;
- (b) Ensuring non-residential activities are in keeping with the scale and intensity of development anticipated by the zone and contribute to the amenity of the neighbourhood;
- (c) Enabling non-residential activities that provide for the health, safety and well-being of the community and that service or support an identified local need;
- (d) Avoiding the establishment of new non-residential activities on rear sites, or sites located on cul-de-sacs, or that have access to national routes, regional arterial roads and arterial roads; and
- (e) Ensuring that the design and scope of non-residential activities and associated buildings:
  - (i) Maintain residential character including the scale and design of buildings and their location on the site, and on-site parking and vehicle manoeuvring areas; and
  - (ii) Mitigate adverse effects related to traffic generation, access, noise, vibration, outdoor storage of materials and light spill, to the extent that they minimise adverse effects on residential character and amenity and the surrounding transport network.

(2) Enable existing non-residential activities to continue and support their redevelopment and expansion provided they do not have a significant adverse effect on the character and amenity of the zone.

GRZ-PI6 Home businesses.

- (1) Provide for home businesses to allow flexibility for people to work from their homes.
- (2) Manage the adverse effects on residential amenity through limiting home businesses to a scale that is compatible with the level of amenity anticipated in the residential environment.

GRZ-PI7 Neighbourhood centres in structure plan areas.

- (1) Provide for new neighbourhood centres within structure plan areas or master plan areas, that:
  - (a) Are for the daily retail and service needs of the community; and

- (b) Are located within a walkable catchment.

GRZ-P18 Outdoor storage.

- (a) The adverse visual effects of outdoor storage are mitigated through screening or landscaping.

GRZ-P19 Objectionable odour.

- (1) Ensure that the effects of objectionable odour do not detract from the amenity of other sites.
- (2) Maintain appropriate setback distances between new sensitive land uses and existing lawfully established activities that generate objectionable odour.

## Rules

### Land use – activities

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use effects standards and Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>GRZ-RI</b>	Residential activity, unless specified below  This includes occupation of a single residential unit for short term rental.	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>GRZ-R2</b>	A new retirement village or alterations to an existing retirement village	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The site or combination of sites where the retirement village is proposed to be located has a minimum net site area of 3ha; (b) The site is either serviced by or within 400m walking distance of public transport; (c) The site is connected to public water and wastewater infrastructure; (d) Minimum outdoor living space or balcony area and dimensions: (i) Apartment – 10m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m; (ii) Studio unit or 1 bedroom unit – 12.5m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m; or (iii) 2 or more bedroomed unit – 15m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m; (e) Minimum service court is either:		<b>(2) Activity status where compliance not achieved: DIS</b>

Part 3: Area-specific matters / Zones / Residential zones / GRZ – General residential zone

<ul style="list-style-type: none"> <li>(i) Apartment – Communal outdoor space (ie no individual service courts required); or</li> <li>(ii) All other units – 10m<sup>2</sup> for each unit;</li> <li>(f) Building height does not exceed 8m, measured from the natural ground level immediately below the structure, except for 15% of the total building coverage, where buildings may be up to 10m high; and</li> <li>(g) The following land use – building standards do not apply:             <ul style="list-style-type: none"> <li>(i) GRZ-S2 (Residential units);</li> <li>(ii) GRZ-S4 – GRZ-S6 (Building Height);</li> <li>(iii) GRZ-S14 – GRZ-S15 (Outdoor living space);</li> <li>(iv) GRZ-S16 (Service Court).</li> </ul> </li> </ul>	
<b>GRZ-R3</b>	Home business
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) It is wholly contained within a building;</li> <li>(b) The storage of materials or machinery associated with the home business are either wholly contained within a building or are screened so as not to be visible from a public road or neighbouring residential property;</li> <li>(c) No more than 2 people who are not permanent residents of the site are employed at any one time;</li> <li>(d) Unloading and loading of vehicles or the receiving of customers or deliveries only occur between 7:30am and 7:00pm on any day;</li> <li>(e) Machinery may only be operated between 7:30am and 9pm on any day.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRZ-R4</b>	Community facility
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRZ-R5</b>	Neighbourhood park
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRZ-R6</b>	Home stay
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) No more than 4 temporary residents.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRZ-R7</b>	Neighbourhood centre

<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Must be within an area identified in a Council approved Structure Plan or Master Plan.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-R8</b></p>	<p>Commercial activity</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Must be within the Bankart Street and Wainui Road Business Overlay Area.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-R9</b></p>	<p>Childcare facility</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) For up to 4 children that are not permanent residents of the household unit.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-R10</b></p>	<p>Buildings, structures and sensitive land uses within the National Grid Yard in sites existing as of 18 July 2018</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Within the National Grid Yard:                  (i) Building alterations and additions to an existing building or structure for a sensitive land use that does not involve an increase in the building height or footprint;                  (ii) New, or additions to existing buildings or structures that are not for a sensitive land use;                  (iii) Infrastructure (other than for the reticulation and storage of water for irrigation purposes) undertaken by a network utility operator as defined in the Resource Management Act 1991                  (iv) Fences less than 2.5m in height, measured from the natural ground level immediately below.                  (b) All buildings or structures permitted by Rule GRZ-R10(1)(a) must:                  (i) Comply with the New Zealand Electrical Code of Practice for Electrical Safe Distances 34:2001 ISSN 0114-0663 under all National Grid transmission line operating conditions; and                  (ii) Locate a minimum of 12m from the outer visible foundation of any National Grid support structure and associated stay wire, unless it is one of the following:</p>	<p><b>(2) Activity status where compliance not achieved: NC</b></p>

<p>(1) A building or structure where Transpower has given written approval in accordance with clause 2.4.1 of the NZECP34:2001 ISSN 0114-0663;</p> <p>(2) Fences less than 2.5m in height, measured from the natural ground level immediately below, and located a minimum of 5m from the nearest National Grid support structure foundation;</p> <p>(3) Network utilities (other than for the reticulation and storage of water for irrigation purposes) or any part of electricity infrastructure undertaken by a network utility operator as defined in the Resource Management Act 1991, that connects to the National Grid; and</p> <p>(iii) Not permanently physically impede existing vehicular access to a National Grid support structure.</p>	
<b>GRZ-R11</b>	Construction or alteration of a building for a sensitive land use
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards:</p> <p>(i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or</p> <p>(ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Effects on the amenity values of the site;</p> <p>(b) The risk of electrical hazards affecting the safety of people;</p> <p>(c) The risk of damage to property; and</p> <p>(d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.</p>
<b>GRZ-R12</b>	Construction, demolition, addition, and alteration of a building or structure
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRZ-R13</b>	<p>Educational facilities</p> <p>This excludes childcare facilities.</p>

<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b> Nil</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The extent to which it is necessary to locate the activity in the GRZ - General residential zone;</li> <li>(b) Reverse sensitivity effects of adjacent activities;</li> <li>(c) The extent to which the activity may adversely impact on the transport network;</li> <li>(d) The extent to which the activity may adversely impact on the streetscape and the amenity of the neighbourhood;</li> <li>(e) The extent to which the activity may adversely impact on the noise environment.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRZ-R14</b>	The establishment of any new sensitive land use within the National Grid Yard
<b>(1) Activity status: NC</b>	
<b>GRZ-R15</b>	Any new building within the Huntly North Wetland specific control identified on the planning maps
<b>(1) Activity status: NC</b>	
<b>GRZ-R16</b>	Any activity that is not listed as prohibited, permitted, restricted discretionary or discretionary.
<b>(1) Activity status: NC</b>	
<b>GRZ-R17</b>	Any building, structure, objects or vegetation that obscure the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (refer to APP8 – Raglan navigation beacon).
<b>(1) Activity status: PR</b>	

*Land use – effects*

<b>GRZ-S1</b>	Servicing and hours of operation – Bankart Street and Wainui Road Business Overlay Area	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The loading and unloading of vehicles and the receiving of customers and deliveries associated with a commercial activity within the Bankart Street and Wainui Road Business Overlay Area shall occur between 7.30am and 6:30pm.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>	

*Land use – building*

<b>GRZ-S2</b>	Residential unit
---------------	------------------

<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) One residential unit within a site.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-S3</b>   Minor residential unit</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) One minor residential unit contained within a site must comply with all of the following standards:                  (i) The net site area is 600m<sup>2</sup> or more; and                  (ii) The gross floor area shall not exceed 70m<sup>2</sup>.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-S4</b>   Height – building general</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) The maximum height of any building or structure, measured from the natural ground level immediately below the structure, shall not exceed 8m;                  (b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 10m measured from the natural ground level immediately below the structure;                  (c) The maximum height of a hose drying tower on a Fire and Emergency fire station site, measured from the natural ground level immediately below the structure, shall not exceed 15m.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b>                  (a) Extent of overshadowing and shading of adjoining sites, particularly internal and external living spaces;                  (b) Loss of privacy through overlooking adjoining sites;                  (c) Whether development on the adjoining sites (such as separation by land used for vehicle access, the provision of screening) reduces the need to protect the adjoining site from overlooking; and                  (d) Design (such as high windows) and location of the building.</p>
<p><b>GRZ-S5</b>   Height – building and vegetation in a battlefield view shaft area</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) The maximum height of a building, structure or vegetation above ground level within a battlefield view shaft as shown on the planning maps, shall not exceed 5m.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-S6</b>   Height – buildings, structures or vegetation – Raglan Navigation Beacon Height Restriction Plane</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) A building, structure or vegetation that is located beneath, but does not intrude into, the Raglan Navigation Beacon Height Restriction Plane, as defined in APP8 – Raglan navigation beacon, provided that:                  (i) A Registered Surveyor has certified, in writing, that the building, structure or</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>

GRZ-S6 is Operative



<p>vegetation does not intrude into the Raglan Navigation Beacon Height Restriction Plane; and</p> <p>(ii) This certification is provided to Council prior to the commencement of any works.</p>	
<p><b>PREC4-SI</b></p>	<p>Height – buildings or structures adjoining Hilltop parks within PREC4 – Havelock precinct</p>
<p><b>(3) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building or structure with a maximum height not exceeding 5m, measured from the natural ground level immediately below that part of the structure, where it is located within 50m (horizontal distance) of the boundary of the Hilltop parks identified on the Havelock precinct plan in APP14 – Havelock precinct plan.</p>	<p><b>(4) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRZ-S7</b></p>	<p>Fences or walls – road boundaries and OSZ – Open space zone boundaries</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Fences and walls between the applicable building setbacks under GRZ-S17 – GRZ- on a site and any road and OSZ – Open space zone boundaries shall comply with all of the following standards, measured from the natural ground level immediately below the structure:</p> <p>(i) Be no higher than 1.2m if solid;</p> <p>(ii) Be no higher than 1.8m if:</p> <p>(iii) visually permeable for the full 1.8m height of the fence or wall; or</p> <p>(iv) solid up to 1.2m and visually permeable between 1.2 and 1.8m.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Building materials and design;</p> <p>(b) Effects on amenity; and</p> <p>(c) Public space visibility.</p>
<p><b>GRZ-S8</b></p>	<p>Fences or walls – road boundaries and OSZ – Open space zone boundaries</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any fences or walls erected within the applicable building setbacks under GRZ-S17 – GRZ-S23 on common boundaries of the GRZ – General residential zone and RLZ – Rural lifestyle zone, between Wayside Road and Travers Road, Te Kauwhata, shall be of a rural-type post and wire or post and rail.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Building materials and design;</p> <p>(b) Effects on amenity; and</p> <p>(c) Public space visibility.</p>
<p><b>GRZ-S9</b></p>	<p>Height in relation to boundary</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Buildings or structures shall not protrude through a height control plane rising at an angle of 45 degrees commencing at an</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p>

<p>elevation of 2.5m above ground level at every point of the site boundary.</p>	<ul style="list-style-type: none"> <li>(a) Height of the building;</li> <li>(b) Design and location of the building;</li> <li>(c) Extent of shading on adjacent any other sites;</li> <li>(d) Privacy on another any other sites; and</li> <li>(e) Effects on amenity values and residential character.</li> </ul>
<p><b>GRZ-S10</b>   Building coverage</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The total building coverage shall not exceed 40%;</li> <li>(b) GRZ-S10(1)(a) does not apply: <ul style="list-style-type: none"> <li>(i) To a structure that is not a building; or</li> <li>(ii) Eaves of a building that project less than 750mm horizontally from the exterior wall of the building.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Whether the balance of open space and buildings will maintain the character and amenity values anticipated for the zone;</li> <li>(b) Visual dominance of the street resulting from building scale; and</li> <li>(c) Management of stormwater flooding, nuisance or damage to within the site.</li> </ul>
<p><b>GRZ-S11</b>   Building coverage</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Within the Te Kauwhata Ecological Residential Area as identified on the planning maps, the total building coverage shall not exceed 35%.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Whether the balance of open space and buildings will maintain the character and amenity values anticipated for the zone;</li> <li>(b) Visual dominance of the street resulting from building scale; and</li> <li>(c) Management of stormwater flooding, nuisance or damage to within the site.</li> </ul>
<p><b>GRZ-S12</b>   Building coverage</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Within the Bankart Street and Wainui Road Business Overlay Area as identified on the planning maps, total building coverage shall not exceed 50%.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Whether the balance of open space and buildings will maintain the character and amenity values anticipated for the zone;</li> <li>(b) Visual dominance of the street resulting from building scale; and</li> <li>(c) Management of stormwater flooding, nuisance or damage to within the site.</li> </ul>
<p><b>GRZ-S13</b>   Impervious surfaces</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The impervious surfaces of a site shall not exceed 70%.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Site design, layout and amenity; and</li> </ul>

		(b) The risk of flooding, nuisance or damage to the site or other buildings and sites.
<b>GRZ-S14</b>	Outdoor living space	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) An outdoor living space shall be provided for each residential unit that meets all of the following standards:</p> <p>(i) It is for the exclusive use of the occupants of the residential unit;</p> <p>(ii) It is readily accessible from a living area of the residential unit;</p> <p>(iii) When located on the ground floor, it has a minimum area of 80m<sup>2</sup> and a minimum dimension of 4m in any direction; and</p> <p>(iv) When located on a balcony of an above ground apartment building, it must have a minimum area of 15m<sup>2</sup> and a minimum dimension of 2m in any direction.</p>		<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the space is useable and contributes to the feeling of spaciousness;</p> <p>(b) Access to sunlight;</p> <p>(c) Privacy of adjoining residential sites;</p> <p>(d) Accessibility to and convenience of the space for occupiers; and</p> <p>(e) Whether the size and quality of communal outdoor living space in the development or other public open space compensates for any reduction in the private space.</p>
<b>GRZ-S15</b>	Outdoor living space	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) An outdoor living space shall be provided for each minor residential unit that meets all of the following standards:</p> <p>(i) It is for the exclusive use of the occupants of the minor residential unit;</p> <p>(ii) It is readily accessible from a living area of the minor residential unit;</p> <p>(iii) When located on the ground floor it has a minimum area of 40m<sup>2</sup> and a minimum dimension of 4m in any direction;</p> <p>(iv) When located on a balcony of an above ground apartment building, it must have a minimum area of 15m<sup>2</sup> and a minimum dimension of 2m in any direction.</p>		<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The extent to which the space is useable and contributes to the feeling of spaciousness;</p> <p>(b) Access to sunlight;</p> <p>(c) Privacy of adjoining residential sites;</p> <p>(d) Accessibility to and convenience of the space for occupiers; and</p> <p>(e) Whether the size and quality of communal outdoor living space in the development or other public open space compensates for any reduction in the private space.</p>
<b>GRZ-S16</b>	Service court	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) A service court shall be provided for each residential unit and minor residential unit, either as two separate areas or one combined area, each with all the following dimensions:</p>		<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The convenience and accessibility of the spaces for building occupiers;</p>

<ul style="list-style-type: none"> <li>(i) Storage of waste and recycling bins – minimum area of 3m<sup>2</sup> and minimum dimension of 1.5m; and</li> <li>(ii) Washing line – minimum area of 5m<sup>2</sup> and minimum dimension of 2m.</li> </ul>	<ul style="list-style-type: none"> <li>(b) The adequacy of the space to meet the expected requirements of building occupiers; and</li> <li>(c) Adverse effects on the location of the space on visual amenity from the street or adjoining sites.</li> </ul>
<p><b>GRZ-S17</b> Building setbacks – all boundaries</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The finished external walls (excluding eaves) of a building shall be set back a minimum of: <ul style="list-style-type: none"> <li>(i) 3m from the road boundary;</li> <li>(ii) 1.3m from the edge of an indicative road (as demonstrated on a structure plan or planning maps);</li> <li>(iii) 1.5m from every boundary other than a road boundary; and</li> <li>(iv) 1.5m from every vehicle access to another site.</li> </ul> </li> <li>(b) GRZ-S17(1)(a) does not apply to a structure which is not a building.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Road network safety and efficiency;</li> <li>(b) Reverse sensitivity effects;</li> <li>(c) Adverse effects on amenity;</li> <li>(d) Streetscape;</li> <li>(e) Potential to mitigate adverse effects;</li> <li>(f) Daylight admission to adjoining properties; and</li> <li>(g) Effects on privacy at adjoining sites.</li> </ul>
<p><b>GRZ-S18</b> Building setbacks – all boundaries</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The finished external walls (excluding eaves) of a non-habitable building can be set back less than 1.5m from a boundary, where: <ul style="list-style-type: none"> <li>(i) The total length of all buildings within 1.5m of the boundary does not exceed 6m; and</li> <li>(ii) The building does not have any windows or doors on the side of the building facing the boundary.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Road network safety and efficiency;</li> <li>(b) Reverse sensitivity effects;</li> <li>(c) Adverse effects on amenity;</li> <li>(d) Streetscape;</li> <li>(e) Potential to mitigate adverse effects;</li> <li>(f) Daylight admission to adjoining properties; and</li> <li>(g) Effects on privacy at adjoining sites.</li> </ul>
<p><b>GRZ-S19</b> Building setbacks – all boundaries</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A garage shall be set back behind the front façade of the residential unit where the residential unit and garage are on a site that has frontage to a road.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Road network safety and efficiency;</li> <li>(b) Reverse sensitivity effects;</li> <li>(c) Adverse effects on amenity;</li> <li>(d) Streetscape;</li> <li>(e) Potential to mitigate adverse effects;</li> <li>(f) Daylight admission to adjoining properties; and</li> <li>(g) Effects on privacy at adjoining sites.</li> </ul>
<p><b>GRZ-S20</b> Building setback – sensitive land use</p>	

<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) Any new building or alteration to an existing building for a sensitive land use shall be set back a minimum of:                  (i) 5m from the designated boundary of the railway corridor;                  (ii) 15m from the boundary of a national route or regional arterial;                  (iii) 25m from the designated boundary of the Waikato Expressway;                  (iv) 300m from the edge of oxidation ponds that are part of a municipal wastewater treatment facility on another site;                  (v) 30m from a municipal wastewater treatment facility where the treatment process is fully enclosed; and                  (vi) 300m from the boundary of the Alstra Poultry intensive farming activities located on River Road and Great South Road, Ngaaruawaahia.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b>                  (a) Road network safety and efficiency;                  (b) On-site amenity values;                  (c) Odour, dust and noise levels received at the notional boundary of the building;                  (d) Mitigation measures; and                  (e) Potential for reverse sensitivity effects.</p>
<p><b>GRZ-S2I</b></p>	<p>Building setback – sensitive land use located outside the Amenity Setback specific control in Tuakau</p>
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) Any new building or alteration to an existing building for a sensitive land use shall be located outside the Amenity Setback specific control identified on the planning maps.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b>                  (a) On-site amenity values;                  (b) Odour, dust and noise levels received at the notional boundary of the building;                  (c) Timing and duration of noise received at the notional boundary of the building; and                  (d) Potential for reverse sensitivity effects</p>
<p><b>PREC4-S2</b></p>	<p>Building setback – sensitive land use within PREC4 – Havelock precinct</p>
<p><b>(3) Activity status: PER</b>  <b>Where:</b>                  (a) Any new building or alteration to an existing building for a sensitive land use within the PREC4 – Havelock precinct that is located outside the Pōkeno Industry Buffer identified on the planning maps.</p>	<p><b>(4) Activity status where compliance not achieved: NC</b></p>
<p><b>GRZ-S22</b></p>	<p>Building setback – water bodies</p>
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) Any building must shall be setback a minimum of:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p>

<ul style="list-style-type: none"> <li>(i) 23m from the margin of any;             <ul style="list-style-type: none"> <li>(1) lake; and</li> <li>(2) wetland;</li> </ul> </li> <li>(ii) 23m from the bank of any river (other than the Waikato and Waipa Rivers);</li> <li>(iii) 28m from the margin of both the Waikato River and the Waipa River; and</li> <li>(iv) 23m from mean high water springs.</li> <li>(v) 10m from any artificial wetland.</li> <li>(b) A public amenity of up to 25m<sup>2</sup> or a pump shed (public or private), within any building setback identified in GRZ-S22(1)(a).</li> </ul>	<ul style="list-style-type: none"> <li>(a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body;</li> <li>(b) Adequacy of erosion and sediment control measures;</li> <li>(c) The functional or operational need for the building to be located close to the waterbody;</li> <li>(d) Effects on public access to the waterbody;</li> <li>(e) Effects on the amenity of the locality; and</li> <li>(f) Effects on natural character values.</li> </ul>
<b>GRZ-S23</b>	Building setback – Environmental Protection Area
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A building shall be set back a minimum of 3m from an Environmental Protection Area.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRZ-S24</b>	Building – Horotiu Acoustic Area (identified on the planning maps)
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Construction, addition to or alteration of a building for a noise sensitive activity within the Horotiu Acoustic Area shall be designed and constructed to achieve the internal design sound level specified in APPI – Acoustic insulation, Table 22 – Internal design sound levels</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) On-site amenity values;</li> <li>(b) Noise levels received at the notional boundary of the building;</li> <li>(c) Timing and duration of noise received at the notional boundary of the building; and</li> <li>(d) Potential for reverse sensitivity effects.</li> </ul>
<b>PREC4-S3</b>	Building design – sensitive land use with PREC4 – Havelock precinct
<p><b>(3) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any new building or alteration to an existing building for a sensitive land use located outside the Pōkeno Industry Buffer but within the 40 dB L<sub>Aeq</sub> noise contour shown on the planning maps that is designed and constructed so that internal noise levels do not exceed 25 dB L<sub>Aeq</sub> in all habitable rooms.</li> <li>(b) Provided that if compliance with clause (a) above requires all external doors of the building and all windows of these rooms to be closed, the building design and construction as a minimum:</li> </ul>	<p><b>(4) Activity status where compliance not achieved: DIS</b></p>

<ul style="list-style-type: none"><li>(i) Is mechanically ventilated and/or cooled to achieve an internal temperature no greater than 25°C based on external design conditions of dry bulb 25.1 °C and wet bulb 20.1 °C.</li><li>(ii) Includes either of the following for all habitable rooms on each level of a dwelling:<ul style="list-style-type: none"><li>(1) Mechanical cooling installed; or</li><li>(2) A volume of outdoor air supply to all habitable rooms with an outdoor air supply rate of no less than:<ul style="list-style-type: none"><li>(a) 6 air changes per hour for rooms with less than 30% of the façade area glazed;</li><li>(b) 15 air changes per hour for rooms with greater than 30% of the façade area glazed;</li><li>(c) 3 air changes per hour for rooms with facades only facing south (between 120 degrees and 240 degrees) or where the glazing in the façade is not subject to any direct sunlight.</li></ul></li></ul></li><li>(iii) Provides relief for equivalent volumes of spill air.</li><li>(iv) All is certified by a suitably qualified and experienced person.</li></ul>	
--	--

## MRZ1 - Medium density residential zone 1

The relevant district-wide chapter provisions apply in addition to this chapter.

*Explanatory note for the purpose of the IPI and to be removed upon completion of the process:*

Only consequential referencing of MRZ – Medium density residential zone to MRZ1 – Medium density residential zone 1 are proposed within this Chapter.

Formatting of the document does not enable the numbered referencing of the Objectives, Policies and Rules to be shown in green underline. Instead all updated numbering is shown in normal black text.

### Purpose

The purpose of the MRZ1 – Medium density residential zone 1 is to enable more efficient use of residentially zoned land and infrastructure by providing for a higher intensity of residential development than typically found in the GRZ – General residential zone. The MRZ1 – Medium density residential zone 1 provides for this form of development within a walkable catchment of town centres, strategic transport corridors and community facilities. The zone will:

- Provide greater housing supply to respond to anticipated growth;
- Reduce pressure for residential development on the urban fringe and beyond;
- Relieve anticipated pressures on the road transport network (which are exacerbated by adopting sprawl to accommodate urban growth). This will be achieved by providing housing close to town and business centres where the use of both public and active modes of transport to access places of employment, retail and entertainment is readily achievable and/or viable;
- Provide greater diversity / choice of housing; and
- Coordinate delivery of infrastructure and services.

The zone provisions enable a variety of dwelling sizes and typologies to be delivered which provides opportunity for greater housing variety and choice. Development within the zone is guided by rules which encourage innovation and flexibility in design responses. The rules provide design guidance for up to 3 dwellings on site, allowing compliant smaller scale developments to be enabled in a manner that maximises opportunities on smaller existing sites. Developments of more than 3 dwellings are subject to a more intensive design assessment process with matters of discretion which provide the primary guidance for assessment, including the intensity of development and enabling appropriate design outcomes regarding:

- The contribution the development makes to the zone having regard to the planned urban form and intensity the zone provides for;
- The creation of safe and high-quality residential neighbourhoods;
- The on-site amenity for residents such as high-quality outdoor spaces;
- The amenity effects on adjoining sites such as privacy and shading; and
- The provision of three waters infrastructure to service the development.

### Objectives

MRZ1-O1 Housing typology.

Achieve greater housing choice for the community in response to changing demographics and housing needs.



**MRZI-O2** Efficient use of land and infrastructure.

Land and infrastructure near the TCZ – Town Centre Zone, LCZ – Local centre zone and COMZ – Commercial zone and close to public transport networks, strategic transport corridors and community facilities is efficiently used for medium density residential living, resulting in a compact urban settlement pattern.

**MRZI-O3** Residential amenity.

Achieve a level of residential amenity commensurate with a medium density environment comprised of primarily townhouse and low-rise apartments.

**MRZI-O4** Activities.

An appropriate mix of complementary and compatible activities is enabled to support residential growth.

## **Policies**

**MRZI-P1** Housing typology and type.

Enable a variety of housing typologies including apartments, terrace housing and duplexes.

**MRZI-P2** Efficient use of land and infrastructure.

- (1) Enable land to be used for higher intensity residential living where such land is:
  - (a) Adjacent to the TCZ – Town centre zone, LCZ – Local centre zone, COMZ – Commercial zone and within a walkable catchment of transport networks; or
  - (b) Integrated into master-planned growth areas in close proximity to neighbourhood centres or publicly accessible open space.
- (2) Recognise the social, economic and environmental benefits arising from higher density development being situated closer to community facilities and the TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone when considering development proposals.
- (3) Recognise the economic and environmental benefits of higher density development that efficiently utilises existing, and planned, investment in both transport and three waters infrastructure.

**MRZI-P3** Building form, massing and coverage.

- (1) Enable residential development that:
  - (a) Is of a height and bulk that manages daylight access and a reasonable standard of privacy for residents; and
  - (b) Manages visual dominance effects on adjoining sites.

**MRZI-P4** Streetscape, yards and outdoor living spaces.

- (1) Enable residential development that contributes to attractive and safe streets and public open spaces by:
  - (a) Providing for passive surveillance to public open spaces and streets through the siting of dwellings and rooms, façade design and fencing / landscaping;

- (b) Incorporating front yard landscaping that will enhance streetscape amenity; and
  - (c) Minimising the prevalence of garage doors, carparking and driveways fronting the street.
- (2) Require development to have sufficient side yard setbacks to provide for:
- (a) Landscaping and permeable surfaces;
  - (b) Privacy to adjoining sites;
  - (c) Sunlight and daylight; and
  - (d) Driveways and accessways.
- (3) Require the provision of outdoor living spaces that:
- (a) Are attractive, functional and accessible; and
  - (b) Provide a reasonable standard of privacy for residents and to adjoining sites.
- (4) Enable flexibility and innovation in the provision of outdoor living spaces by recognising the varying means by which suitable spaces can be provided for a particular form of development; including shared outdoor spaces, roof terraces or other communal outdoor living spaces.

MRZI-P5 Changes to amenity values.

Recognise that the planned urban built form may result in changes to the amenity values and characteristics of the urban character over time.

MRZI-P6 Home businesses.

- (1) Provide for home businesses to allow flexibility for people to work from their homes.
- (2) Manage adverse effects on residential amenity through limiting home occupations to a scale that is compatible with the primary residential purpose of the zone.

MRZI-P7 Non-residential activities.

- (1) Maintain the zone primarily for residential activities while also:
  - (a) Ensuring community facilities:
    - (i) Are suitably located;
    - (ii) Are of a limited scale and intensity that is compatible with the zone;
    - (iii) Contribute to the amenity of the neighbourhood; and
    - (iv) Support the social and economic well-being of the residential community.
  - (b) Avoiding the establishment of new non-residential activities (except home occupations) on rear sites, or sites located on cul-de-sacs; and
  - (c) Ensuring that the design and scale of non-residential activities and associated buildings mitigates adverse effects related to traffic generation, access, noise, vibration, outdoor storage of materials and light spill.

- (2) Enabling existing non-residential activities to continue and support their redevelopment and expansion, provided they do not have a significant adverse effect on character and amenity.

## Rules

### Land use – activities

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>MRZ1-RI</b>	Residential activity, unless specified below  This includes occupation of a single residential unit for short term rental.
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>MRZ1-R2</b>	A new retirement village or alterations to an existing retirement village
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The site is connected to public water and wastewater infrastructure; (b) The minimum living space or balcony area and dimensions are: (i) Apartment – 10m <sup>2</sup> area with a minimum dimension horizontal and vertical of 2.5m; (ii) Studio unit or 1 bedroom unit – 12.5m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m; or (iii) 2 or more bedroomed unit – 15m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m. (c) The minimum service court is either: (i) Apartment – Communal outdoor space (i.e. no individual service courts required); or (ii) All other units – 10m <sup>2</sup> for each unit. (d) The following land use – effects standard does not apply: (i) SIGN-R1, SIGN-R8 – SIGN-R10 (Signs). (e) The following Land Use – Building standards do not apply: (i) MRZ <u>1</u> -S1 (Residential unit); (ii) MRZ <u>1</u> -S8 (Outdoor living space); and (f) The following infrastructure and energy rule does not apply:	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b> (a) Consideration of the effects of the activity-specific standard not met; (b) Measures to avoid, remedy or mitigate adverse effects; and (c) Cumulative effects.

(i) Rule TRPT-R4(1)(a) (Traffic generation).		
<b>MRZI-R3</b>	Home business	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> <ul style="list-style-type: none"> <li>(a) The home business is wholly contained within a building;</li> <li>(b) The storage of materials or machinery associated with the home business are wholly contained within a building or are screened so as not to be visible from a public road or neighbouring residential property;</li> <li>(c) No more than 2 people who are not permanent residents of the site are employed at any one time;</li> <li>(d) Unloading and loading of vehicles, the receiving of customers or deliveries only occur between 7:30am and 7:00pm on any day; and</li> <li>(e) Machinery may only be operated between 7:30am and 9pm on any day.</li> </ul>		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) Consideration of the effects of the activity-specific standard not met;</li> <li>(b) Measures to avoid, remedy or mitigate adverse effects; and</li> <li>(c) Cumulative effects.</li> </ul>
<b>MRZI-R4</b>	Community facilities	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> <ul style="list-style-type: none"> <li>(a) No more than 200m<sup>2</sup> GFA.</li> </ul>		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) Consideration of the effects of the activity-specific standard not met;</li> <li>(b) Measures to avoid, remedy or mitigate adverse effects; and</li> <li>(c) Cumulative effects.</li> </ul>
<b>MRZI-R5</b>	Neighbourhood park	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>MRZI-R6</b>	Home stay	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> <ul style="list-style-type: none"> <li>(a) No more than 4 temporary residents.</li> </ul>		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> <ul style="list-style-type: none"> <li>(a) Consideration of the effects of the activity-specific standard not met;</li> <li>(b) Measures to avoid, remedy or mitigate adverse effects; and</li> <li>(c) Cumulative effects.</li> </ul>
<b>MRZI-R7</b>	Boarding houses/boarding establishments	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b>		<b>(2) Activity status where compliance not achieved: RDIS</b>

(a) No more than 10 people per site inclusive of staff and residents.	<b>Council's discretion is restricted to the following matters:</b> (a) Consideration of the effects of the activity-specific standard not met; (b) Measures to avoid, remedy or mitigate adverse effects; and (c) Cumulative effects.
<b>MRZI-R8</b>	Construction or alteration of a building for a sensitive land use
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards: (i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or (ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Effects on the amenity values of the site; (b) The risk of electrical hazards affecting the safety of people; (c) The risk of damage to property; and (d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.
<b>MRZI-R9</b>	Construction, demolition, addition, and alteration of a building or structure
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>MRZI-R10</b>	Any activity that is not listed as permitted, restricted discretionary or prohibited,
<b>Activity status: DIS</b>	
<b>MRZI-R11</b>	Any building, structure, objects or vegetation that obscures the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (APP8 – Raglan navigation beacon).
<b>Activity status: PR</b>	

*Land use – building*

<b>MRZI-S1</b>	Residential unit
<b>(1) Activity status: PER</b> <b>Where:</b> (a) Up to three residential units per site.	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Intensity of the development; and (b) Design, scale and layout of buildings and outdoor living spaces in relation to the planned urban character of the zone;

	<ul style="list-style-type: none"> <li>(c) The relationship of the development with adjoining streets or public open spaces, including the provision of landscaping; and</li> <li>(d) Privacy and overlooking within the development and on adjoining sites, including the orientation of habitable rooms and outdoor living spaces; and</li> <li>(e) Provision of 3-waters infrastructure to individual units; and</li> <li>(f) The provision of adequate waste and recycling bin storage including the management of amenity effects of these on streets or public open spaces; and</li> <li>(g) Where on-site car parking is provided, the design and location of car parking (including garaging) as viewed from streets or public open spaces.</li> </ul>
<b>MRZI-S2</b>	Minimum residential unit size
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Residential units must have a minimum net internal floor area of: <ul style="list-style-type: none"> <li>(i) 35m<sup>2</sup> for studio dwellings; and</li> <li>(ii) 45m<sup>2</sup> for one or more bedroom dwellings.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The functionality of the residential unit; and</li> <li>(b) Internal residential amenity.</li> </ul>
<b>MRZI-S3</b>	Height – building general
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The permitted height of any building or structure is 11m measured from the natural ground level immediately below that part of the structure;</li> <li>(b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 13m measured from the natural ground level immediately below the structure;</li> <li>(c) In Raglan, the permitted height of any building or structure is 7.5m measured from the natural ground level immediately below that part of the structure.</li> <li>(d) In Raglan, chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 9.5m measured from the natural ground level immediately below the structure;</li> <li>(e)</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Height of the building or structure;</li> <li>(b) Design, scale and location of the building;</li> <li>(c) Extent of shading on adjacent sites; and</li> <li>(d) Privacy and overlooking on adjoining sites.</li> </ul>
<b>MRZI-S4</b>	Fences or walls – road boundaries

<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Fences and walls between the applicable building setbacks under MRZ<u>1</u>-S10 and MRZ<u>1</u>-I1 on a site and any road boundaries, must comply with all of the following standards:</p> <p>(i) Be no higher than 1.5m if solid;</p> <p>(ii) Be no higher than 1.8m if:</p> <p>(1) Visually permeable for the full 1.8m height of the fence or wall;  or</p> <p>(2) Solid up to 1.5m and visually permeable between 1.5 and 1.8m.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Building materials and design;</p> <p>(b) Effects on streetscape amenity; and</p> <p>(c) Public space visibility.</p>
<p><b>MRZ1-S5</b>   Height in relation to boundary</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Buildings and structures must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 3m above natural ground level at every point of the site boundary, except</p> <p>(i) Where the boundary forms part of a legal right of way, entrance strip or access site; the standard applies from the farthest boundary of that legal right of way, entrance strip or access site;</p> <p>(ii) This standard does not apply to existing or proposed internal boundaries within a site;</p> <p>(iii) Where a site in the MRZ<u>1</u> – Medium density residential zone <u>1</u> adjoins a site in the GRZ – General residential zone, LLRZ – Large lot residential or SETZ – Settlement zone, then buildings must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 2.5m above natural ground level at every point of the site boundary abutting that GRZ – General residential zone, LLRZ – Large lot residential zone or SETZ – Settlement zone;</p> <p>(iv) Where the boundary adjoins a legal road.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Height of the building;</p> <p>(b) Design and location of the building;</p> <p>(c) Extent of shading on adjacent sites; and</p> <p>(d) Privacy on adjoining sites.</p>
<p><b>MRZ1-S6</b>   Building coverage</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

<p>(a) The total building coverage must not exceed 45%.</p> <p>(b) MRZ<u>1</u>-S6(1)(a) does not apply:</p> <p>(i) To a structure that is not a building; or</p> <p>(ii) Eaves of a building that project less than 750mm horizontally from the exterior wall of the building.</p>	<p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Design, scale and location of the building;</p> <p>(b) Provision for outdoor living space and service courts; and</p> <p>(c) Effects on the planned urban built character of the surrounding residential area.</p>
<p><b>MRZI-S7</b>   Impervious surfaces</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The impervious surfaces of a site must not exceed 70%.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Site design, layout and amenity; and</p> <p>(b) The risk of flooding, nuisance or damage to the site or other buildings and sites.</p>
<p><b>MRZI-S8</b>   Outdoor living space</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) An outdoor living space must be provided for each residential unit that meets all of the following standards:</p> <p>(i) It is for the exclusive use of the occupants of the residential unit;</p> <p>(ii) It is readily accessible from a living area of the residential unit;</p> <p>(iii) Where the residential unit contains an internal habitable space (excluding garages, bathrooms, laundries, and hall or stairways) on the ground floor, an outdoor living court shall be provided and shall have a minimum area of 20m<sup>2</sup> and a minimum dimension of 4m in any direction; and</p> <p>(iv) Where the residential unit has its principal living area at first floor level or above, a balcony shall be provided and shall have a minimum area of 5m<sup>2</sup> for studio and one-bedroom dwellings, or 8m<sup>2</sup> for two or more bedroom dwellings and a minimum dimension of 1.5m.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Design and location of the building;</p> <p>(b) Provision for outdoor living space including access to sunlight and open space and the usability and accessibility of the outdoor living space proposed;</p> <p>(c) Privacy and overlooking on adjoining sites; and</p> <p>(d) The proximity of the site to communal or public open space that has the potential to mitigate any lack of private outdoor living space.</p>
<p><b>MRZI-S9</b>   Ground floor internal habitable space</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Garages shall occupy less than 50% of the ground floor space internal to buildings on the site.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The visual dominance of garaging, parking, and vehicle manoeuvring areas and the balance across the site of internal</p>



		habitable space, outdoor living courts, and landscaping at ground level; and (b) The design and location of garaging as viewed from streets or public open spaces.
<b>MRZ1-S10</b>	Building setbacks – all boundaries	
<b>(1) Activity status: PER</b> <b>Where:</b> (a) The finished external walls (excluding eaves) of a building must be set back a minimum of: (i) 3m from the road boundary; (ii) 3m from the edge of an indicative road (as demonstrated on a structure plan or planning maps); (iii) 1m from every boundary other than a road boundary; and (b) Balconies greater than 1.5m above ground level shall be set back a minimum of 4m from every boundary other than a boundary to a road or public open space; (c) MRZ <u>1</u> -S10(1)(a) and (b) do not apply to structures that are not buildings.	<b>Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b> (d) Road network safety and efficiency; (e) Potential to mitigate adverse effects on the streetscape through use of other design features; (f) Daylight admission to adjoining properties; and (g) Privacy overlooking on adjoining sites.	
<b>MRZ1-S11</b>	Building setbacks – water bodies	
<b>(1) Activity status: PER</b> <b>Where:</b> (a) A building must be set back a minimum of: (i) 20m from the margin of any lake; (ii) 20m from the margin of any wetland; (iii) 23m from the bank of any river (other than the Waikato River and Waipa River); (iv) 38m from the margin of either the Waikato River and the Waipa River (v) 23m from mean high water springs (b) A public amenity of up to 25m <sup>2</sup> or pump shed within any building setback identified in MRZ <u>1</u> -S12(1)(a); (c) MRZ <u>1</u> -S11(1)(a) does not apply to a structure which is not a building.	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b> (a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body; (b) Adequacy of erosion and sediment control measures; (c) The functional or operational need for the building to be located close to the waterbody; (d) Effects on public access to the waterbody; (e) Effects on the amenity of the locality; and (f) Effects on natural character values.	

## MRZ2 – Medium density residential zone 2

*Explanatory note for the purpose of the IPI and to be removed upon completion of the process:*

The provisions in this chapter are based on the provisions of the MRZ – Medium density residential zone of the proposed Waikato District Plan.

Standard text is used for existing provisions contained in the proposed Waikato District Plan.

Green underline text is used for new provisions.

~~Black Strikethrough~~ is used to show the deletion of existing provisions.

The provisions in this chapter incorporate the density standards in Part 2 of Schedule 3A of the Resource Management Act 1991 (the Act) and the objectives and policies in Clause 3 of Schedule 3A of the Act. In accordance with Section 80H of the Act these provisions are shown **shaded grey**.

Provisions that have legal effect are marked in this chapter with a gavel (as shown in the margin of this paragraph).

Rules providing for residential units in the Medium density residential zone 2 as a permitted activity in accordance with the density standards in Schedule 3A of the Act have immediate legal effect under Section 86BA of the Act unless the site is within a qualifying matter area or a new residential zone. A new residential zone means an area that was not shown as a residential zone in the Operative Waikato District Plan. Applicable qualifying matters include the rules set out in the table below:

Qualifying matter	Topic	District wide rules	Zone rules
Matter of national importance under s6 (s771(a))	Natural character of the lakes and rivers and their margins s6(a)  Maintenance and enhancement of public access to and along lakes and rivers s6(d)		GRZ-S22 Building setbacks – water bodies MRZ2–S13 Building setbacks – water bodies GRZ-R15 Building within the Huntly North Wetland specific control
	Outstanding natural features and landscapes s6(b)	NFL-R2 Earthworks within an ONF or ONL NFL-R3 Subdivision	GRZ-S22 Building setbacks – water bodies MRZ2–S13 Building Setbacks – water bodies
	Significant indigenous vegetation and significant habitats of indigenous fauna s6(c)	ECO–R3 Earthworks in an SNA ECO–R8 Vegetation clearance within an SNA ECO-R11 Vegetation clearance outside an SNA	
	Relationship of Maaori and their culture and	SASM–R4 Earthworks	

	traditions with their ancestral lands, water, sites, waahi tapu and other taonga s6(e)	SASM–R5 Title boundaries	
	Protection of historic heritage from inappropriate subdivision, use and development s6(f)	<p>HH-R2 All site development</p> <p>HH-R4 Additions and alterations to a historic heritage item</p> <p>HH-R5 Construction or alteration to a building in the Huntly heritage area</p> <p>HH-R7 Demolition, removal or relocation of any B ranked historic heritage item</p> <p>HH-R8 Demolition, removal or relocation of any A ranked historic heritage item</p> <p>HH-R9 Subdivision of land containing a historic heritage item</p>	
	Management of significant risks from natural hazards s6(h)	<p>Flood plain management area NH-R10</p> <p>High risk flood area NH-R20, NH-R19</p> <p>Defended area NH-R25, NH-R24</p> <p>Mine subsidence risk area NH-R72, NH-R73, NH-R74</p>	
Matter required to give effect to a national policy statement (s771(b))	National Policy Statement for Electricity Transmission	EW-R2 Earthworks activities within the National Grid Yard	<p>GRZ-R14 New sensitive land use within National Grid Yard</p> <p>MRZ2-R10 Buildings, structures and sensitive land uses within the National Grid Yard</p> <p>MRZ2-R10 New sensitive land use within the National Grid Yard</p> <p>SUB-R26 Subdivision within the National Grid Corridor</p>

			SUB-R162 Subdivision within National Grid Corridor
Matter required to give effect to Te Ture Whaimana (s771(c))			GRZ-S22 Building setbacks – water bodies MRZ2 – S13 Building setbacks – water bodies
Matter required for the purpose of ensuring the safe or efficient operation of nationally significant infrastructure (s771(e))	State Highways		GRZ-S20 Building setback – sensitive land use MRZ2-R14 Building setback – sensitive land use
	North Island Main Trunk rail		
	Gas transmission line		
Any other matter that makes higher density inappropriate in an area (s771(j))	Urban fringe		MDRS not proposed to apply to the GRZ
	Reverse sensitivity		GRZ-S20 Building setback – sensitive land use GRZ-S21 Building setback – sensitive land use located outside Amenity Setback PREC4-S2 Building setback – sensitive land use within Havelock Precinct MRZ2-S14 Building setback – sensitive land use
	Notable trees	TREE-R1 Removal or destruction TREE-R3 Activities within the dripline TREE-R4 Subdivision of land containing a notable tree	

The relevant district-wide chapter provisions apply in addition to this chapter.

## **Purpose**

The purpose of the MRZ2 – Medium density residential zone 2 is to enable the most efficient use of residentially zoned land and infrastructure within the suite of Waikato District Plan residential zones. The MRZ2 – Medium density residential zone 2 provides for this form of development within a walkable catchment of the town centres of Huntly, Ngaaruawaahia, Pookeno and Tuakau. The zone will:

- Provide housing at increased densities with three residential units per lot and buildings up to three storeys in height being permitted;
- Provide for the development of more than three residential units per lot, albeit subject to a more intensive design assessment process with matters of discretion to provide for appropriate design outcomes;
- Encourage a variety of housing types and sizes that respond to housing needs and demands of the district and its planned urban built character;
- Accommodate the highest level of residential growth within the district;
- Reduce pressure for residential development on the urban fringe and beyond;
- Relieve anticipated pressures on the road transport network (which are exacerbated by adopting sprawl to accommodate urban growth) by enabling greater development capacity in town centres where the use of both public and active modes of transport to access places of employment, retail and entertainment is readily achievable and/or viable;
- Provide the highest capacity, diversity and choice of housing; and
- Coordinate delivery of infrastructure and services.

## **Objectives**

### MRZ2-O1 Housing typology.

Provide for a variety of housing types and sizes that respond to:

- (a) Housing needs and demand; and
- (b) The neighbourhood's planned urban built character, including three-storey buildings.

### MRZ2-O2 Efficient use of land and infrastructure.

Land and infrastructure near the TCZ – Town Centre Zone, LCZ – Local centre zone and COMZ – Commercial zone and close to public transport networks, strategic transport corridors and community facilities is efficiently used for medium density residential living, resulting in a compact urban settlement pattern.

### MRZ2-O3 Residential amenity.

Achieve a level of residential amenity commensurate with a medium density environment comprised of primarily three-storey buildings, including semi-detached and terraced housing, townhouses and low-rise apartments.

### MRZ2-O4 Activities.

An appropriate mix of complementary and compatible activities is enabled to support residential growth.

**MRZ2-O5** Qualifying matters.

The capacity to accommodate medium density residential development may be limited to recognise and/or protect one or more qualifying matters.

**MRZ2-O6** Reverse sensitivity.

- (1) Avoid or minimise the potential for reverse sensitivity by managing the location and design of sensitive activities through:
- (a) The use of building setbacks; and
  - (b) The design of subdivisions and development.

## **Policies**

**MRZ2-P1** Housing Typology.

Enable a variety of housing typologies with a mix of densities within the zone, including three-storey attached and detached dwellings, and low-rise apartments.

**MRZ2-P2** Residential Amenity.

Encourage development to achieve attractive and safe streets and public open spaces, including by providing for passive surveillance.

**MRZ2-P3** Housing Design.

Enable housing to be designed to meet the day-to-day needs of residents.

**MRZ2-P4** Enabling Housing Development.

Provide for developments not meeting permitted activity status, while encouraging high-quality developments.

**MRZ2-P5** Streetscape, yards and outdoor living spaces.

- (1) Enable residential development that contributes to attractive and safe streets and public open spaces by:
- (a) Providing for passive surveillance to public open spaces and streets through the siting of dwellings and rooms, façade design and fencing / landscaping;
  - (b) Incorporating front yard landscaping that will enhance streetscape amenity; and
  - (c) Minimising the prevalence of garage doors, carparking and driveways fronting the street.
- (2) Require development to have sufficient side yard setbacks to provide for:
- (a) Landscaping and permeable surfaces;
  - (b) Privacy to adjoining sites;
  - (c) Sunlight and daylight; and
  - (d) Driveways and accessways.
- (3) Require the provision of outdoor living spaces that:
- (a) Are attractive, functional and accessible; and

- (b) Provide a reasonable standard of privacy for residents and to adjoining sites.
- (4) Enable flexibility and innovation in the provision of outdoor living spaces by recognising the varying means by which suitable spaces can be provided for a particular form of development; including shared outdoor spaces, roof terraces or other communal outdoor living spaces.

MRZ2-P6 Qualifying Matters

Restrict residential development to an appropriate level to provide for and protect any relevant qualifying matters.

MRZ2-P7 Efficient use of land and infrastructure.

- (1) Enable land to be used for higher intensity residential living where such land is:
  - (a) Adjacent to the TCZ – Town centre zone, LCZ – Local centre zone, COMZ – Commercial zone and within a walkable catchment of transport networks; or
  - (b) Integrated into master-planned growth areas in close proximity to neighbourhood centres or publicly accessible open space.
- (2) Recognise the social, economic and environmental benefits arising from higher density development being situated closer to community facilities and the TCZ – Town centre zone, LCZ – Local centre zone and COMZ – Commercial zone when considering development proposals.
- (3) Recognise the economic and environmental benefits of higher density development that efficiently utilises existing, and planned, investment in both transport and three waters infrastructure.

MRZ2-P8 Changes to amenity values.

Recognise that the planned urban built form may result in changes to the amenity values and characteristics of the urban character over time.

MRZ2-P9 Home businesses.

- (1) Provide for home businesses to allow flexibility for people to work from their homes.
- (2) Manage adverse effects on residential amenity through limiting home occupations to a scale that is compatible with the primary residential purpose of the zone.

MRZ2-P10 Non-residential activities.

- (1) Maintain the zone primarily for residential activities while also:
  - (a) Ensuring community facilities:
    - (i) Are suitably located;
    - (ii) Are of a limited scale and intensity that is compatible with the zone;
    - (iii) Contribute to the amenity of the neighbourhood; and
    - (iv) Support the social and economic well-being of the residential community.
  - (b) Avoiding the establishment of new non-residential activities (except home occupations) on rear sites, or sites located on cul-de-sacs; and

- (c) Ensuring that the design and scale of non-residential activities and associated buildings mitigates adverse effects related to traffic generation, access, noise, vibration, outdoor storage of materials and light spill.
- (2) Enabling existing non-residential activities to continue and support their redevelopment and expansion, provided they do not have a significant adverse effect on character and amenity.

**MRZ2-PI I** Reverse Sensitivity.

Maintain appropriate setback distances between new sensitive land uses and existing lawfully established activities that may result in reverse sensitivity effects.

## Rules

### Land use – activities

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>MRZ2-R1</b>	Residential activity, unless specified below  This includes occupation of a single residential unit for short term rental.	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>	
<b>MRZ2-R2</b>	A new retirement village or alterations to an existing retirement village	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The site is connected to public water and wastewater infrastructure; (b) The minimum living space or balcony area and dimensions are: (i) Apartment – 10m <sup>2</sup> area with a minimum dimension horizontal and vertical of 2.5m; (ii) Studio unit or 1 bedroom unit – 12.5m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m; or (iii) 2 or more bedroomed unit – 15m <sup>2</sup> area with minimum dimension horizontal and vertical of 2.5m. (c) The minimum service court is either: (i) Apartment – Communal outdoor space (i.e. no individual service courts required); or (ii) All other units – 10m <sup>2</sup> for each unit. (d) The following land use – effects standard does not apply: (i) SIGN-R1, SIGN-R8 – SIGN-R10 (Signs).	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Consideration of the effects of the activity-specific standard not met; (b) Measures to avoid, remedy or mitigate adverse effects; and (c) Cumulative effects.	





<p>(e) The following Land Use – Building standards do not apply:</p> <p>(i) MRZ2-S1 (Residential unit (per unit));</p> <p>(ii) MRZ2-S6 (Outdoor living space); and</p> <p>(f) The following infrastructure and energy rule does not apply:</p> <p>(i) Rule TRPT-R4(1)(a) (Traffic generation).</p>	
<b>MRZ2-R3</b>	Home business
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) The home business is wholly contained within a building;</p> <p>(b) The storage of materials or machinery associated with the home business are wholly contained within a building or are screened so as not to be visible from a public road or neighbouring residential property;</p> <p>(c) No more than 2 people who are not permanent residents of the site are employed at any one time;</p> <p>(d) Unloading and loading of vehicles, the receiving of customers or deliveries only occur between 7:30am and 7:00pm on any day; and</p> <p>(e) Machinery may only be operated between 7:30am and 9pm on any day.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Consideration of the effects of the activity-specific standard not met;</p> <p>(b) Measures to avoid, remedy or mitigate adverse effects; and</p> <p>(c) Cumulative effects.</p>
<b>MRZ2-R4</b>	Community facilities
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) No more than 200m<sup>2</sup> GFA.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Consideration of the effects of the activity-specific standard not met;</p> <p>(b) Measures to avoid, remedy or mitigate adverse effects; and</p> <p>(c) Cumulative effects.</p>
<b>MRZ2-R5</b>	Neighbourhood park
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>MRZ2-R6</b>	Home stay
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) No more than 4 temporary residents.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Consideration of the effects of the activity-specific standard not met;</p>


		(b) Measures to avoid, remedy or mitigate adverse effects; and (c) Cumulative effects.
<b>MRZ2-R7</b>	Boarding houses/boarding establishments	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) No more than 10 people per site inclusive of staff and residents.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Consideration of the effects of the activity-specific standard not met; (b) Measures to avoid, remedy or mitigate adverse effects; and (c) Cumulative effects.
<b>MRZ2-R8</b>	Construction or alteration of a building for a sensitive land use	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards: (i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or (ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Effects on the amenity values of the site; (b) The risk of electrical hazards affecting the safety of people; (c) The risk of damage to property; and (d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.
<b>MRZ2-R9</b>	Construction, demolition, addition, and alteration of a building or structure	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> <b>Nil.</b>		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>MRZ2-R10</b>	<u>Buildings, structures and sensitive land uses within the National Grid Yard in sites existing as of 18 July 2018</u>	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) <u>Within the National Grid Yard:</u> (i) <u>Building alterations and additions to an existing building or structure for a sensitive land use that does not involve an increase in the building height or footprint</u> (ii) <u>New, or additions to existing buildings or structures that are not for a sensitive land use;</u> (iii) <u>Infrastructure (other than for the reticulation and storage of water for irrigation purposes) undertaken by a</u>		<b>(2) Activity status where compliance not achieved: NC</b>

<p><u>network utility operator as defined in the Resource Management Act 1991</u></p> <p>(iv) <u>Fences less than 2.5m in height, measured from the natural ground level immediately below.</u></p> <p>(b) <u>All buildings or structures permitted by Rule GRZ2-R10(1)(a) must:</u></p> <p>(i) <u>Comply with the New Zealand Electrical Code of Practice for Electrical Safe Distances 34:2001 ISSN 0114-0663 under all National Grid transmission line operating conditions; and</u></p> <p>(ii) <u>Locate a minimum of 12m from the outer visible foundation of any National Grid support structure and associated stay wire, unless it is one of the following:</u></p> <p>(c) <u>A building or structure where Transpower has given written approval in accordance with clause 2.4.1 of the NZECP34:2001 ISSN 0114-0663;</u></p> <p>(d) <u>Fences less than 2.5m in height, measured from the natural ground level immediately below, and located a minimum of 5m from the nearest National Grid support structure foundation;</u></p> <p>(e) <u>Network utilities (other than for the reticulation and storage of water for irrigation purposes) or any part of electricity infrastructure undertaken by a network utility operator as defined in the Resource Management Act 1991, that connects to the National Grid; and</u></p> <p>(f) <u>Not permanently physically impede existing vehicular access to a National Grid support structure.</u></p>	
<b>MRZ2-R11</b>	<u>The establishment of any new sensitive land use within the National Grid Yard</u>
<b>Activity status: NC</b>	
<b>MRZ2-R12</b>	Any activity that is not listed as permitted, restricted discretionary or prohibited,
<b>Activity status: DIS</b>	
<b>MRZ-R13</b>	<del>Any building, structure, objects or vegetation that obscures the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (APP8 – Raglan navigation beacon).</del>
<b>Activity status: PR</b>	

*Land use – building*

<b>MRZ2-S1</b>	Residential unit
----------------	------------------

<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Up to three residential units per site.</p> 	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Intensity of the development; and</li> <li>(b) Design, scale and layout of buildings and outdoor living spaces in relation to the planned urban character of the zone;</li> <li>(c) The relationship of the development with adjoining streets or public open spaces, including the provision of landscaping; and</li> <li>(d) Privacy and overlooking within the development and on adjoining sites, including the orientation of habitable rooms and outdoor living spaces; and</li> <li>(e) Provision of 3-waters infrastructure to individual units; and</li> <li>(f) The provision of adequate waste and recycling bin storage including the management of amenity effects of these on streets or public open spaces; and</li> <li>(g) Where on-site car parking is provided, the design and location of car parking (including garaging) as viewed from streets or public open spaces.</li> </ul> <p><b>Notification</b>  <u>Any application for resource consent for four or more dwellings per site that comply with all of the standards in (MRZ2-S2 to MRSZ-S9) will be considered without public or limited notification.</u></p>
<p><b>MRZ2-S2</b>   Height – building general</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) <u>Buildings must not exceed 11 metres in height, except that 50% of a building’s roof in elevation, measured vertically from the junction between wall and roof, may exceed this height by 1m, where the entire roof slopes 15° or more, as shown on the following diagram (enlarged as Figure 1 at the conclusion of this Chapter).</u></p> 	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Height of the building or structure;</li> <li>(b) Design, scale and location of the building;</li> <li>(c) Extent of shading on adjacent sites; and</li> <li>(d) Privacy and overlooking on adjoining sites.</li> </ul> <p><b>Notification</b>  <u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S2 will be considered without public notification.</u></p>



- (a) The permitted height of any building or structure is 11m measured from the natural ground level immediately below that part of the structure;
- (b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 13m measured from the natural ground level immediately below the structure;
- (c) In Raglan, the permitted height of any building or structure is 7.5m measured from the natural ground level immediately below that part of the structure.
- (d) In Raglan, chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 9.5m measured from the natural ground level immediately below the structure;

**MRZ2-S3** | Height in relation to boundary

**(1) Activity status: PER**

**Where:**

- (a) Buildings must not project beyond a 60° recession plane measured from a point 4 metres vertically above ground level along all boundaries, as shown on the following diagram (enlarged as Figure 2 at the conclusion of this Chapter). Where the boundary forms part of a legal right of way, entrance strip, access site, or pedestrian access way, the height in relation to boundary applies from the farthest boundary of that legal right of way, entrance strip, access site, or



**(2) Activity status where compliance not achieved: RDIS**


**Council’s discretion is restricted to the following matters:**

- (a) Height of the building;
- (b) Design and location of the building;
- (c) Extent of shading on adjacent sites; and
- (d) Privacy on adjoining sites.

**Notification**

Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S3 will be considered without public notification.



pedestrian access way.



- (b) Standard (a) above does not apply to:
- (i) a boundary with a road
  - (ii) existing or proposed internal boundaries within a site:
  - (iii) site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.


(a) Buildings and structures must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 3m above natural ground level at every point of the site boundary, except

- (i) Where the boundary forms part of a legal right of way, entrance strip or access site; the standard applies from the farthest boundary of that legal right of way, entrance strip or access site;
- (ii) This standard does not apply to existing or proposed internal boundaries within a site;
- (iii) Where a site in the MRZ—Medium density residential zone adjoins a site in the GRZ—General residential zone, LLRZ—Large lot residential or SETZ—Settlement zone, then buildings must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 2.5m above natural ground level at every point of the site boundary abutting that GRZ—General residential zone, LLRZ—Large lot residential zone or SETZ—Settlement zone;

(iv) <del>Where the boundary adjoins a legal road.</del>										
<b>MRZ2-S4</b>	Setbacks									
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) <u>Buildings must be set back from the relevant boundary by the minimum depth listed in the yards table below:</u></p> <table border="1" style="margin-left: 20px;"> <thead> <tr> <th style="text-align: center;">Yard</th> <th style="text-align: center;">Minimum depth</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">Front</td> <td style="text-align: center;">1.5m</td> </tr> <tr> <td style="text-align: center;">Side</td> <td style="text-align: center;">1m</td> </tr> <tr> <td style="text-align: center;">Rear</td> <td style="text-align: center;">1m (excluded on corner sites)</td> </tr> </tbody> </table> <p>(b) <u>This standard does not apply to site boundaries where there is an existing common wall between 2 buildings on adjacent sites or where a common wall is proposed.</u></p> <p><del>(a) The finished external walls (excluding eaves) of a building must be set back a minimum of:</del></p> <p><del>(i) 3m from the road boundary;</del></p> <p><del>(ii) 3m from the edge of an indicative road (as demonstrated on a structure plan or planning maps);</del></p> <p><del>(iii) 1m from every boundary other than a road boundary; and</del></p> <p><del>(b) Balconies greater than 1.5m above ground level shall be set back a minimum of 4m from every boundary other than a boundary to a road or public open space;</del></p> <p><del>(c) MRZ-S10(1)(a) and (b) do not apply to structures that are not buildings.</del></p>	Yard	Minimum depth	Front	1.5m	Side	1m	Rear	1m (excluded on corner sites)		<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Road network safety and efficiency;</p> <p>(b) Potential to mitigate adverse effects on the streetscape through use of other design features;</p> <p>(c) Daylight admission to adjoining properties; and</p> <p>(d) Privacy overlooking on adjoining sites.</p> <p><b>Notification</b></p> <p><u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S4 will be considered without public notification.</u></p>
Yard	Minimum depth									
Front	1.5m									
Side	1m									
Rear	1m (excluded on corner sites)									
<b>MRZ2-S5</b>	Building coverage									
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) <u>The maximum building coverage must not exceed 50% of the net site area.</u></p> <p>(b) <del>The maximum building coverage must not exceed 45% of the net site area.</del></p> <p>(c) <del>MRZ-S6(1)(a) does not apply:</del></p> <p><del>(i) To a structure that is not a building;</del></p> <p><del>or</del></p>		<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Design, scale and location of the building;</p> <p>(b) Provision for outdoor living space and service courts; and</p> <p>(c) Effects on the planned urban built character of the surrounding residential area.</p> <p><b>Notification</b></p>								

<p>(ii) <del>Eaves of a building that project less than 750mm horizontally from the exterior wall of the building.</del></p>	<p><u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S5 will be considered without public notification.</u></p>
<p><b>MRZ2-S6</b></p>	<p>Outdoor living space (per unit)</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) <u>A residential unit at ground floor level must have an outdoor living space that is at least 20m<sup>2</sup> and that comprises ground floor, balcony, patio, or roof terrace space that meets all of the following standards:</u></p> <p>(i) <u>where located at ground level, has no dimension less than 3m; and</u></p> <p>(ii) <u>where provided in the form of a balcony, patio, or roof terrace, is at least 8m<sup>2</sup> and has a minimum dimension of 1.8m; and</u></p> <p>(iii) <u>is accessible from the residential unit; and</u></p> <p>(iv) <u>may be—</u></p> <p style="padding-left: 20px;">(1) <u>grouped cumulatively by area in one communally accessible location; or</u></p> <p style="padding-left: 20px;">(2) <u>located directly adjacent to the unit; and</u></p> <p>(v) <u>is free of buildings, parking spaces, and servicing and manoeuvring areas.</u></p> <p>(b) <u>A residential unit located above ground floor level must have an outdoor living space in the form of a balcony, patio, or roof terrace that—</u></p> <p>(i) <u>is at least 8m<sup>2</sup> and has a minimum dimension of 1.8m; and</u></p> <p>(ii) <u>is accessible from the residential unit; and</u></p> <p>(iii) <u>may be—</u></p> <p style="padding-left: 20px;">(1) <u>grouped cumulatively by area in one communally accessible location, in which case it may be located at ground level; or</u></p> <p style="padding-left: 20px;">(2) <u>located directly adjacent to the unit.</u></p> <p>(a) <del>An outdoor living space must be provided for each residential unit that meets all of the following standards:</del></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Design and location of the building;</p> <p>(b) Provision for outdoor living space including access to sunlight and open space and the usability and accessibility of the outdoor living space proposed;</p> <p>(c) Privacy and overlooking on adjoining sites; and</p> <p>(d) The proximity of the site to communal or public open space that has the potential to mitigate any lack of private outdoor living space.</p> <p><b>Notification</b></p> <p><u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S6 will be considered without public notification.</u></p>



<ul style="list-style-type: none"> <li>(i) It is for the exclusive use of the occupants of the residential unit;</li> <li>(ii) It is readily accessible from a living area of the residential unit;</li> <li>(iii) Where the residential unit contains an internal habitable space (excluding garages, bathrooms, laundries, and hall or stairways) on the ground floor, an outdoor living court shall be provided and shall have a minimum area of 20m<sup>2</sup> and a minimum dimension of 4m in any direction; and</li> <li>(iv) Where the residential unit has its principal living area at first floor level or above, a balcony shall be provided and shall have a minimum area of 5m<sup>2</sup> for studio and one bedroom dwellings, or 8m<sup>2</sup> for two or more bedroom dwellings and a minimum dimension of 1.5m.</li> </ul>	
<p><b>MRZ2-S7</b></p>	<p><u>Outlook space (per unit)</u></p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) <u>An outlook space must be provided for each residential unit as outlined below.</u></li> <li>(b) <u>An outlook space must be provided from habitable room windows as shown in the diagram below (enlarged as Figure 3 at the conclusion of this Chapter):</u></li> </ul>  <ul style="list-style-type: none"> <li>(c) <u>The minimum dimensions for a required outlook space are as follows:</u> <ul style="list-style-type: none"> <li>(i) <u>a principal living room must have an outlook space with a minimum dimension of 4m in depth and 4m in width; and</u></li> <li>(ii) <u>all other habitable rooms must have an outlook space with a minimum dimension of 1m in depth and 1m in width.</u></li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Measures to ensure that outlook spaces shall remain unobstructed, while providing an open outlook with access to daylight from the windows of habitable rooms;</li> <li>(b) The nature of the occupation of the room without the required outlook;</li> <li>(c) The effects on amenity of future occupants from a reduced outlook; and</li> <li>(d) Any privacy benefits from providing a reduced outlook.</li> </ul> <p><b>Notification</b>  <u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S7 will be considered without public notification.</u></p>

<p>(d) <u>The width of the outlook space is measured from the centre point of the largest window on the building face to which it applies.</u></p> <p>(e) <u>Outlook spaces may be over driveways and footpaths within the site or over a public street or other public open space.</u></p> <p>(f) <u>Outlook spaces may overlap where they are on the same wall plane in the case of a multi-storey building.</u></p> <p>(g) <u>Outlook spaces may be under or over a balcony.</u></p> <p>(h) <u>Outlook spaces required from different rooms within the same building may overlap.</u></p> <p>(i) <u>Outlook spaces must—</u></p> <p style="padding-left: 20px;">(i) <u>be clear and unobstructed by buildings; and</u></p> <p style="padding-left: 20px;">(ii) <u>not extend over an outlook space or outdoor living space required by another dwelling.</u></p>	
<p><b>MRZ2-S8</b></p>	<p>Windows to the street</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) <u>Any residential unit facing the street must have a minimum of 20% of the street-facing façade in glazing. This can be in the form of windows or doors.</u></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The extent to which front facing glazing is provided from ground floor living areas that is visible and prominent from the street;</p> <p>(b) Whether the majority of the glazing provided on the street facing façade of the unit is clear glazing to habitable spaces within the unit;</p> <p>(c) The level of passive surveillance from the residential unit to the street; and</p> <p>(d) Any other building features such as porches or gables that will add visual interest.</p> <p><b>Notification</b>  <u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S8 will be considered without public notification.</u></p>
<p><b>MRZ2-S9</b></p>	<p>Landscaped area</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) <u>A residential unit at ground floor level must have a landscaped area of a minimum of 20% of a developed site with</u></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p>

<p><u>grass or plants and can include the canopy of trees regardless of the ground treatment below them.</u></p> <p>(b) <u>The landscaped area may be located on any part of the development site, and does not need to be associated with each residential unit.</u></p>	<p>(a) The on-site and/or neighbouring amenity provided by the proposed landscaping;</p> <p>(b) The extent of landscaping between the buildings and road boundary to soften and integrate the development into the surrounding area;</p> <p>(c) The extent to which the breach is necessary to enable more efficient, cost effective and/or practical use of the remainder of the site;</p> <p>(d) The additional accessibility and safety benefits of providing less landscaped area; and</p> <p>(e) The effect of any reduction in landscaping on adjoining properties, including the street or other public open spaces.</p> <p><b>Notification</b>  <u>Any application for resource consent for one to three dwellings that does not meet the standard of MRZ2-S9 will be considered without public notification.</u></p>
<b>MRZ-S2</b>	Minimum residential unit size
<p><b>(3) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Residential units must have a minimum net internal floor area of:</p> <p>(i) 35m<sup>2</sup> for studio dwellings; and</p> <p>(ii) 45m<sup>2</sup> for one or more bedroom dwellings.</p>	<p><b>(4) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The functionality of the residential unit; and</p> <p><b>Internal residential amenity.</b></p>
<b>MRZ2-S10</b>	Impervious surfaces
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The impervious surfaces of a site must not exceed 70%.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Site design, layout and amenity; and</p> <p>(b) The risk of flooding, nuisance or damage to the site or other buildings and sites.</p>
<b>MRZ2-S11</b>	Ground floor internal habitable space
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Garages shall occupy less than 50% of the ground floor space internal to buildings on the site.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The visual dominance of garaging, parking, and vehicle manoeuvring areas and the balance across the site of internal habitable space, outdoor living courts, and landscaping at ground level; and</p>

		(b) The design and location of garaging as viewed from streets or public open spaces.
<b>MRZ2-SI2</b>	Fences or walls	
<b>(1) Activity status: PER</b> <b>Where:</b> (a) Boundary fences and walls between properties and any road boundaries, must comply with all of the following standards: (i) Be no higher than 1.5m if solid; (ii) Be no higher than 1.8m if: (1) Visually permeable for the full 1.8m height of the fence or wall; or (2) Solid up to 1.5m and visually permeable between 1.5 and 1.8m.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Building materials and design; (b) Effects on streetscape amenity; and (c) Public space visibility.
<b>MRZ2-SI3</b>	Building setbacks – water bodies	
<b>(1) Activity status: PER</b> <b>Where:</b> (a) A building must be set back a minimum of: (i) 20m from the margin of any lake; (ii) 20m from the margin of any wetland; (iii) <del>21.5m</del> <sup>23m</sup> from the bank of any river (other than the Waikato River and Waipa River); (iv) <del>25.5m</del> <sup>38m</sup> from the margin of either the Waikato River and the Waipa River (v) <del>23m from mean high water springs</del> (b) A public amenity of up to 25m <sup>2</sup> or pump shed within any building setback identified in MRZ2-SI3(1)(a); (c) This standard does not apply to a structure which is not a building.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body; (b) Adequacy of erosion and sediment control measures; (c) The functional or operational need for the building to be located close to the waterbody; (d) Effects on public access to the waterbody; (e) Effects on the amenity of the locality; and (f) Effects on natural character values.
<b>MRZ2-SI4</b>	<u>Building setback – sensitive land use</u>	
<b>(1) Activity status: PER</b> <b>Where:</b> (a) <u>Any new building or alteration to an existing building for a sensitive land use shall be set back a minimum of:</u> (i) <u>5m from the designated boundary of the railway corridor;</u> (ii) <u>15m from the boundary of a national route or regional arterial;</u> (iii) <u>25m from the designated boundary of the Waikato Expressway;</u>		<b>(2) Activity status where compliance not achieved: RDIS</b> <b><u>Council's discretion is restricted to the following matters:</u></b> (a) <u>Road network safety and efficiency;</u> (b) <u>On-site amenity values;</u> (c) <u>Odour, dust and noise levels received at the notional boundary of the building;</u> (d) <u>Mitigation measures; and</u> (e) <u>Potential for reverse sensitivity effects.</u>

<ul style="list-style-type: none"><li>(iv) <u>300m from the edge of oxidation ponds that are part of a municipal wastewater treatment facility on another site;</u></li><li>(v) <u>30m from a municipal wastewater treatment facility where the treatment process is fully enclosed; and</u></li><li>(vi) <u>300m from the boundary of the Alstra Poultry intensive farming activities located on River Road and Great South Road, Ngaaruawaahia.</u></li><li>(vii) <u>6m from the centre of a gas transmission line identified on the planning maps</u></li></ul>	
--	--

### Medium Density Residential Standard Figures




Figure 1: Building Height (refer to MRZ2-S2)




Figure 2: Height in relation to boundary (refer to MRZ2-S3)




Figure 3: Outlook space per unit (refer to MRZ2-S7)



## GRUZ – General rural zone

*The relevant district-wide chapter provisions apply in addition to this chapter.*

### **Purpose**

The GRUZ – General rural zone provides predominantly for primary production activities, including intensive indoor primary production. The zone also provides for occasional community facilities, agricultural produce processing facilities, rural-related commercial and industrial activities, conservation activities, network infrastructure, and quarrying activities. These diverse activities are set within a landscape that is visually dominated by openness and vegetation with significant separation between buildings and where natural character elements such as waterways, wetlands, water bodies, indigenous vegetation, and natural landforms are key contributors to the character of the rural zone.

### **Objectives**

GRUZ-O1 Purpose of the zone.

- (1) Enable farming activities;
- (2) Protect high class soils for farming activities;
- (3) Provide for rural industry, infrastructure, rural commercial, conservation activities, community facilities, and extractive activities;
- (4) Maintain rural character and amenity;
- (5) Limit development to activities that have a functional need to locate in the zone.

GRUZ-O2 Productive capacity of soils.

The primary productive value of soils, in particular high class soils, is retained.

GRUZ-O3 Rural character and amenity.

- (1) Maintain rural character and amenity.
- (2) The attributes of areas and features valued for their contribution to landscape values and visual amenity are maintained or enhanced.

GRUZ-O4 Extractive activities

Recognise the contribution of extractive industries to the economic and social well-being of the district.

### **Policies**

GRUZ-P1 High class soils.

Ensure the adverse effects of activities do not compromise the physical, chemical and biological properties of high class soils.

GRUZ-P2 Effects of subdivision and development on soils.

Subdivision, use and development minimises the fragmentation of productive rural land, particularly where high class soils are located.

**GRUZ-P3** Contributing elements to rural character and amenity values.

Recognise that rural character and amenity values vary across the zone as a result of the natural and physical resources present and the scale and extent of land use activities.

**GRUZ-P4** Productive rural activities.

- (1) Enable the on-going use of the rural environment zone as a productive working environment by:
- (a) Recognising that buildings and structures associated with farming and forestry and other operational structures for productive rural activities contribute to rural character and amenity values;
  - (b) Ensuring productive rural activities are supported by appropriate rural industries and services;
  - (c) Providing for lawfully-established rural activities and protecting them from sensitive land uses and reverse sensitivity effects; and
  - (d) Recognising the economic, social and cultural benefits that result from use and development of rural resources.

**GRUZ-P5** Other anticipated activities in rural areas

Enable activities that provide for the rural community's social, cultural, and recreational needs, subject to such activities being of a scale, intensity, and location that are in keeping with rural character and amenity values.

**GRUZ-P6** Industrial and commercial activities.

- (1) Provide for rural industry and rural commercial activities provided they are either dependent on the rural soil resource or have a functional or operational need for a rural location.
- (2) Such activities are to be managed to ensure that:
- (a) Their scale, intensity, and built form maintain rural character;
  - (b) They maintain an appropriate level of amenity for neighbouring sites; and
  - (c) They minimise reverse sensitivity effects on existing productive rural, intensive farming, quarrying, or rural industrial activities.
- (3) Avoid locating industrial and commercial activities in rural areas that do not have a genuine functional connection with the rural land or soil resource.

**GRUZ-P7** Intensive Farming activities.

Provide for intensive farming activities where they operate in accordance with industry best practice and the management of adverse effects beyond the site boundaries.

**GRUZ-P8** Home businesses.

Enable home businesses, provided that it is of a scale that maintains rural the character and amenity.

GRUZ-P9 Meremere Dragway.

Enable the ongoing operation and activities at the Meremere Dragway, provided that its adverse effects are avoided, remedied or mitigated.

GRUZ-P10 Waste management activities.

- (1) Encourage the rehabilitation of existing quarry sites
- (2) Ensure waste management facilities are located and operated so that rural amenity and character are maintained and conflict with rural activities are minimised.
- (3) Avoid waste management facilities located within:
  - (a) An Outstanding Natural Landscape;
  - (b) An Outstanding Natural Feature;
  - (c) An Outstanding Natural Character Area.

GRUZ-P11 Agricultural Research Centres.

Enable and protect the continued operation and development of Agricultural Research Centres that are an integral part of the agricultural sector.

GRUZ-P12 Huntly Power Station – coal and ash management.

- (1) Recognise and protect facilities that are integral to energy production at Huntly Power Station.
- (2) Provide for specific facilities that involve the handling, stockpiling, and haulage of coal and the management of coal ash water within identified areas in close proximity to Huntly Power Station.

GRUZ-P13 Reverse sensitivity and separation of incompatible activities.

- (1) Contain, as far as practicable, adverse effects within the site where the effect is generated.
- (2) Provide adequate separation of the activity from the site boundaries.
- (3) Ensure that new or extended sensitive land uses achieve adequate separation distances from and/or adopt appropriate measures to avoid, remedy or mitigate potential reverse sensitivity effects on productive rural activities, intensive farming, rural industry, infrastructure, extractive activities, or Extraction Resource Areas.

GRUZ-P14 Density of residential units and seasonal worker accommodation.

- (1) Maintain an open and spacious rural character by:
  - (a) Limiting residential units and seasonal worker accommodation to those associated with farming and productive rural activities;
  - (b) Limiting residential units to no more than one per Record of Title, except for particularly large titles where a minimum of 40ha is provided for each residential unit;
  - (c) Limiting the size, location, and number of minor residential units and requiring such units to be ancillary to an existing residential unit; and

- (d) Limiting seasonal worker accommodation to no more than one facility per Record of Title that is at least 20ha in area.

**GRUZ-P15 Retirement villages.**

Provide for alterations and additions to retirement villages existing or subject to a resource consent at 17 January 2022.

**GRUZ-P16 Building scale and location.**

- (1) Provide for buildings and structures where they are necessary components of farming and rural-related activities including rural industry, rural commercial, and extractive activities.
- (2) Manage the size and location of buildings and structures to:
- (a) Maintain adequate levels of outlook, daylight, and privacy for adjoining sensitive land uses and public reserves; and
- (b) Maintain rural character, amenity, and landscape values, in particular where located in areas with high landscape values, the coastal environment, and adjacent to waterbodies.

**GRUZ-P17 Management of extractive activities.**

- (1) Provide for extractive activities provided that adverse effects are appropriately avoided, remedied or mitigated; and, where this is not possible, off-set or compensated.
- (2) Protect access to, and extraction of, mineral, aggregate and coal resources by:
- (a) Identifying on planning maps lawfully-established extractive activities as either Aggregate Extraction Areas and or Coal Mining Areas on planning maps;
- (b) Identifying on planning maps the site of a potential extractive activity in an Extractive Resource Area;
- (3) Ensure that lawfully-established extractive activities are not compromised by new subdivision, use or development;
- (4) Avoid locating sensitive land uses within specified building setbacks in order to ensure the effective operation of an Aggregate Extraction Area, Coal Mining Area, or Extractive Resource Area.

**Rules**

*Land use – activities*

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>GRUZ-R1</b>	Farming
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>GRUZ-R2</b>	A home business

<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) It is wholly contained within a building;</li> <li>(b) The storage of materials or machinery associated with the home business is either wholly contained within a building, or where outside occupies no more than 100m<sup>2</sup> of site area and is located where it is not visible from other sites or public roads;</li> <li>(c) No more than 2 people who are not permanent residents of the site are employed at any one time;</li> <li>(d) Unloading and loading of vehicles or the receiving of customers or deliveries only occur after 7:00am and before 7:00pm on any day;</li> <li>(e) Machinery can be operated after 7:30am and up to 7:00pm on any day;</li> <li>(f) The home business shall not occupy more than 200m<sup>2</sup> in total within buildings and outdoor storage areas.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R3</b>   Meremere Dragway activity</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R4</b>   Afforestation not in an Outstanding Natural Landscape or Outstanding Natural Feature</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Be undertaken in accordance with Resource Management (National Environmental Standards for Plantation Forestry) Regulations 2017. Where compliance is not achieved with the permitted activity standards in the NES, then the activity is subject to the activity status as set out in the NES.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R5</b>   Plantation forestry</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Be undertaken in accordance with Resource Management (National Environmental Standards for Plantation Forestry) Regulations 2017. Where compliance is not achieved with the permitted activity standards in the NES, then the activity is subject to the activity status as set out in the NES.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R6</b>   Produce stall</p>	

<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R7</b>   Home stay</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Have no more than 5 guests.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R8</b>   Equestrian centre</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R9</b>   Horse training centre</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R10</b>   Visitors' accommodation</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Have no more than 5 guests; and                  (b) Be within a building that was existing as at 17 January 2022; and                  (c) Standards GRUZ-R10(a) and (b) do not apply to occupation of a single residential unit for short term rental.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R11</b></p>	<p>Residential activity, unless specified below.                   This includes occupation of a single residential unit for short term rental.</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R12</b>   Conservation activity</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R13</b>   Child care facility</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Have no more than four non-resident children.</p>	<p><b>(2) Activity status: RDIS</b>  <b>Where:</b>                  (a) A child care facility for five or more non-resident children, which is not in an Urban Expansion Area.   <b>Council's discretion is restricted to the following matters:</b>                  (b) The extent to which the scale and nature of the activity is consistent with managing urban growth through the consolidation of townships and the extent to which it is</p>

	<p>necessary to locate in the GRUZ – General Rural Zone;</p> <p>(c) Effects on rural character and amenity of both the streetscape and neighbours with particular regard to the bulk and location of buildings;</p> <p>(d) Nuisance effects including light spill and glare, odour, dust, and noise;</p> <p>(e) Traffic effects;</p> <p>(f) Reverse sensitivity effects on existing farming, intensive farming, rural industry, or quarrying activities; and</p> <p>(g) The extent to which the facilities are designed to meet Crime Prevention Through Environmental Design outcomes.</p> <p><b>(3) Activity status: DIS</b></p> <p><b>Where:</b></p> <p>(a) A child care facility located in an Urban Expansion Area.</p>
<b>GRUZ-R14</b>	<p>Maintenance, operation, and alterations to Tamahere Hospital (Section 55 SO 457609).</p> <p>Note: additions to this facility are subject to Rule GRUZ-R37.</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) The alterations do not increase net floor area.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-R15</b>	<p>Educational Facilities including student and staff accommodation at Dilworth Rural Campus (Lot 2 DP 52908 and Lot 1 DP 210936</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Land Use – building standards for the zone except:</p> <p>(i) GRUZ-S1 (Number of residential units) does not apply;</p> <p>(ii) GRUZ-S2 (Minor residential units) does not apply;</p> <p>(b) Student or staff accommodation must be ancillary to the educational facilities.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-R16</b>	<p>Mineral exploration and prospecting, including:</p> <p>(a) Sampling by methods involving hand tools;</p> <p>(b) Mechanical sampling where there is existing vehicle access to the area to be trenched or sampled;</p> <p>(c) Samples taken using explosives; and</p> <p>(d) Geophysical surveys not using explosives.</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

<p>(a) Shall not be located within all or part of any of the following landscape and natural character areas:</p> <ul style="list-style-type: none"> <li>(i) Outstanding Natural Feature;</li> <li>(ii) Outstanding Natural Landscape;</li> <li>(iii) High natural character area;</li> <li>(iv) Outstanding Natural Character area.</li> </ul> <p>(b) All drilling is limited to 150mm in diameter and a density of one drill site per hectare.</p> <p>(c) The cumulative length of trenching or sampling does not exceed 50 lineal metres per hectare.</p> <p>(d) Where areas are disturbed, topsoil shall be stockpiled and replaced over such areas, and the site shall be rehabilitated and restored generally to its original condition within 1 month of sampling being completed.</p> <p>(e) The use of explosives for sampling shall only occur between 7:00am to 7:00pm.</p>	<p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Separation from sensitive activities;</li> <li>(b) The visual and amenity effects of stockpiles;</li> <li>(c) Amenity effects relating to the hours of operation and noise;</li> <li>(d) Landscape and ecological effects;</li> <li>(e) Effects on waterbodies, riparian margins, and wetlands;</li> <li>(f) Site restoration; and</li> <li>(g) Financial contributions towards landscaping, site restoration, and roading.</li> </ul>
<p><b>GRUZ-R17</b>   Free range pig or poultry farming, and poultry hatcheries</p>	
<p><b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R18</b>   Seasonal worker accommodation</p>	
<p><b>(1) Activity status: PER</b> <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Is used solely for part of the year to meet labour requirements for primary production;</li> <li>(b) Comprises of communal kitchen and eating areas and separate sleeping and ablution facilities;</li> <li>(c) Accommodates no more than 12 workers; and</li> <li>(d) Complies with Code of Practice for Able Bodied Seasonal Workers, published by Dept of Building and Housing 2008.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The effectiveness of methods to avoid, remedy, or mitigate the effects on existing activities, including the provision of screening, landscaping, and methods for noise control; and</li> <li>(b) The extent to which the application complies with the Code of Practice for Able Bodied Seasonal Workers, published by the Department of Building and Housing 2008.</li> </ul>
<p><b>GRUZ-R19</b>   Recreational hunting and freshwater fishing</p>	
<p><b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>GRUZ-R20</b>   Gardening</p>	
<p><b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>



<b>GRUZ-R21</b>	Buildings, structures and sensitive land use within the National Grid Yard on sites existing as of 18 July 2018
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Within National Grid Yard:</p> <ul style="list-style-type: none"> <li>(i) Building alterations and additions to an existing building or structure that does not involve an increase in the building height or footprint; or</li> <li>(ii) Infrastructure (other than for the reticulation and storage of water for irrigation purposes) undertaken by a network utility operator as defined in the Resource Management Act 1991; or</li> <li>(iii) Non-habitable buildings or structures for farming activities in rural zones including accessory structures and yards for milking/dairy sheds (but not including any intensive farming buildings, commercial greenhouses and milking/dairy sheds); or</li> <li>(iv) Non-habitable horticultural buildings; or</li> <li>(v) Artificial crop protection and support structures (excluding commercial greenhouses and <i>Pseudomonas syringae</i> pv. <i>Actinidiae</i> (Psa) disease control structures);</li> <li>(vi) Fences less than 2.5m in height, measured from the natural ground level immediately below the structure; and</li> <li>(vii) Minor structures associated with farming activity that are not situated within 12m of the outer visible foundation of any National Grid tower or 10m of the outer visible foundation of a National Grid tower, including: fences, gates, stock exclusion structures, cattle-stops, stock underpasses, stock bridges and culvert crossings, and drinking water supply pipelines, troughs, and water storage tanks.</li> </ul> <p>(b) All buildings or structures permitted by Rule GRUZ-R21(1)(a) must:</p> <ul style="list-style-type: none"> <li>(i) Comply with the New Zealand Electrical Code of Practice for Electrical Safe Distances 34:2001 ISSN 0114-0663 under all National Grid</li> </ul>	<p><b>(2) Activity status where compliance not achieved: NC</b></p>

<p>transmission line operating conditions; and</p> <p>(1) Locate a minimum 12m from the outer visible foundation of any National Grid support structure foundation and associated stay wire, unless it is:</p> <p>(2) A building or structure where Transpower has given written approval in accordance with clause 2.4.1 of the NZECP; or</p> <p>(3) Fences less than 2.5m in height, measured from the natural ground level immediately below the structure, and located a minimum of 5m from the nearest National Grid support structure foundation; or</p> <p>(ii) Network utilities (other than for the reticulation and storage of water for irrigation purposes) or any part of electricity infrastructure undertaken by a network utility operator as defined in the Resource Management Act 1991, that connects to the National Grid; and</p> <p>(iii) Not permanently physically impede existing vehicular access to a National Grid support structure;</p> <p>(c) Artificial crop protection structures and support structures between 8m and 12m from a pole support structure but not a tower and any associated guy wire that:</p> <p>(i) Meet the requirements of the NZECP 34:2001 ISSN 0114-0663 for separation distances from the conductor;</p> <p>(ii) Are no higher than 2.5m;</p> <p>(iii) Are removable or temporary, to allow a clear working space of at least 12 metres from the pole when necessary for maintenance and emergency repair purposes;</p> <p>(iv) Allow all-weather access to the pole and a sufficient area for maintenance equipment, including a crane.</p>	
<p><b>GRUZ-R22</b></p>	<p>Construction or alteration of a building for a sensitive land use</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) The construction or alteration of a building for a sensitive land use that</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on the amenity values of the site;</p>

Part 3: Area-specific matters / Zones / Rural zones / GRUZ – General rural zone

<p>complies with all of the following standards:</p> <p>(i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or</p> <p>(ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.</p>	<p>(b) The risk of electrical hazards affecting the safety of people;</p> <p>(c) The risk of damage to property; and</p> <p>(d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.</p>
<b>GRUZ-R23</b>	Construction, demolition, addition, and alteration of a building or structure
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRUZ-R24</b>	An agricultural or horticultural research activity, including laboratories and administrative facilities within the Agricultural Research Centres specific control area identified on the planning maps
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRUZ-R25</b>	An educational facility, including conference and teaching facilities within the Agricultural Research Centres specific control area identified on the planning maps
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) That is incidental to agricultural or horticultural research.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-R26</b>	An industrial activity within the Agricultural Research Centres specific control area identified on the planning maps
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) That is incidental to agricultural or horticultural research.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-R27</b>	A trade or engineering workshop within the Agricultural Research Centres specific control area identified on the planning maps
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) That is incidental to agricultural or horticultural research.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-R28</b>	Intensive farming within the Agricultural Research Centres specific control area identified on the planning maps
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) That is incidental to agricultural or horticultural research; and</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<p>(b) Where an associated building and animal feedlot are located at least 200m inside any boundary of an Agricultural Research Centre site.</p>	
<p><b>GRUZ-R29</b></p>	<p>The on-site disposal or storage of solid organic waste or cleanfill within the Agricultural Research Centres specific control area identified on the planning maps</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) That is incidental to agricultural or horticultural research; and                  (b) Where the solid organic waste or cleanfill is generated on the site.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R30</b></p>	<p>A staff facility, including:                  (a) A recreational facility                  (b) Staff residential units                  (c) Cafeterias and cafés                  (d) Social clubs</p> <p>within the Agricultural Research Centres specific control area identified on the planning maps</p>
<p><b>(2) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) That is incidental to agricultural or horticultural research.</p>	<p><b>(3) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R31</b></p>	<p>Coal related activities within the Huntly Power Station - Coal and Ash Management specific control area identified on the planning maps</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) Coal related activities within the Huntly Power Station - Coal and Ash Management specific control area identified on the planning maps involving:                  (i) Stockpiling;                  (ii) Screening and sorting;                  (iii) Use of transportation conveyors;                  (iv) Erection, operation, and maintenance of loading and unloading facilities; and                  (v) An activity that is ancillary to those listed in (i) – (iv) above.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R32</b></p>	<p>The management, stockpiling, transportation, and disposal of coal ash and coal ash water within the Huntly Power Station - Coal and Ash Management specific control area identified on the planning maps</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  (a) The management, stockpiling, transportation, and disposal of coal ash and coal ash water where:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b>                  (a) Visual amenity; and                  (b) Traffic effects.</p>

<p>(i) These materials are transported between the Huntly Power Station and the ash ponds located adjacent to Te Ohaaki Road via the pipeline located within the Huntly Power Station - Coal and Ash Management specific control area;</p> <p>(ii) They involve the operation and maintenance of the ash disposal ponds located adjacent to Te Ohaaki Road within within the Huntly Power Station - Coal and Ash Management specific control area; and</p> <p>(iii) They involve the transportation of ash from the ash ponds to a long-term disposal facility, provided the heavy vehicle movement are not more than 85 per day.</p>	
<p><b>GRUZ-R33</b></p>	<p>Energy corridor – transportation of minerals and substances within the Huntly Power Station - Coal and Ash Management specific control area identified on the planning maps</p>
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <p>(a) The transportation of minerals and substances in an energy corridor must comply with all the following standards:</p> <p>(i) be limited to coal ash, aggregate, overburden, cleanfill, wastewater and other liquids (other than a hazardous substance);</p> <p>(ii) not deposit discernible minerals or dust; and</p> <p>(iii) not result in odour identified outside the energy corridor.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Adverse amenity effects.</p>
<p><b>GRUZ-R34</b></p>	<p>Intensive farming</p>
<p><b>(1) Activity status: RDIS</b>  <b>Activity-specific standards:</b>          Nil.  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Intensive Farming that meets all of the following standards:</p> <p>(i) Land use – effects standards for the zone;</p> <p>(ii) Land use – building standards for the zone;</p> <p>(iii) Building coverage does not exceed 3% of the site:</p> <p>(1) GRUZ-S9 – GRUZ-S11 (Building coverage) does not apply;</p> <p>(iv) Building height does not exceed 15m;</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<p>(1) GRUZ-S4 – GRUZ-S7 (Building height) does not apply.</p> <p>(b) Intensive farming s not located in:</p> <ul style="list-style-type: none"><li>(i) An Outstanding Natural Feature;</li><li>(ii) An Outstanding Natural Landscape;</li><li>(iii) An Outstanding Natural Character Area; or</li><li>(iv) A High Natural Character Area.</li></ul> <p>(c) For intensive pig farming, buildings and outdoor enclosures are set back at least:</p> <ul style="list-style-type: none"><li>(i) 300 metres from any site boundary;</li><li>(ii) From any boundary of a GRZ – General residential zone, MRZ<u>1</u> – Medium density residential zone <u>1</u>, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large lot residential zone, SETZ – Settlement zone or RLZ – Rural lifestyle zone:<ul style="list-style-type: none"><li>(1) 1200 metres (500 or fewer less pigs); or</li><li>(2) 2000 metres (more than 500 pigs).</li></ul></li></ul> <p>(d) For housed or free-range poultry that meets the definition for intensive farming and all other intensive farming, buildings and outdoor enclosures are set back at least:</p> <ul style="list-style-type: none"><li>(i) 300 metres from any site boundary; and</li><li>(ii) 500 metres from any boundary of a GRZ – General Residential, MRZ<u>1</u> – Medium density residential zone <u>1</u>, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large Lot Residential, SETZ - Settlement or RLZ – Rural Lifestyle Zone.</li><li>(iii) The extent to which the activity may adversely impact on the noise environment.</li></ul> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"><li>(e) Traffic effects;</li><li>(f) Effects on amenity values, including odour, visual impact, landscaping;</li><li>(g) Location, type and scale of development; and</li><li>(h) Noise effects.;</li><li>(i) Odour and dust effects, except where a Certificate of Compliance or resource consent has been obtained from the</li></ul>	
--	--

<p>Waikato Regional Council for air discharges; and</p> <p>(j) The extent to which the farm will operate in accordance with an approved farm Environment Plan or relevant industry codes of practice.</p>	
<p><b>GRUZ-R35</b></p>	<p>Rural Industry, including packhouses and coolstores that handle produce sourced from other sites, feed mills and animal feed production, and rural contractors' depots</p>
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Rural Industry, including packhouses and coolstores that handle produce sourced from other sites, feed mills and animal feed production, and rural contractors' depots; that meet the following standards:</p> <p>(i) Not in an Urban Expansion Area; and</p> <p>(ii) Is not an extractive activity.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(b) The extent to which the scale and nature of the activity is consistent with managing urban growth through the consolidation of townships and the extent to which it is necessary to locate in the GRUZ – General rural zone;</p> <p>(c) Effects on rural character and amenity of both the streetscape and neighbours with particular regard to the bulk and location of buildings,</p> <p>(d) Location, type and scale of development;</p> <p>(e) Nuisance effects including light spill and glare, odour, dust, noise; and</p> <p>(k) Traffic effects.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R36</b></p>	<p>Educational facilities that are primary or secondary schools not otherwise provided for as a permitted activity by Rule GRUZ-R15(1) or GRUZ-R25(1)</p>
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) Educational facilities that are primary or secondary schools not otherwise provided for as a permitted activity by Rule GRUZ-R15(1) or GRUZ-R25(1) which meet the following standard:</p> <p>(i) Not in an Urban Expansion Area.</p> <p><b>Council's discretion is restricted to the following matters:</b></p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<p>(b) The extent to which the scale and nature of the activity is consistent with managing urban growth through the consolidation of townships and the extent to which it is necessary to locate in the GRUZ – General rural zone;</p> <p>(c) Effects on rural character and amenity of both the streetscape and neighbours with particular regard to the bulk and location of buildings;</p> <p>(d) Nuisance effects including light spill and glare, odour, dust, and noise;</p> <p>(e) Traffic effects;</p> <p>(f) Reverse sensitivity effects on existing farming, intensive farming, rural industry, or quarrying activities; and</p> <p>(g) The extent to which the facilities are designed to meet Crime Prevention Through Environmental Design outcomes.</p>	
<p><b>GRUZ-R37</b></p>	<p>Community facility</p>
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) A Community facility which meets the following standard:</p> <p>(i) Not in an Urban Expansion Area.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(b) The extent to which the scale and nature of the activity is consistent with managing urban growth through the consolidation of townships and the extent to which it is necessary to locate in the GRUZ – General rural zone;</p> <p>(c) Effects on rural character and amenity of both the streetscape and neighbours with particular regard to the bulk and location of buildings;</p> <p>(d) Nuisance effects including light spill and glare, odour, dust, and noise;</p> <p>(e) Traffic effects;</p> <p>(f) Reverse sensitivity effects on existing farming, intensive farming, rural industry, or quarrying activities; and</p> <p>(g) The extent to which the facilities are designed to meet Crime Prevention Through Environmental Design outcomes.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R38</b></p>	<p>Rural commercial</p>



<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Rural commercial that meet the following standard: <ul style="list-style-type: none"> <li>(i) Not in an Urban Expansion Area.</li> </ul> </li> </ul> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) The extent to which the scale and nature of the activity is consistent with managing urban growth through the consolidation of townships and the extent to which it is necessary to locate in the GRUZ – General rural zone;</li> <li>(c) Effects on rural character and amenity of both the streetscape and neighbours with particular regard to the bulk and location of buildings;</li> <li>(d) Nuisance effects including light spill and glare, odour, dust, and noise;</li> <li>(e) Traffic effects; and</li> <li>(f) Reverse sensitivity effects on existing farming, intensive farming, rural industry, or quarrying activities.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R39</b>   Agricultural and horticultural research facilities</p>	
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Agricultural and horticultural research facilities that meet the following standard: <ul style="list-style-type: none"> <li>(i) Not in an Urban Expansion Area.</li> </ul> </li> </ul> <p>Note: For research activities undertaken within an Agriculture Research Centre Specific Area, rules GRUZ-R24 – GRUZ-30 also apply.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(b) Effects on rural character and amenity;</li> <li>(c) Nuisance effects including light spill and glare, odour, dust, and noise;</li> <li>(d) Traffic effects;</li> <li>(e) Reverse sensitivity effects on existing farming, intensive farming, rural industry, or quarrying activities;</li> <li>(f) The extent to which the scale and nature of the activity is consistent with managing urban growth through the consolidation of townships.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-R40</b>   An extractive activity or waste management activity located within an Aggregate Extraction Area, Coal Mining Area or Extractive Resource Area</p>	

<p><b>(1) Activity status: RDIS</b>  <b>Activity-specific standards:</b>                  Nil</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on rural character and amenity;</li> <li>(b) Location, type and scale of development;</li> <li>(c) Nuisance effects including dust, noise, vibration, odour and light spill;</li> <li>(d) Industry best practice and use of management plans;</li> <li>(e) Traffic effects;</li> <li>(f) Erosion and sediment control; and</li> <li>(g) Rehabilitation and end use including back filling.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>GRUZ-R41</b>	A waste management facility located outside an Aggregate Extraction Area, Coal Mining Area or Extractive Resource Area.
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R42</b>	Hazardous waste storage, processing or disposal.
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R43</b>	An educational facility that is not a primary or secondary school.
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R44</b>	A correctional facility
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R45</b>	An extractive activity located outside an Aggregate Extraction Area, Coal Mining Area or Extractive Resource Area.
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R46</b>	Visitors' accommodation for 6 or more people or that is within a building that was constructed after 17 January 2022.
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R47</b>	Motorised sport and recreation
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R48</b>	Transport depot
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R49</b>	Afforestation of any part of an Outstanding Natural Landscape or Outstanding Natural Feature
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R50</b>	A dog or cat boarding, daycare, breeding or animal training establishment
<b>(1) Activity status: DIS</b>	
<b>GRUZ-R51</b>	Construction of a building located on an indicative road prior to that road being constructed and vested in Council.
<b>(1) Activity status: NC</b>	
<b>GRUZ-R52</b>	Any new building for a sensitive land use, or addition to an existing building that involves an increase in the building envelope or height for a sensitive land use, within the National Grid Yard
<b>(1) Activity status: NC</b>	

Part 3: Area-specific matters / Zones / Rural zones / GRUZ – General rural zone

<b>GRUZ-R53</b>	Any change of use of an existing building to a sensitive land use within the National Grid Yard
<b>(I) Activity status: NC</b>	
<b>GRUZ-R54</b>	The establishment of any new sensitive land use within the National Grid Yard
<b>(I) Activity status: NC</b>	
<b>GRUZ-R55</b>	Dairy/milking sheds (excluding accessory structures and buildings), commercial greenhouses, Pseudomonas syringae pv. Actinidiae (Psa) disease control structures, or buildings for intensive farming within the National Grid Yard
<b>(I) Activity status: NC</b>	
<b>GRUZ-R56</b>	An extractive activity industry located within all or part of any of the following landscape and natural character areas: (a) Outstanding Natural Feature; (b) Outstanding Natural Landscape; (c) High natural character area; or (d) Outstanding Natural Character area.
<b>(I) Activity status: NC</b>	
<b>GRUZ-R57</b>	A waste management facility located within all or part of any of the following landscape and natural character areas: (a) Outstanding Natural Feature; (b) Outstanding Natural Landscape; (c) High Natural Character area; or (d) Outstanding Natural Character Area.
<b>(I) Activity status: NC</b>	
<b>GRUZ-R58</b>	The following activities located within the Urban Expansion Area, the following activities: (a) Intensive farming; (b) Storage, processing or disposal of hazardous waste; (c) Correctional facility; (d) Extractive activity; (e) Industrial activity, including rural industry; (f) Rural commercial; (g) Agricultural and horticultural research facilities; (h) Motorised sport and recreation activity; or (i) Transport depot.
<b>(I) Activity status: NC</b>	
<b>GRUZ-R59</b>	Industrial activity, excluding a rural industrial activity
<b>(I) Activity status: NC</b>	
<b>GRUZ-R60</b>	Commercial activity, excluding a produce stall or rural commercial activity.
<b>(I) Activity status: NC</b>	
<b>GRUZ-R61</b>	Any activity that is not specifically listed as a permitted, controlled, restricted discretionary or non-complying activity
<b>(I) Activity status: NC</b>	
<b>GRUZ-R62</b>	Any building, structure, objects or vegetation that obscure the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (APP8 – Raglan navigation beacon).
<b>Activity status: PR</b>	

Land use – building

<b>GRUZ-S1</b>	Number of residential units and seasonal worker accommodation within a lot	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) One residential unit within a Record of Title containing an area less than 40ha;</li> <li>(b) Within a lot Record of Title containing an area of 40ha or more, one additional residential unit is permitted for every additional 40ha of area up to a maximum of three residential units;</li> <li>(c) One seasonal worker accommodation shall be located within a Record of Title containing an area of 20ha or more (this is in addition to the residential unit in GRUZ-S1(1)(a));</li> <li>(d) Any residential unit(s) under GRUZ-S1(1)(a) and (b), or seasonal worker accommodation under GRUZ-S1(1)(a)(c) must not be located within any of the following landscape and natural character areas: <ul style="list-style-type: none"> <li>(i) Outstanding Natural Feature;</li> <li>(ii) Outstanding Natural Landscape;</li> <li>(iii) Outstanding Natural Character Area;</li> <li>or</li> <li>(iv) High Natural Character Area.</li> </ul> </li> </ul>	<p><b>(2) Activity status: DIS</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A residential unit that complies with GRUZ-S1(1)(a) or (b) and is located within an area listed in (d); or</li> <li>(b) Seasonal worker accommodation that complies with GRUZ-S1(1)(c) and is located within an area listed in (d).</li> </ul> <p><b>(3) Activity status: NC</b></p> <p><b>Where</b></p> <ul style="list-style-type: none"> <li>(a) A residential unit that does not comply with GRUZ-S1(1)(a) or (b);</li> <li>(b) Seasonal worker accommodation that does not comply with GRUZ-S1(1)(c).</li> </ul>	
<b>GRUZ-S2</b>	Minor residential units	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) One minor residential unit not exceeding 120m<sup>2</sup> gross floor area (excluding accessory buildings) within a Record of Title lot.</li> <li>(b) The minor residential unit shall be located on the same Record of Title as an existing residential unit and shall: <ul style="list-style-type: none"> <li>(i) Be located within 100m of the existing residential unit;</li> <li>(ii) Share a single driveway access with the existing residential unit.</li> </ul> </li> <li>(c) Any minor residential unit must not be located within any of the following landscape or natural character areas: <ul style="list-style-type: none"> <li>(i) Outstanding Natural Feature;</li> <li>(ii) Outstanding Natural Landscape;</li> <li>(iii) Outstanding Natural Character Area;</li> <li>or</li> <li>(iv) High Natural Character Area.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>	

<b>GRUZ-S3</b>	Building height – general
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The maximum height of any building or structure measured from the natural ground level immediately below that part of the structure must not exceed 15m, except:</p> <p>(i) The maximum height is 10m where located within 50m of a road or internal boundary;</p> <p>(ii) For hose drying towers associated with emergency service facilities the maximum height is 15m.</p> <p>(b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 17m measured from the natural ground level immediately below the structure, except where located within 50m of a road or internal boundary where the maximum height is 12m.</p> <p>Advice note: the height of frost fans is subject to GRUZ-S4.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Height of the building;</p> <p>(b) Design and location of the building;</p> <p>(c) Admission of daylight and sunlight to the site and other site;</p> <p>(d) Privacy on any other site; and</p> <p>(e) Amenity values of the locality.</p>
<b>GRUZ-S4</b>	Building height – frost fans
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The height of the support structure for a frost fan must not exceed 10.5m; and</p> <p>(b) The fan blades must not rotate higher than 13.5m above natural ground level.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-S5</b>	Building height – within a Campus (Agricultural Research Centres specific control area)
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building or structure within a campus identified on the planning maps must not exceed a height of 15m measured from the natural ground level immediately below that part of the structure.</p> <p>(b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 17m measured from the natural ground level immediately below the structure</p> <p>(c) GRUZ-S3 (Building height – general) does not apply.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on visual amenity.</p>
<b>GRUZ-S6</b>	Building height – within the Huntly Power Station Coal and Ash Management specific control area

<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) A building measured from the natural ground level immediately below that part of the structure must not exceed a height of:                  (i) 30m within an area of up to 1500m<sup>2</sup>; and                  (ii) 20m for the balance of the Huntly Power Station Coal and Ash Management specific control area.                  (b) GRUZ-S3 (Building height – general) does not apply.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-S7</b>   Height – buildings, structures and vegetation in a battlefield view shaft</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) The maximum height of any building, structure or vegetation within a battlefield view shaft as shown on the planning map must not exceed 5m.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>GRUZ-S8</b>   Height in relation to boundary</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) A building or structure (excluding poles or aerials) must not protrude through the height in relation to boundary rising at an angle of 45 degrees commencing at an elevation of 2.5m above ground level at every point of the site boundary.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b>                  (a) Height of the building;                  (b) Design and location of the building;                  (c) Admission of daylight and sunlight to the site and other site;                  (d) Privacy on any other site; and                  (e) Amenity values of the locality.</p>
<p><b>GRUZ-S9</b>   Building coverage</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b>                  (a) The total building coverage must not exceed:                  (i) 2% of the site area or 500m<sup>2</sup> (whichever is larger) for sites smaller than 10ha;                  (ii) 5,000m<sup>2</sup> for sites larger than 10ha.                  (b) GRUZ-S9(1)(a) does not apply:                  (i) To a structure that is not a building; or                  (ii) Eaves of a building that project less than 750mm horizontally from the exterior wall of the building.                  (c) No site coverage limit applies to Artificial Crop Protection Structures that meet the following standards:</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matter:</b>                  (a) Design, scale and location of the building.</p>

<ul style="list-style-type: none"> <li>(i) Green or black cloth shall be used on vertical faces within 30m of the site boundary;</li> <li>(ii) Green, black or white cloth shall be used on horizontal surfaces.</li> </ul>	
<b>GRUZ-S10</b>	Building coverage
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The total building coverage at Dilworth Rural Campus (Lot 2 DP 52908 and Lot 1 DP 210935) must not exceed 10,000m<sup>2</sup>.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-S11</b>	Building coverage – within a Campus (Agricultural Research Centres specific control area)
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Building coverage must not exceed 70% of a campus identified on the planning maps.</li> <li>(b) GRUZ-S9 (Building coverage) does not apply.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on visual amenity; and</li> <li>(b) Stormwater management.</li> </ul>
<b>GRUZ-S12</b>	Building setbacks – all boundaries
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A habitable building located on a Record of Title less than 1.6ha must be set back a minimum of: <ul style="list-style-type: none"> <li>(i) 7.5m from the road boundary;</li> <li>(ii) 17.5m from the centre line of an indicative road;</li> <li>(iii) 25m from the boundary of an adjoining site that is 6ha or more;</li> <li>(iv) 12m from the boundary of an adjoining site that is less than 6ha;</li> </ul> </li> <li>(b) A non-habitable building or structure located on a Record of Title less than 1.6ha must be set back a minimum of: <ul style="list-style-type: none"> <li>(i) 7.5m from the road boundary;</li> <li>(ii) 17.5m from the centre line of an indicative road;</li> <li>(iii) 12m from every boundary other than a road boundary.</li> </ul> </li> <li>(c) Standard GRUZ-S12(1)(b) does not apply to fences or structures less than 2m in height, retaining walls, poles or arials.</li> <li>(d) A habitable building located on a Record of Title 1.6ha or more must be set back a minimum of: <ul style="list-style-type: none"> <li>(i) 12m from the road boundary;</li> <li>(ii) 22m from the centre line of an indicative road;</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on rural amenity values;</li> <li>(b) Transport network safety and efficiency;</li> <li>(c) Reverse sensitivity effects; and</li> <li>(d) Where the road boundary is with an unformed paper road the likelihood of the road being formed or readily utilised by the public.</li> </ul>

<p>(iii) 25m from every boundary other than a road boundary.</p> <p>(e) A non-habitable building or structure located on a Record of Title 1.6ha or more must be set back a minimum of:</p> <p>(i) 12m from the road boundary;</p> <p>(ii) 22m from the centre line of an indicative road;</p> <p>(iii) 12m from every boundary other than a road boundary.</p> <p>(f) Standard GRUZ-S12(1)(e) does not apply to fences or structures less than 2m in height, retaining walls, poles or aerials;</p> <p>(g) Any building at Dilworth Rural Campus (Lot 2 DP 52908 and Lot 1 DP 210936) must be set back a minimum of 12m from any site boundary.</p>	
<p><b>GRUZ-S13</b> Building setbacks – sensitive land use</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any building for a sensitive land use must be set back a minimum of:</p> <p>(i) 5m from the designated boundary of the railway corridor;</p> <p>(ii) 15m from a national route or regional arterial road;</p> <p>(iii) 35m from the designated boundary of the Waikato Expressway;</p> <p>(iv) 200m from an Aggregate Extraction Area or Extractive Resource Area containing a sand resource;</p> <p>(v) 500m from an Aggregate Extraction Area or Extractive Resource Area containing a rock resource, or a Coal Mining Area;</p> <p>(vi) 100m from a site in the Tamahere Commercial Areas A and C;</p> <p>(vii) 300m from the boundary of buildings or outdoor enclosures used for an intensive farming activity. This setback does not apply to sensitive activities located on the same site as the intensive farming activity;</p> <p>(viii) 300m from oxidation ponds that are part of a municipal wastewater treatment facility on another site;</p> <p>(ix) 30m from a municipal wastewater treatment facility where the treatment process is fully enclosed; and</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Road network safety and efficiency;</p> <p>(b) On-site amenity values;</p> <p>(c) Odour, dust and noise levels received at the notional boundary of the building;</p> <p>(d) Mitigation measures; and</p> <p>(e) Potential for reverse sensitivity effects.</p>



(x) Not be located within the Te Uku wind farm setback shown on the planning maps.	
<b>GRUZ-S14</b>   Building setback – noise sensitive activities	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Construction of, or addition, or alteration to a building containing a noise sensitive activity must comply with APP1 – Acoustic insulation within:</p> <p>(i) 350m of the Huntly Power Station site boundary; or</p> <p>(ii) The Waikato Gun Club Noise Control Boundary.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Internal design sound levels;</p> <p>(b) On-site amenity values; and</p> <p>(c) Potential for reverse sensitivity effects.</p>
<b>GRUZ-S15</b>   Building setback – waterbodies	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building other than provided for under Standards GRUZ-S15(1)(b) and (c) must be set back a minimum of:</p> <p>(i) 32m from the margin of any lake with a size of 8ha or more;</p> <p>(ii) 32m from the margin of any wetland;</p> <p>(iii) 32m from the bank of a river with an average width of 3m or more, other than the Waikato River and Waipa River;</p> <p>(iv) 37m from a bank of the Waikato River and Waipa River;</p> <p>(v) 12m from the bank of any river with an average width of 3m or less;</p> <p>(vi) 12m from the margin of any lake with a size of less than 8ha;</p> <p>(vii) 32m from mean high water springs</p> <p>(b) A public amenity building, or maimai used for temporary waterfowl hunting purposes, of up to 25m<sup>2</sup> in size;</p> <p>(c) A pump shed (public or private) set back a minimum of 5m from any waterbody.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body;</p> <p>(b) Adequacy of erosion and sediment control measures;</p> <p>(c) The functional or operational need for the building to be located close to the waterbody;</p> <p>(d) Effects on public access to the waterbody;</p> <p>(e) Effects on rural character and amenity; and</p> <p>(f) Effects on natural character values.</p>
<b>GRUZ-S16</b>   Building setback – Te Kawhata Environmental Protection Area	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any building must be set back a minimum of 3m from the Te Kawhata Environmental Protection Area identified on the planning maps.</p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>GRUZ-S17</b>   Building setback and location within the Huntly Power Station Coal and Ash Management specific control area	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<p>(a) A building must be:</p> <ul style="list-style-type: none"> <li>(i) Set back at least 20m from every boundary of the Huntly Power Station Coal and Ash Management specific control area where its height exceeds 20m; and</li> <li>(ii) Set back at least 10m from every boundary of the Huntly Power Station Coal and Ash Management specific control area where its height is up to 20m; or</li> <li>(iii) Located within an energy corridor (refer to the Huntly Power Station Coal and Ash Management specific control area on the planning maps).</li> </ul> <p>(b) GRUZ-S12 – GRUZ-S16 do not apply.</p>	
<p><b>GRUZ-S18</b></p>	<p>Coal stockpile height, setback and coverage within the Huntly Power Station Coal and Ash Management specific control area</p>
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Coal stockpiles must: <ul style="list-style-type: none"> <li>(i) not exceed a height of 15m;</li> <li>(ii) be set back at least 5m from the boundary of the Huntly Power Station Coal and Ash Management specific control area;</li> <li>(iii) not exceed 25% of the the Huntly Power Station Coal and Ash Management specific control area.</li> </ul> </li> </ul> <p>(b) GRUZ-S12 – GRUZ-S16 do not apply.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Visual amenity.</li> </ul>

## LCZ – Local centre zone

*The relevant district-wide chapter provisions apply in addition to this chapter.*

### Purpose

The LCZ – Local centre zone provides for a range of commercial and community activities that service the needs of the residential catchment.

### Objectives

LCZ-O1 Economic growth of industry.

Commercial activity is focussed within a differentiation of commercial zones (comprising the TCZ – Town centre zone, LCZ – Local centre zone, COMZ – Commercial zone, and the BTZ – Business Tamahere zone.

LCZ-O2 Local centre zone character.

The commercial scale, form of buildings and character of the zone is maintained.

LCZ-O3 Local centre zone amenity.

The amenity values of residential activities within, and activities in, adjoining zones are protected from the adverse effects of developments and activities in the zone.

### Policies

LCZ-P1 Commercial function and purpose.

Provide for commercial activities which serve the local convenience needs of the surrounding area, including retail within the zone.

LCZ-P2 Commercial purpose.

The role of the zone is to support the local economy and the needs of businesses by ensuring that:

- (a) The scale of commercial activities supports the local convenience needs of the surrounding residential and rural areas; and
- (b) Enhances their vitality and amenity while providing for a range of commercial and community activities and facilities.

LCZ-P3 Employment opportunities.

Commercial development within the zone increases employment opportunities within the district.

LCZ-P4 Retail.

- (I) Locate small scale retail activities within the TCZ – Town centre zone and LCZ – Local centre zone and discourage large scale activities with the exception of supermarkets from establishing within the TCZ – Town centre zone.

- (2) Locate large scale retail and commercial activities within the COMZ – Commercial zone.
- LCZ-P5 Residential upper floors.
- (1) Maintain the commercial viability of the zone while:
- (a) Providing for mixed use developments, ensuring residential activities are preferably located above ground floor; and
  - (b) Avoiding residential activity located at ground level, where it could undermine commercial activity and frontage.
- LCZ-P6 Landscaping of onsite parking areas.
- Provide a degree of amenity for onsite parking areas within the zone by ensuring a planting strip is established and maintained.
- LCZ-P7 Strategic infrastructure setback.
- (1) Ensure buildings within the zone are designed and set back from strategic infrastructure by:
- (a) Retaining the predominant building setback within the street; and
  - (b) Allowing sufficient space for the establishment of landscaping on the site.
- LCZ-P8 Height.
- Ensure the height of new buildings is complementary to, and promotes, the existing character of the zone and adjoining residential zones.
- LCZ-P9 Reverse sensitivity.
- Development within the zone is acoustically insulated to mitigate the adverse effects of noise.
- LCZ-P10 Adjoining site amenity.
- (1) Maintain amenity of adjoining GRZ – General residential zone, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2 or OSZ – Open space zone by:
- (a) Requiring buildings within the zone to be set back from boundaries adjoining GRZ – General residential, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2 and OSZ – Open space zoned land; and
  - (b) The progressive reduction in the height of buildings in the zone, the closer they are located to boundaries adjoining GRZ – General residential, MRZ1 – Medium density residential zone 1, MRZ2 – Medium density residential zone 2 and OSZ – Open space zoned land.
- LCZ-P11 Outdoor storage.
- The adverse visual effects of outdoor storage in the zone are mitigated through appropriate location, screening or landscaping.

LCZ-P12 Objectionable odour.

Within the zone ensure that the adverse effects of objectionable odour from activities do not detract from the amenity of other sites.

**Rules**

*Land use – activities*

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use effects standards and Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>LCZ-R1</b>	Commercial activity	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R2</b>	Supermarket	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R3</b>	Community facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Excluding a cemetery.		<b>(2) Activity status where compliance not achieved: DIS</b>
<b>LCZ-R4</b>	Residential activity, unless specified below  This includes occupation of a single residential unit for short term rental.	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Located above ground floor level.		<b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b>  (a) The extent to which the residential activity effects the primary purpose of the zone to provide for commercial activities.
<b>LCZ-R5</b>	Educational facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R6</b>	Child care facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R7</b>	Office	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>

<b>LCZ-R8</b>	Public amenity
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R9</b>	Health facility
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R10</b>	Visitor accommodation
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R11</b>	Public transport facility
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R12</b>	Community corrections activity
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R13</b>	Construction or alteration of a building for a sensitive land use
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards: (i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or (ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.	<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Effects on the amenity values of the site; (b) The risk of electrical hazards affecting the safety of people; (c) The risk of damage to property; and (d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.
<b>LCZ-R14</b>	Construction or demolition of, or alteration or addition to, a building or structure
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	<b>(2) Activity status where compliance not achieved: n/a</b>
<b>LCZ-R15</b>	A multi-unit development
<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b>	<b>(2) Activity status where compliance not achieved: DIS</b>

- (a) A multi-unit development that meets all of the following standards:
- (i) Land use – effects standards for the zone;
  - (ii) Land use – buildings standards for the zone, except the following rules do not apply;
    - (1) LCZ-S9 (Residential units) does not apply;
    - (2) LCZ-S10 (Outdoor living space) does not apply;
- (b) A detailed site plan depicting the proposed Record of Title boundaries for each residential unit and any common areas (including access and services) must be provided, ensuring that a freehold (fee simple) or unit title subdivision complies with Rule SUB-R85 (Subdivision of multi-unit developments);
- (c) Each residential unit must be designed and constructed to achieve the internal design sound levels specified in APP1 – Acoustic insulation, Table 25 – Internal sound levels;
- (d) A communal service court is provided comprising;
- (i) minimum area of 20m<sup>2</sup>; and
  - (ii) minimum dimension of 3m.
- (e) Outdoor living space areas are provided to meet the following minimum requirements for each residential unit:

Residential Unit	Minimum outdoor Living space area	Minimum Dimensions
Studio unit or 1 bedroom	10m <sup>2</sup>	2m
2 or more bedrooms	15m <sup>2</sup>	2m

- (f) Each residential unit must meet the following minimum unit size:

Unit or Apartment Area	Minimum Unit
Studio Unit	35m <sup>2</sup>
1 or more bedroom unit	45m <sup>2</sup>

**Council's discretion is restricted to the following matters:**

Design:

- (g) The extent to which that portion of the building or site which fronts a road or public space:

<p>(i) Provides for passive surveillance of the street from habitable rooms at ground and upper floor levels.</p> <p>(ii) Avoids the use of impermeable screens or fencing that obstruct visual connections.</p> <p>(iii) Avoids unrelieved and blank façades.</p> <p>(iv) Creates visual interest through the use of cladding materials, colour and articulation of the façade.</p> <p>(v) Utilises soft or hard landscape elements to contribute positively to streetscape amenity.</p> <p>(vi) Minimises vehicle garaging/parking or manoeuvring areas.</p> <p>(vii) Service courts are screened or obscured.</p> <p><u>On-site amenity:</u></p> <p>(h) The extent to which the design:</p> <p>(i) Maximises opportunities for accessibility, privacy between units, access to daylight and shelter, including outdoor living spaces.</p> <p>(ii) Incorporates measures that may be required to mitigate the potential for reverse sensitivity effects.</p> <p>(iii) Maximises opportunities for passive solar gain within units.</p> <p><u>Infrastructure:</u></p> <p>(i) The extent to which the design can be efficiently serviced with 3 waters infrastructure.</p> <p><u>Natural hazards:</u></p> <p>(j) The extent to which the design avoids or mitigates effects arising from the presence of natural hazards.</p> <p><u>Staging:</u></p> <p>(k) The extent to which staging is necessary to ensure that development is carried out in a coordinated and timely manner.</p>	
<b>LCZ-RI6</b>	Any activity that is not specifically listed as a permitted, controlled, restricted discretionary or non-complying activity
<b>Activity status: DIS</b>	
<b>LCZ-RI7</b>	Any building, structure, objects or vegetation that obscure the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (APP8 – Raglan navigation beacon).
<b>Activity status: PR</b>	

*Land use – effects*



<b>LCZ-S1</b>	Servicing and hours of operation	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The loading and unloading of vehicles and the receiving of customers and deliveries associated with a commercial activity on a site adjoining the GRZ - General residential zone, MRZ1 – Medium density residential zone 1, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large lot residential zone or SETZ – Settlement zone must only occur between 6.00am and 8.00pm.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values on adjoining sites within the GRZ - General residential zone, MRZ1 – Medium density residential zone 1, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large lot residential zone or SETZ – Settlement zone;</p> <p>(b) Timing, duration and frequency of adverse effects;</p> <p>(c) Location of activity in relation to zone boundary;</p> <p>(d) Location of activity in relation to residential units on adjoining sites;</p> <p>(e) The means to avoid, remedy or mitigate adverse effects on adjoining sites.</p>	
<b>LCZ-S2</b>	Onsite parking areas – landscaping	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Onsite car parking area for 5 or more parking spaces located adjoining a road, must comply with the following standards:</p> <p>(i) The car parking area must be separated from the road by a 1.5m wide planting strip, with the exception of vehicle access points; and</p> <p>(ii) Plants within the planting and pedestrian strip must be maintained to a height no greater than 1m.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Design and location of the parking area and landscaping strip; and</p> <p>(b) Effects on streetscape amenity.</p>	
<b>LCZ-S3</b>	Outdoor storage	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Outdoor storage of goods or materials must comply with all of the following standards:</p> <p>(i) Be associated with the activity operating from the site;</p> <p>(ii) Not encroach on parking or loading areas;</p> <p>(iii) Standards LCZ-S4 Height and LCZ-S5 Height in relation to boundary; and</p> <p>(iv) Be fully screened from view by a close boarded fence or solid fence or wall to a height of 1.8m fencing or landscaping from any;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Visual amenity;</p> <p>(b) Effects on loading and parking areas;</p> <p>(c) Size and location of storage area; and</p> <p>(d) Measures to mitigate adverse effects.</p>	

<ul style="list-style-type: none"> <li>(1) Public road;</li> <li>(2) Public reserve; and</li> <li>(3) Adjoining site in another zone.</li> </ul>	
--	--

Land use – building

<b>LCZ-S4</b>	Building height
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The maximum height of any building or structure measured from the natural ground level immediately below that part of the structure must not exceed 12m;</li> <li>(b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 14m measured from the natural ground level immediately below the structure; and</li> <li>(c) The maximum height of hose drying towers associated with emergency service facilities measured from the natural ground level immediately below that part of the structure must not exceed 15m.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Height of the building;</li> <li>(b) Design and location of the building</li> <li>(c) Extent of shading on an adjoining site; and</li> <li>(d) Privacy on adjoining sites.</li> </ul>
<b>LCZ-S5</b>	Height in relation to boundary
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Any building or structure must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 2.5m above ground level at the site boundary where it adjoins the: <ul style="list-style-type: none"> <li>(i) GRZ – General residential zone;</li> <li>(ii) MRZ1 – Medium density residential zone 1;</li> <li>(iii) LLRZ – Large lot residential zone;</li> <li>(iv) SETZ – Settlement zone;</li> <li>(v) RLZ – Rural lifestyle zone; or</li> <li>(vi) OSZ – Open space zone; or</li> <li>(vii) MRZ2 – Medium density residential zone 2.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Height of the building;</li> <li>(b) Design and location of the building;</li> <li>(c) Level of shading on any other adjoining sites;</li> <li>(d) Privacy on other sites; and</li> <li>(e) Amenity values of the locality.</li> </ul>
<b>LCZ-S6</b>	Building setbacks – zone boundaries
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A building must be set back a minimum of at least: <ul style="list-style-type: none"> <li>(i) 3.0 m from rear and side boundaries adjoining any: <ul style="list-style-type: none"> <li>(1) GRZ – General residential zone;</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Height, design and location of the building relative to the boundary;</li> </ul>

<p>(2) MRZ1 – Medium density residential zone 1;</p> <p>(3) LLRZ – Large lot residential zone;</p> <p>(4) SETZ - Settlement zone;</p> <p>(5) RLZ – Rural lifestyle zone; or</p> <p>(6) OSZ – Open space zone; or</p> <p>(7) MRZ2 – Medium density residential zone 2.</p> <p>(ii) 1.5m from rear and side boundaries adjoining any:</p> <p>(1) GRUZ – General rural zone;</p> <p>(2) GIZ – General industrial zone; or</p> <p>(3) HIZ – Heavy industrial zone.</p> <p>(iii) 15m from SH23 for any site between Greenslade Road and Hills Road, Raglan.</p> <p>(b) LCZ-S6(1)(a) does not apply to a structure which is not a building.</p>	<p>(b) Impacts on the privacy for adjoining site(s);</p> <p>(c) Impacts on amenity values, including main living areas, outdoor living space of adjoining site(s); and</p> <p>(d) Landscaping and/or screening.</p>
<p><b>LCZ-S7</b>   Building setback – waterbodies</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building that is set back a minimum of:</p> <p>(i) 27.5m from the margin of any lake;</p> <p>(ii) 27.5m from the margin of any wetland;</p> <p>(iii) 27.5 from the bank of any river (other than the Waikato River and Waipa River);</p> <p>(iv) 32.5m from the margin of either the Waikato River and the Waipa River;</p> <p>(v) 27.5m from mean high water springs;</p> <p>(vi) 10m from any artificial wetland;</p> <p>(b) A public amenity of up to 25m<sup>2</sup> or pump shed (private or public) within any building setback identified in Standard LCZ-S7(1)(a);</p> <p>(c) LCZ-S7(1)(a) does not apply to a structure which is not a building.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body;</p> <p>(b) Adequacy of erosion and sediment control measures;</p> <p>(c) The functional or operational need for the building to be located close to the waterbody;</p> <p>(d) Effects on public access to the waterbody;</p> <p>(e) Effects on the amenity of the locality; and</p> <p>(f) Effects on natural character values.</p>
<p><b>LCZ-S8</b>   Horotiu acoustic area</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Construction, addition to or alteration of a building for a noise-sensitive activity within the Horotiu Acoustic Area must be designed and constructed to achieve the internal design sound level specified in APPI – Acoustic insulation, Table 22 – Internal design sound levels.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) On-site amenity values;</p> <p>(b) Noise levels received at the notional boundary of the residential unit;</p> <p>(c) Timing and duration of noise received at the notional boundary of the residential unit;</p>

		(d) Potential for reverse sensitivity effects.
<b>LCZ-S9</b>	Residential units	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) One residential unit on the Record of Title must comply with all of the following standards:</p> <p>(i) The residential unit must not be located at ground level;</p> <p>(ii) The residential unit is designed and constructed to achieve the internal design sound levels specified in APPI – Acoustic insulation, Table 25 – Internal sound levels.</p> <p>(b) Standard LCZ-S9(1)(a) does not apply to multi-unit development (refer to Rule LCZ-R15 (Multi-unit development)).</p>		<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<b>LCZ-S10</b>	Outdoor living space	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) An outdoor living space must be provided for each residential unit that meets all of the following standards:</p> <p>(i) It is for the exclusive use of the occupants of the residential unit;</p> <p>(ii) It is readily accessible from a living area of the residential unit; and</p> <p>(iii) It is located on a balcony containing at least 15m<sup>2</sup> and a circle with a diameter of at least 2.4m.</p>		<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Design and location of the building;</p> <p>(b) Provision of outdoor living including access to daylight and open space and the useability and accessibility of the outdoor living space proposed;</p> <p>(c) Privacy on adjoining sites;</p> <p>(d) The proximity of the site to communal or public open space that has the potential to mitigate any lack of private outdoor living space.</p>

## COMZ – Commercial zone

*The relevant district-wide chapter provisions apply in addition to this chapter.*

### **Purpose**

The COMZ - Commercial zone identifies areas used predominantly for a range of commercial and community activities.

### **Objectives**

COMZ-O1 Economic growth of industry.

Commercial activity is focussed within a differentiation of commercial zones (comprising the TCZ – Town centre zone, LCZ – Local centre zone, COMZ – Commercial zone, and the BTZ – Business Tamahere zone.

COMZ-O2 Commercial zone character.

The commercial scale, form of buildings and character of the zone is maintained.

COMZ-O3 Commercial zone amenity.

The amenity values of residential activities within, and activities in, adjoining zones are protected from the adverse effects of developments and activities in the zone.

### **Policies**

COMZ-P1 Commercial function and purpose.

Larger scale commercial activities are provided for within the zone.

COMZ-P2 Commercial purpose.

- (I) The role of the zone is to support the local economy and the needs of businesses by:
- (a) Providing for a wide range of commercial activities; and
  - (b) Providing for commercial activities at a scale that supports the commercial viability of towns and villages; and
  - (c) Ensuring that commercial activities complement and support the role of business town centres.

COMZ-P3 Role and function of the zone.

- (I) Ensure the role of the zone is complementary to the TCZ – Town centre zone by:
- (a) Enabling a wide range of commercial activities including large format retail activities within the zone; and
  - (b) Discouraging small scale retail activities, administration and commercial services within the zone.

COMZ-P4 Employment opportunities.

Commercial development within the zone increases employment opportunities within the district.

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

COMZ-P5 Retail.

- (1) Locate small scale retail activities within the TCZ – Town centre zone and LCZ – Local centre zone and discourage large scale activities with the exception of supermarkets from establishing within the TCZ – Town centre zone.
- (2) Locate large scale retail and commercial activities within the COMZ – Commercial zone.

COMZ-P6 Residential upper floors.

- (1) Maintain the commercial viability of the zone while:
  - (a) Providing for mixed use developments, ensuring residential activities are preferably located above ground floor; and
  - (b) Avoiding residential activity located at ground level, where it could undermine commercial activity and frontage.

COMZ-P7 Landscaping of onsite parking areas.

Provide a degree of amenity for onsite parking areas within the zone by ensuring a planting strip is established and maintained.

COMZ-P8 Strategic infrastructure setback.

- (1) Ensure buildings within the zone are designed and set back from strategic infrastructure by:
  - (a) Retaining the predominant building setback within the street; and
  - (b) Allowing sufficient space for the establishment of landscaping on the site.

COMZ-P9 Height.

Ensure the height of new buildings is complementary to, and promotes, the existing character of the zone and adjoining residential zones.

COMZ-P10 Reverse sensitivity.

Development within the zone is acoustically insulated to mitigate the adverse effects of noise.

COMZ-P11 Adjoining site amenity.

- (1) Maintain amenity of adjoining GRZ – General residential zone, MRZ1 – Medium density residential zone [1](#), [MRZ2 – Medium density residential zone 2](#) or OSZ – Open space zone by:
  - (a) Requiring buildings within the zone to be set back from boundaries adjoining GRZ – General residential, MRZ1 – Medium density residential zone [1](#), [MRZ2 – Medium density residential zone 2](#) and OSZ – Open space zoned land; and
  - (b) The progressive reduction in the height of buildings in the zone, the closer they are located to boundaries adjoining GRZ – General residential, MRZ1 – Medium density residential zone [1](#), [MRZ2 – Medium density residential zone 2](#) and OSZ – Open space zoned land.

## Rules

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

Land use – activities

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use effects standards and Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>COMZ-R1</b>	Commercial activity	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Any individual tenancy must have a gross floor area of greater than 350m <sup>2</sup> .		<b>(2) Activity status where compliance not achieved: DIS</b>
<b>COMZ-R2</b>	Supermarket	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>COMZ-R3</b>	Community facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Excluding a cemetery.		<b>(2) Activity status where compliance not achieved: DIS</b>
<b>COMZ-R4</b>	Residential activity, unless specified below  This includes occupation of a single residential unit for short term rental.	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Located above ground floor level.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b>  (a) The extent to which the residential activity effects the primary purpose of the zone to provide for commercial activities.
<b>COMZ-R5</b>	Educational facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>COMZ-R6</b>	Child care facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>COMZ-R7</b>	Office	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>COMZ-R8</b>	Public amenity	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>COMZ-R9</b>	Health facility	

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>COMZ-R10</b>   Visitor accommodation</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>COMZ-R11</b>   Public transport facility</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>COMZ-R12</b>   Servicing of boats at Raglan Wharf</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>COMZ-R13</b>   Community corrections activity</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>                  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<p><b>COMZ-R14</b>   Buildings, structures and sensitive land use within the National Grid Yard on sites existing as of 18 July 2018</p>	
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) Within National Grid Yard:                         <ul style="list-style-type: none"> <li>(i) Building alterations and additions to an existing building or structure that does not involve an increase in the building height or footprint; or</li> <li>(ii) Infrastructure (other than for the reticulation and storage of water for irrigation purposes) undertaken by a network utility operator as defined in the Resource Management Act 1991; or</li> <li>(iii) Non-habitable buildings or structures for farming activities in rural zones including accessory structures and yards for milking/dairy sheds (but not including any intensive farming buildings, commercial greenhouses and milking/dairy sheds); or</li> <li>(iv) Non-habitable horticultural buildings; or</li> <li>(v) Artificial crop protection and support structures (excluding commercial greenhouses and Pseudomonas syringae pv. Actinidiae (Psa) disease control structures);</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: NC</b></p>



<p>(vi) Fences less than 2.5m in height, measured from the natural ground level immediately below the structure; and</p> <p>(vii) Minor structures associated with farming activity that are not situated within 12m of the outer visible foundation of any National Grid tower or 10m of the outer visible foundation of a National Grid tower, including: fences, gates, stock exclusion structures, cattle-stops, stock underpasses, stock bridges and culvert crossings, and drinking water supply pipelines, troughs, and water storage tanks.</p> <p>(b) All buildings or structures permitted by Rule COMZ-R14(1)(a) must:</p> <p>(i) Comply with the New Zealand Electrical Code of Practice for Electrical Safe Distances 34:2001 ISSN 0114-0663 under all National Grid transmission line operating conditions; and</p> <p>(1) Locate a minimum 12m from the outer visible foundation of any National Grid support structure foundation and associated stay wire, unless it is:</p> <p>(2) A building or structure where Transpower has given written approval in accordance with clause 2.4.1 of the NZECP; or</p> <p>(3) Fences less than 2.5m in height, measured from the natural ground level immediately below the structure, and located a minimum of 5m from the nearest National Grid support structure foundation; or</p> <p>(ii) Network utilities (other than for the reticulation and storage of water for irrigation purposes) or any part of electricity infrastructure undertaken by a network utility operator as defined in the Resource Management Act 1991, that connects to the National Grid; and</p> <p>(iii) Not permanently physically impede existing vehicular access to a National Grid support structure;</p> <p>(c) Artificial crop protection structures and support structures between 8m and 12m</p>	
---	--

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<p>from a pole support structure but not a tower and any associated guy wire that:</p> <ul style="list-style-type: none"> <li>(i) Meet the requirements of the NZECP 34:2001 ISSN 0114-0663 for separation distances from the conductor;</li> <li>(ii) Are no higher than 2.5m;</li> <li>(iii) Are removable or temporary, to allow a clear working space of at least 12 metres from the pole when necessary for maintenance and emergency repair purposes;</li> <li>(iv) Allow all-weather access to the pole and a sufficient area for maintenance equipment, including a crane.</li> </ul>	
<b>COMZ-RI5</b>	Construction or alteration of a building for a sensitive land use
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards: <ul style="list-style-type: none"> <li>(i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or</li> <li>(ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on the amenity values of the site;</li> <li>(b) The risk of electrical hazards affecting the safety of people;</li> <li>(c) The risk of damage to property; and</li> <li>(d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.</li> </ul>
<b>COMZ-RI6</b>	Construction or demolition of, or alteration or addition to, a building or structure
<p><b>(1) Activity status: PER</b>  <b>Activity-specific standards:</b>  Nil.</p>	<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>COMZ-RI7</b>	A multi-unit development
<p><b>(1) Activity status: RDIS</b>  <b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) A multi-unit development that meets all of the following standards: <ul style="list-style-type: none"> <li>(i) Land use – effects standards for the zone;</li> <li>(ii) Land use – building standards for the zone, except the following rules do not apply;</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

<p>(1) COMZ-S9 (Residential units) does not apply;</p> <p>(2) COMZ-S10 (Outdoor living space) does not apply;</p> <p>(b) A detailed site plan depicting the proposed Record of Title boundaries for each residential unit and any common areas (including access and services) must be provided, ensuring that a freehold (fee simple) or unit title subdivision complies with Rule SUB-R93 (Subdivision of multi-unit developments);</p> <p>(c) Each residential unit must be designed and constructed to achieve the internal design sound levels specified in APP1 – Acoustic insulation, Table 25 – Internal sound levels;</p> <p>(d) A communal service court is provided comprising;</p> <p style="padding-left: 20px;">(i) minimum area of 20m<sup>2</sup>; and</p> <p style="padding-left: 20px;">(ii) minimum dimension of 3m.</p> <p>(e) Outdoor living space areas are provided to meet the following minimum requirements for each residential unit:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Residential Unit</th> <th style="text-align: left;">Minimum outdoor Living space area</th> <th style="text-align: left;">Minimum Dimensions</th> </tr> </thead> <tbody> <tr> <td>Studio unit or 1 bedroom</td> <td>10m<sup>2</sup></td> <td>2m</td> </tr> <tr> <td>2 or more bedrooms</td> <td>15m<sup>2</sup></td> <td>2m</td> </tr> </tbody> </table> <p>(f) Each residential unit must meet the following minimum unit size:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Unit or Apartment Area</th> <th style="text-align: left;">Minimum Unit</th> </tr> </thead> <tbody> <tr> <td>Studio Unit</td> <td>35m<sup>2</sup></td> </tr> <tr> <td>1 or more bedroom unit</td> <td>45m<sup>2</sup></td> </tr> </tbody> </table> <p><b>Council's discretion is restricted to the following matters:</b></p> <p><u>Design:</u></p> <p>(g) The extent to which that portion of the building or site which fronts a road or public space:</p> <p style="padding-left: 20px;">(i) Provides for passive surveillance of the street from habitable rooms at ground and upper floor levels.</p> <p style="padding-left: 20px;">(ii) Avoids the use of impermeable screens or fencing that obstruct visual connections.</p> <p style="padding-left: 20px;">(iii) Avoids unrelieved and blank façades.</p> <p style="padding-left: 20px;">(iv) Creates visual interest through the use of cladding materials, colour and articulation of the façade.</p>	Residential Unit	Minimum outdoor Living space area	Minimum Dimensions	Studio unit or 1 bedroom	10m <sup>2</sup>	2m	2 or more bedrooms	15m <sup>2</sup>	2m	Unit or Apartment Area	Minimum Unit	Studio Unit	35m <sup>2</sup>	1 or more bedroom unit	45m <sup>2</sup>	
Residential Unit	Minimum outdoor Living space area	Minimum Dimensions														
Studio unit or 1 bedroom	10m <sup>2</sup>	2m														
2 or more bedrooms	15m <sup>2</sup>	2m														
Unit or Apartment Area	Minimum Unit															
Studio Unit	35m <sup>2</sup>															
1 or more bedroom unit	45m <sup>2</sup>															

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<p>(v) Utilises soft or hard landscape elements to contribute positively to streetscape amenity.</p> <p>(vi) Minimises vehicle garaging/parking or manoeuvring areas.</p> <p>(vii) Service courts are screened or obscured.</p> <p><u>On-site amenity:</u></p> <p>(h) The extent to which the design:</p> <p>(i) Maximises opportunities for accessibility, privacy between units, access to daylight and shelter, including outdoor living spaces.</p> <p>(ii) Incorporates measures that may be required to mitigate the potential for reverse sensitivity effects.</p> <p>(iii) Maximises opportunities for passive solar gain within units.</p> <p>Infrastructure:</p> <p>(i) The extent to which the design can be efficiently serviced with 3 waters infrastructure.</p> <p>Natural hazards:</p> <p>(j) The extent to which the design avoids or mitigates effects arising from the presence of natural hazards.</p> <p>Staging:</p> <p>(k) The extent to which staging is necessary to ensure that development is carried out in a coordinated and timely manner.</p>	
<b>COMZ-R18</b>	Commercial activities within in the Motorway service centre specific control
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity of the locality;</p> <p>(b) Landscaping;</p> <p>(c) Design and layout;</p> <p>(d) Effects on efficiency and safety of the land transport network, including the Waikato Expressway;</p> <p>(e) Access design; and</p> <p>(f) Potential reverse sensitivity effects.</p>	<p><b>(2) Activity status: NC</b></p> <p><b>Where:</b></p> <p>(a) Any other activity within the Motorway service centre specific control area.</p> <p>Advice note: The other land-use activities listed within the COMZ – Commercial zone do not apply to the Motorway service centre specific control area, however the land-use effects and land-use standards do apply.</p>
<b>COMZ-R19</b>	Any activity that is not specifically listed as a permitted, controlled, restricted discretionary or non-complying activity
<b>(1) Activity status: DIS</b>	

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<b>COMZ-R20</b>	Any new building for a sensitive land use, or addition to an existing building that involves an increase in the building envelope or height for a sensitive land use, within the National Grid Yard
<b>(1) Activity status: NC</b>	
<b>COMZ-R21</b>	Any change of use of an existing building to a sensitive land use within the National Grid Yard
<b>(1) Activity status: NC</b>	
<b>COMZ-R22</b>	The establishment of any new sensitive land use within the National Grid Yard
<b>(1) Activity status: NC</b>	
<b>COMZ-R23</b>	Dairy/milking sheds (excluding accessory structures and buildings), commercial greenhouses, Pseudomonas syringae pv. Actinidiae (Psa) disease control structures, or buildings for intensive farming within the National Grid Yard
<b>(1) Activity status: NC</b>	
<b>COMZ-R24</b>	Any building, structure, objects or vegetation that obscure the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (APP8 – Raglan navigation beacon).
<b>(1) Activity status: PR</b>	

Land use – effects

<b>COMZ-S1</b>	Servicing and hours of operation	
<b>(1) Activity status: PER</b>	<p><b>Where:</b></p> <p>(a) The loading and unloading of vehicles and the receiving of customers and deliveries associated with a commercial activity on a site adjoining the GRZ - General residential zone, MRZ1 – Medium density residential zone 1, <u>MRZ2 – Medium density residential zone 2</u>, LLRZ – Large lot residential zone or SETZ – Settlement zone must only occur between 6.00am and 8.00pm.</p>	<b>(2) Activity status where compliance not achieved: RDIS</b>
		<p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on amenity values on adjoining sites within the GRZ - General residential zone, MRZ1 – Medium density residential zone 1, <u>Medium density residential zone 2</u>, LLRZ – Large lot residential zone or SETZ – Settlement zone;</p> <p>(b) Timing, duration and frequency of adverse effects;</p> <p>(c) Location of activity in relation to zone boundary;</p> <p>(d) Location of activity in relation to residential units on adjoining sites;</p> <p>(e) The means to avoid, remedy or mitigate adverse effects on adjoining sites.</p>
<b>COMZ-S2</b>	Onsite parking areas – landscaping	
<b>(1) Activity status: PER</b>	<p><b>Where:</b></p> <p>(a) Onsite car parking area for 5 or more parking spaces located adjoining a road, must comply with the following standards:</p> <p>(i) The car parking area must be separated from the road by a 1.5m</p>	<b>(2) Activity status where compliance not achieved: RDIS</b>
		<p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Design and location of the parking area and landscaping strip; and</p> <p>(b) Effects on streetscape amenity.</p>

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<p>wide planting strip, with the exception of vehicle access points; and</p> <p>(ii) Plants within the planting and pedestrian strip must be maintained to a height no greater than 1m.</p>	
<p><b>COMZ-S3</b>   Outdoor storage</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Outdoor storage of goods or materials must comply with all of the following standards:</p> <p>(i) Be associated with the activity operating from the site;</p> <p>(ii) Not encroach on parking or loading areas;</p> <p>(iii) Standards COMZ-S4 Height and COMZ-S7 Height in relation to boundary; and</p> <p>(iv) Be fully screened from view by a close boarded fence or solid fence or wall to a height of 1.8m fencing or landscaping from any:</p> <p>(1) Public road;</p> <p>(2) Public reserve; and</p> <p>(3) Adjoining site in another zone.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Visual amenity;</p> <p>(b) Effects on loading and parking areas;</p> <p>(c) Size and location of storage area; and</p> <p>(d) Measures to mitigate adverse effects.</p>

Land use – building

<p><b>COMZ-S4</b>   Building height</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) The maximum height of any building or structure measured from the natural ground level immediately below that part of the structure must not exceed 12m;</p> <p>(b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 14m measured from the natural ground level immediately below the structure;</p> <p>(c) The maximum height of hose drying towers associated with emergency service facilities measured from the natural ground level immediately below that part of the structure must not exceed 15m.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Height of the building;</p> <p>(b) Design and location of the building</p> <p>(c) Extent of shading on an adjoining site; and</p> <p>(d) Privacy on adjoining sites.</p>
<p><b>COMZ-S5</b>   Height in relation to boundary</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p>

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<p>(a) Any building or structure must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 2.5m above ground level at the site boundary where it adjoins the:</p> <p>(i) GRZ – General residential zone;</p> <p>(ii) MRZ<sub>1</sub> – Medium density residential zone <u>1</u>;</p> <p>(iii) LLRZ – Large lot residential zone;</p> <p>(iv) SETZ – Settlement zone;</p> <p>(v) RLZ – Rural lifestyle zone; <del>or</del></p> <p>(vi) OSZ – Open space zone; <u>or</u></p> <p>(vii) <u>MRZ2 – Medium density residential zone 2.</u></p>	<p>(a) Height of the building;</p> <p>(b) Design and location of the building;</p> <p>(c) Level of shading on any other adjoining sites;</p> <p>(d) Privacy on other sites; and</p> <p>(e) Amenity values of the locality.</p>
<p><b>COMZ-S6</b> Building setbacks – zone boundaries</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building must be set back a minimum of at least:</p> <p>(i) 3.0 m from rear and side boundaries adjoining any:</p> <p>(1) GRZ – General residential zone;</p> <p>(2) MRZ<sub>1</sub> – Medium density residential zone <u>1</u>;</p> <p>(3) LLRZ – Large lot residential zone;</p> <p>(4) SETZ - Settlement zone;</p> <p>(5) RLZ – Rural lifestyle zone; <del>or</del></p> <p>(6) OSZ – Open space zone; <u>or</u></p> <p>(7) <u>MRZ2 – Medium density residential zone 2.</u></p> <p>(ii) 1.5m from rear and side boundaries adjoining any:</p> <p>(1) GRUZ – General rural zone;</p> <p>(2) GIZ – General industrial zone; or</p> <p>(3) HIZ – Heavy industrial zone.</p> <p>(iii) 15m from SH23 for any site between Greenslade Road and Hills Road, Raglan.</p> <p>(b) COMZ-S6(1)(a) does not apply to a structure which is not a building.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Height, design and location of the building relative to the boundary;</p> <p>(b) Impacts on the privacy for adjoining site(s);</p> <p>(c) Impacts on amenity values, including main living areas, outdoor living space of adjoining site(s); and</p> <p>(d) Landscaping and/or screening.</p>
<p><b>COMZ-S7</b> Building setback – waterbodies</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building that is set back a minimum of:</p> <p>(i) 27.5m from the margin of any lake;</p> <p>(ii) 27.5m from the margin of any wetland;</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body;</p>

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<ul style="list-style-type: none"> <li>(iii) 27.5 from the bank of any river (other than the Waikato River and Waipa River);</li> <li>(iv) 32.5m from the margin of either the Waikato River and the Waipa River;</li> <li>(v) 27.5m from mean high water springs;</li> <li>(vi) 10m from any artificial wetland;</li> <li>(b) A public amenity of up to 25m<sup>2</sup> or pump shed (private or public) within any building setback identified in Standard COMZ-S7(1)(a);</li> <li>(c) COMZ-S7(1)(a) does not apply to a structure which is not a building.</li> </ul>	<ul style="list-style-type: none"> <li>(b) Adequacy of erosion and sediment control measures;</li> <li>(c) The functional or operational need for the building to be located close to the waterbody;</li> <li>(d) Effects on public access to the waterbody;</li> <li>(e) Effects on the amenity of the locality; and</li> <li>(f) Effects on natural character values.</li> </ul>
<p><b>COMZ-S8</b>   Horotiu acoustic area</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Construction, addition to or alteration of a building for a noise-sensitive activity within the Horotiu Acoustic Area must be designed and constructed to achieve the internal design sound level specified in APPI – Acoustic insulation, Table 22 – Internal design sound levels</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) On-site amenity values;</li> <li>(b) Noise levels received at the notional boundary of the residential unit;</li> <li>(c) Timing and duration of noise received at the notional boundary of the residential unit;</li> <li>(d) Potential for reverse sensitivity effects.</li> </ul>
<p><b>COMZ-S9</b>   Residential units</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) One residential unit on the Record of Title must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) The residential unit must not be located at ground level;</li> <li>(ii) The residential unit is designed and constructed to achieve the internal design sound levels specified in APPI – Acoustic insulation, Table 22 – Internal design sound levels.</li> </ul> </li> <li>(b) Standard COMZ-S9(1)(a) does not apply to multi-unit development (refer to Rule COMZ-R17 (Multi-unit development)).</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>COMZ-S10</b>   Outdoor living space</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) An outdoor living space must be provided for each residential unit that meets all of the following standards: <ul style="list-style-type: none"> <li>(i) It is for the exclusive use of the occupants of the residential unit;</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Design and location of the building;</li> <li>(b) Provision of outdoor living including access to daylight and open space and</li> </ul>



Part 3: Area-specific matters / Zones / Commercial and mixed use zones / COMZ – Commercial zone

<p>(ii) It is readily accessible from a living area of the residential unit; and</p> <p>(iii) It is located on a balcony containing at least 15m<sup>2</sup> and a circle with a diameter of at least 2.4m.</p>	<p>the useability and accessibility of the outdoor living space proposed;</p> <p>(c) Privacy on adjoining sites;</p> <p>(d) The proximity of the site to communal or public open space that has the potential to mitigate any lack of private outdoor living space.</p>
---	---

## TCZ – Town centre zone

*The relevant district-wide chapter provisions apply in addition to this chapter.*

### Purpose

The TCZ – Town centre zone provides for a range of commercial, community, recreational and residential activities.

### Objectives

TCZ-O1 Economic growth of industry.

Commercial activity is focussed within a differentiation of commercial zones (comprising the TCZ – Town centre zone, LCZ – Local centre zone, COMZ – Commercial zone, and the BTZ – Business Tamahere zone.

TCZ-O2 Town centre zone character.

- (1) The commercial and mixed use character of Raglan, Huntly, Ngaaruawaahia, Te Kauwhata, Pokeno and Tuakau town centres is maintained and enhanced.
- (2) The zone is promoted as a community focal point.
- (3) Development of town centres is designed in a functional and attractive manner serving the needs of the community.

TCZ-O3 Town centre zone amenity.

The amenity values of residential activities within, and activities in, adjoining zones are protected from the adverse effects of developments and activities in the zone.

### Policies

TCZ-P1 Commercial function and purpose.

- (1) Commercial activity develops in a way that ensures the town centre within each town is maintained as the primary focal point for retail, administration, commercial services and civic functions.

TCZ-P2 Commercial purpose.

- (1) The role of the zone in Raglan, Huntly, Ngaaruawaahia, Te Kauwhata, Pokeno and Tuakau is strengthened by ensuring that:
  - (a) They are recognised and maintained as the primary retail, administration, commercial service and civic centre for each town; and
  - (b) The scale of commercial activities supports their continued viability as the primary retail, administration and commercial service centre for each town; and
  - (c) Enhances their vitality and amenity while providing for a range of commercial and community activities and facilities.

- TCZ-P3 Employment opportunities.  
Commercial development within the zone increases employment opportunities within the district.
- TCZ-P4 Retail.
- (1) Locate small scale retail activities within the TCZ – Town centre zone and LCZ – Local centre zone and discourage large scale activities with the exception of supermarkets from establishing within the TCZ – Town centre zone.
  - (2) Locate large scale retail and commercial activities within the COMZ – Commercial zone.
- TCZ-P5 Residential upper floors.
- (1) Maintain the commercial viability of the zone while:
    - (a) Providing for mixed use developments, ensuring residential activities are preferably located above ground floor; and
    - (b) Avoiding residential activity located at ground level, where it could undermine commercial activity and frontage.
- TCZ-P6 Town centre zone built form.
- (1) The scale and form of new development in the zone is to:
    - (a) Provide for a safe, accessible, compact and attractive town centre environment;
    - (b) Facilitate the integration of retail shopping, administration and commercial services, residential, civic and community activities;
    - (c) Reflect the role and character of the town centre;
    - (d) Increase the prominence of buildings on street corners;
    - (e) Maintain a low rise built form and small scale, pedestrian focussed retail activities; and
    - (f) Manage adverse effects on the surrounding environment, particularly at the interface with residential areas.
- TCZ-P7 Huntly town centre.
- (1) Development maintains and enhances the role of the Huntly town centre by:
    - (a) Maintaining wide footpaths and high quality public space, prioritising and providing for pedestrian movement and safety;
    - (b) Maintaining a pedestrian focus by discouraging vehicle access across footpaths; and
    - (c) Providing for a building scale appropriate to the town centre.
- TCZ-P8 Ngaaruawaahia town centre.
- (1) Development maintains and enhances the role of the Ngaaruawaahia town centre by:
    - (a) Maintaining wide footpaths, prioritising and providing for pedestrian movement and safety;

- (b) Maintaining a pedestrian focus by discouraging vehicle access across footpaths;
- (c) Promoting improved pedestrian and cycle linkages with Te Awa River ride, Ngaaruawaahia swimming pool and the town centre; and
- (d) Providing for an appropriate building scale with narrow frontages

TCZ-P9 Te Kauwhata town centre.

(I) Development maintains and enhances the role of the Te Kauwhata town centre by:

- (a) Maintaining wide footpaths, prioritising and providing for pedestrian movement and safety;
- (b) Maintaining a pedestrian focus by discouraging vehicle access across footpaths;
- (c) Providing for an appropriate building scale with narrow frontages; and
- (d) Protecting and enhancing the character of existing buildings through new built form.

TCZ-P10 Pokeno town centre.

(I) Development maintains and enhances the role of the Pokeno town centre by:

- (a) Maintaining wide footpaths, prioritising and providing for pedestrian movement and safety;
- (b) Maintaining a pedestrian focus by discouraging vehicle access across footpaths;
- (c) Providing for an appropriate building scale with narrow frontages; and
- (d) Protecting and enhancing the character of existing buildings through new built form.

TCZ-P11 Tuakau town centre.

(I) Development maintains and enhances the role of the Tuakau town centre by:

- (a) Maintaining wide open streets, with wide pedestrian footpaths;
- (b) Maintaining a pedestrian focus by discouraging vehicle access across footpaths; and
- (c) Providing for an appropriate building scale with narrow frontages.

TCZ-P12 Pedestrian frontages: active street frontages.

(I) Provide for active street frontages in the design or redesign of buildings, and avoid car parking and accessways on sites within the pedestrian frontage area of the zone to enable the maintenance of:

- (a) Passive surveillance;
- (b) Continuous verandahs;
- (c) Display windows and building façades;
- (d) Pedestrian safety; and
- (e) Buildings located up to the street boundary.

TCZ-PI3 Corner buildings.

- (I) Ensure buildings within zone positively reinforce corner locations through:
- (a) Building design;
  - (b) The position of the building on the site;
  - (c) Architectural details; and
  - (d) Having prominent building entrances.

TCZ-PI4 Landscaping.

- (I) Within the zone and outside of the pedestrian frontage areas, ensure that landscaping contributes to the adjacent streetscape.

TCZ-PI5 Height.

- (I) Ensure the height of new buildings is complementary to, and promotes, the existing character of the business town centre within each town.

TCZ-PI6 New buildings

- (I) New buildings within the zone:
- (a) Respond to the specific site characteristics and wider street and town context;
  - (b) Promote architectural form, building features and placement;
  - (c) The design of buildings contributes to vibrancy, character and commercial viability of the town centre;
  - (d) Provide landscape and open space design that responds to the characteristics and qualities of the area;
  - (e) Minimise visual and amenity impacts of accessways and parking facilities; and
  - (f) Maximise pedestrian access and safety.

TCZ-PI7 Reverse sensitivity.

Development within the zone is acoustically insulated to mitigate the adverse effects of noise.

TCZ-PI8 Adjoining site amenity.

- (I) Maintain amenity of adjoining GRZ – General residential zone, MRZ1 – Medium density residential zone [1](#), [MRZ2 – Medium density residential zone 2](#) or OSZ – Open space zone by:
- (a) Requiring buildings within the zone to be set back from boundaries adjoining GRZ – General residential, MRZ1 – Medium density residential zone [1](#), [MRZ2 – Medium density residential zone 2](#) and OSZ – Open space zoned land; and
  - (b) The progressive reduction in the height of buildings in the zone, the closer they are located to boundaries adjoining GRZ – General residential, MRZ1 – Medium density residential zone [1](#), [MRZ2 – Medium density residential zone 2](#) and OSZ – Open space zoned land.

TCZ-P19 Outdoor storage.

The adverse visual effects of outdoor storage in the zone are mitigated through appropriate location, screening or landscaping.

TCZ-P20 Objectionable odour.

Within the zone ensure that the adverse effects of objectionable odour from activities do not detract from the amenity of other sites.

## Rules

### Land use – activities

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use effects standards and Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>TCZ-R1</b>	Commercial activity	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TCZ-R2</b>	Residential activity, unless specified below  This includes occupation of a single residential unit for short term rental.	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Located above ground floor level; and (b) The entrance lobby, stairwell or lift may be located on the ground floor level		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Streetscape effects; (b) The extent to which the residential activity effects the primary purpose of the zone to provide for retail, administration, civic and commercial activities.
<b>TCZ-R3</b>	Supermarket	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TCZ-R4</b>	Visitor accommodation	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TCZ-R5</b>	Community facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Excluding a cemetery.		<b>(2) Activity status where compliance not achieved: DIS</b>
<b>TCZ-R6</b>	Health facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b>		<b>(2) Activity status where compliance not achieved: DIS</b>

(a) Excluding a hospital.		
<b>TCZ-R7</b>	Office	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) Located above ground floor level within the Verandah Line notation on the planning maps.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Streetscape effects including ways in which to activate visual connection and interest between pedestrians and the office; and (b) Extent of glazing and length of frontage of the office to the street.
<b>TCZ-R8</b>	Public transport facility	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TCZ-R9</b>	Community corrections activity	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TCZ-R10</b>	Construction or alteration of a building for a sensitive land use	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> (a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards: (i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or (ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.		<b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b> (a) Effects on the amenity values of the site; (b) The risk of electrical hazards affecting the safety of people; (c) The risk of damage to property; and (d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.
<b>TCZ-R11</b>	Demolition of, or alteration or addition to, a building or structure	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>TCZ-R12</b>	A multi-unit development	
<b>(1) Activity status: RDIS</b> <b>Activity-specific standards:</b>		<b>(2) Activity status where compliance not achieved: DIS</b>

<p>(a) A multi-unit development that meets all of the following standards:</p> <ul style="list-style-type: none"> <li>(i) Land use – effects;</li> <li>(ii) Land use – building, except the following standards do not apply;             <ul style="list-style-type: none"> <li>(1) Standard TCZ-S6 (Display windows) does not apply;</li> <li>(2) Standard TCZ-S7 (Verandahs) does not apply</li> <li>(3) TCZ-S10 (Residential units) does not apply;</li> <li>(4) TCZ-S11 (Outdoor living space) does not apply;</li> </ul> </li> </ul> <p>(b) A detailed site plan depicting the proposed Record of Title boundaries for each residential unit and any common areas (including access and services) must be provided, ensuring that a freehold (fee simple) or unit title subdivision complies with Rule SUB-R100 (Subdivision of multi- unit developments);</p> <p>(c) Each residential unit must be designed and constructed to achieve the internal design sound levels specified in APP1 – Acoustic insulation, Table 25 – Internal sound levels;</p> <p>(d) A communal service court is provided comprising;</p> <ul style="list-style-type: none"> <li>(i) minimum area of 20m<sup>2</sup>; and</li> <li>(ii) minimum dimension of 3m.</li> </ul> <p>(e) Outdoor living space areas are provided to meet the following minimum requirements for each residential unit:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Residential Unit</th> <th style="text-align: left;">Minimum outdoor Living space area</th> <th style="text-align: left;">Minimum Dimensions</th> </tr> </thead> <tbody> <tr> <td>Studio unit or 1 bedroom</td> <td>10m<sup>2</sup></td> <td>2m</td> </tr> <tr> <td>2 or more bedrooms</td> <td>15m<sup>2</sup></td> <td>2m</td> </tr> </tbody> </table> <p>(f) Each residential unit must meet the following minimum unit size:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Unit or Apartment Area</th> <th style="text-align: left;">Minimum Unit</th> </tr> </thead> <tbody> <tr> <td>Studio Unit</td> <td>35m<sup>2</sup></td> </tr> <tr> <td>1 or more bedroom unit</td> <td>45m<sup>2</sup></td> </tr> </tbody> </table> <p><b>Council's discretion is restricted to the following matters:</b></p> <p><u>Design:</u></p> <p>(g) The extent to which that portion of the building or site which fronts a road or public space:</p>	Residential Unit	Minimum outdoor Living space area	Minimum Dimensions	Studio unit or 1 bedroom	10m <sup>2</sup>	2m	2 or more bedrooms	15m <sup>2</sup>	2m	Unit or Apartment Area	Minimum Unit	Studio Unit	35m <sup>2</sup>	1 or more bedroom unit	45m <sup>2</sup>	
Residential Unit	Minimum outdoor Living space area	Minimum Dimensions														
Studio unit or 1 bedroom	10m <sup>2</sup>	2m														
2 or more bedrooms	15m <sup>2</sup>	2m														
Unit or Apartment Area	Minimum Unit															
Studio Unit	35m <sup>2</sup>															
1 or more bedroom unit	45m <sup>2</sup>															



<ul style="list-style-type: none"> <li>(i) Provides for passive surveillance of the street from habitable rooms at ground and upper floor levels.</li> <li>(ii) Avoids the use of impermeable screens or fencing that obstruct visual connections.</li> <li>(iii) Avoids unrelieved and blank façades.</li> <li>(iv) Creates visual interest through the use of cladding materials, colour and articulation of the façade.</li> <li>(v) Utilises soft or hard landscape elements to contribute positively to streetscape amenity.</li> <li>(vi) Minimises vehicle garaging/parking or manoeuvring areas.</li> <li>(vii) Service courts are screened or obscured.</li> </ul> <p><u>On-site amenity:</u></p> <ul style="list-style-type: none"> <li>(h) The extent to which the design:             <ul style="list-style-type: none"> <li>(i) Maximises opportunities for accessibility, privacy between units, access to daylight and shelter, including outdoor living spaces.</li> <li>(ii) Incorporates measures that may be required to mitigate the potential for reverse sensitivity effects.</li> <li>(iii) Maximises opportunities for passive solar gain within units.</li> </ul> </li> </ul> <p>Infrastructure:</p> <ul style="list-style-type: none"> <li>(i) The extent to which the design can be efficiently serviced with 3 waters infrastructure.</li> </ul> <p>Natural hazards:</p> <ul style="list-style-type: none"> <li>(j) The extent to which the design avoids or mitigates effects arising from the presence of natural hazards.</li> </ul> <p>Staging:</p> <ul style="list-style-type: none"> <li>(k) The extent to which staging is necessary to ensure that development is carried out in a coordinated and timely manner.</li> </ul>	
<p><b>TCZ-RI3</b></p>	<p>Construction of any new building</p>
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <ul style="list-style-type: none"> <li>(a) The construction of any new building that meets all of the following conditions standards:             <ul style="list-style-type: none"> <li>(i) Land use – effects;</li> <li>(ii) Land use – building except;                 <ul style="list-style-type: none"> <li>(1) TCZ-S10 (Residential units) does not apply;</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>

(2) TCZ-S11 (Outdoor living space) does not apply.		
<p><b>Council's discretion is restricted to the following matters:</b></p> <p>(b) The extent to which the building is consistent with the following matters:</p> <p>(i) A site and contextual analysis;</p> <p>(ii) A connectivity and movement network analysis;</p> <p>(iii) A neighbourhood character assessment; and</p> <p>(iv) Design illustrating how the building will promote character elements</p>		
<b>TCZ-R14</b>	Educational facility	
<p><b>(1) Activity status: RDIS</b></p> <p><b>Activity-specific standards:</b></p> <p>Nil.</p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The extent to which it is necessary to locate the activity with the TCZ – Town Centre Zone;</p> <p>(b) Reverse sensitivity effects of adjacent activities;</p> <p>(c) The extent to which the activity may adversely impact on the transport network;</p> <p>(d) The extent to which the activity may adversely impact on the streetscape; and</p> <p>(e) The effects of noise.</p>		<p><b>(2) Activity status where compliance not achieved: n/a</b></p>
<b>TCZ-R15</b>	Emergency service facilities	
<b>Activity status: DIS</b>		
<b>TCZ-R16</b>	Any activity that is not specifically listed as a permitted, controlled, restricted discretionary or non-complying activity	
<b>Activity status: DIS</b>		
<b>TCZ-R17</b>	Construction of a building located on an indicative road	
<b>Activity status: NC</b>		
<b>TCZ-R18</b>	Any building, structure, objects or vegetation that obscure the sight line of the Raglan navigation beacons for vessels entering Whaingaroa (Raglan Harbour) (APP8 – Raglan navigation beacon).	
<b>Activity status: PR</b>		

*Land use – effects*

<b>TCZ-S1</b>	Servicing and hours of operation	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>		<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>

<p>(a) The loading and unloading of vehicles and the receiving of customers and deliveries associated with a commercial activity on a site adjoining the GRZ - General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone or SETZ – Settlement zone must only occur between 6.00am and 8.00pm.</p>	<p><b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values on adjoining sites within the GRZ - General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone or SETZ – Settlement zone;</li> <li>(b) Timing, duration and frequency of adverse effects;</li> <li>(c) Location of activity in relation to zone boundary;</li> <li>(d) Location of activity in relation to residential units on adjoining sites;</li> <li>(e) The means to avoid, remedy or mitigate adverse effects on adjoining sites.</li> </ul>
<p><b>TCZ-S2</b></p>	<p>Outdoor storage</p>
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) Outdoor storage of goods or materials must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) Be associated with the activity operating from the site;</li> <li>(ii) Not encroach on parking or loading areas;</li> <li>(iii) Standards TCZ-S3 Height and TCZ-S4 Height in relation to boundary; and</li> <li>(iv) Be fully screened from view by a close boarded fence or solid fence or wall to a height of 1.8m fencing or landscaping from any: <ul style="list-style-type: none"> <li>(1) Public road;</li> <li>(2) Public reserve; and</li> <li>(3) Adjoining site in another zone.</li> </ul> </li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Visual amenity;</li> <li>(b) Effects on loading and parking areas;</li> <li>(c) Size and location of storage area; and</li> <li>(d) Measures to mitigate adverse effects.</li> </ul>

*Land use – building*

<p><b>TCZ-S3</b></p>	<p>Building height</p>
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) The maximum height of any building or structure measured from the natural ground level immediately below that part of the structure must not exceed 12;</li> <li>(b) Chimneys not exceeding 1m in width and finials shall not exceed a maximum height of 14m measured from the natural</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Height of the building;</li> <li>(b) Design and location of the building</li> <li>(c) Extent of shading on an adjoining site; and</li> <li>(d) Privacy on adjoining sites.</li> </ul>

<p>ground level immediately below the structure;</p> <p>(c) The maximum height of hose drying towers associated with emergency service facilities measured from the natural ground level immediately below that part of the structure must not exceed 15m.</p>	
<p><b>TCZ-S4</b>   Height in relation to boundary</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Any building or structure must not protrude through a height control plane rising at an angle of 45 degrees commencing at an elevation of 2.5m above ground level at the site boundary where it adjoins the:</p> <p>(i) GRZ – General residential zone;</p> <p>(ii) MRZ1 – Medium density residential zone 1;</p> <p>(iii) LLRZ – Large lot residential zone;</p> <p>(iv) SETZ – Settlement zone;</p> <p>(v) RLZ – Rural lifestyle zone; or</p> <p>(vi) OSZ – Open space zone; or</p> <p>(vii) MRZ2 – Medium density residential zone 2.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Height of the building;</p> <p>(b) Design and location of the building;</p> <p>(c) Level of shading on any other sites adjoining site;</p> <p>(d) Privacy on other site; and</p> <p>(e) Amenity values of the locality.</p>
<p><b>TCZ-S5</b>   Gross leasable floor area</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Every individual tenancy (excluding supermarkets) must have a gross leasable floor area of no more than 350m<sup>2</sup></p>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>TCZ-S6</b>   Display windows and building façades</p>	
<p><b>(1) Activity status: PER</b>  <b>Where:</b></p> <p>(a) Any new building façade adjoining a road boundary, or alteration of an existing building façade, adjoining a road boundary must comply with the following standards:</p> <p>(i) Not be set back from the road boundary at ground floor level; and</p> <p>(ii) Provide display windows comprising at least 50% of the building façade at ground floor level.</p> <p>(b) Standard TCZ-S6(1)(a) does not apply to the entrance lobby, stairwell or lift located at ground floor level that services an above ground level multi-unit development.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b>  <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Design and location of the building having regard to the operational and functional requirements of the activity to be accommodated</p> <p>(b) Extent to which the activity achieves the intent of the control by other means, to enable passive surveillance and promote pedestrian safety</p> <p>(c) Effects on amenity values and town centre character.</p>

<b>TCZ-S7</b>	Verandahs	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) Any new building, or alteration to the frontage of an existing building, on land with a verandah line identified on the planning maps, must be provided with a verandah that complies with the following standards:</p> <p>(i) Is attached to the façade of the building;</p> <p>(ii) Has a height above the footpath of at least 2.5m but not more than 3.5m;</p> <p>(iii) Has a minimum width of 3m;</p> <p>(iv) The outer edge of the verandah is set back 0.5m from the kerb;</p> <p>(v) It is attached to any verandahs on adjoining buildings, so as to provide continuous pedestrian shelter;</p> <p>(vi) It is cantilevered from the building.</p> <p>(b) Standard TCZ-S7(1)(a) does not apply to a building included in SCHED I – Historic heritage items.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) The effects on the amenity of the streetscape, including providing continuous pedestrian shelter and town centre character;</p> <p>(b) The character and layout of the building;</p> <p>(c) The nature, design and location of the verandah; and</p> <p>(d) The functional requirements of the activities that the buildings are intended to accommodate.</p>	
<b>TCZ-S8</b>	Building setbacks – zone boundaries	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <p>(a) A building must be set back a minimum of at least:</p> <p>(i) 3m from rear and side boundaries adjoining any:</p> <p>(1) GRZ – General residential zone;</p> <p>(2) MRZ<sub>1</sub> – Medium density residential zone <sub>1</sub>;</p> <p>(3) RLZ – Rural lifestyle zone;</p> <p>(4) LLRZ – Large lot residential zone;</p> <p>(5) SETZ - Settlement zone; or</p> <p>(6) OSZ – Open space zone; or</p> <p>(7) <u>MRZ<sub>2</sub> – Medium density residential zone 2.</u></p> <p>(ii) 1.5m from rear and side boundaries adjoining any:</p> <p>(1) GRUZ – General rural zone;</p> <p>(2) GIZ – General industrial zone; or</p> <p>(3) HIZ – Heavy industrial zone.</p> <p>(b) TCZ-S8(1)(a) does not apply to a structure which is not a building.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Height, design and location of the building relative to the boundary;</p> <p>(b) Impacts on the privacy for adjoining site(s);</p> <p>(c) Impacts on amenity values, including main living areas, outdoor living space of adjoining site(s); and</p> <p>(d) Landscaping and/or screening.</p>	
<b>TCZ-S9</b>	Building setback – waterbodies	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p>	

<p>(a) A building must be set back a minimum of:</p> <ul style="list-style-type: none"> <li>(i) 27.5m from the margin of any lake;</li> <li>(ii) 27.5m from the margin of any wetland;</li> <li>(iii) 27.5 from the bank of any river (other than the Waikato River and Waipa River);</li> <li>(iv) 32.5m from the margin of either the Waikato River and the Waipa River;</li> <li>(v) 27.5m from mean high water springs;</li> <li>(vi) 10m from any artificial wetland;</li> </ul> <p>(b) A public amenity of up to 25m<sup>2</sup> or pump shed (private or public) within any building setback identified in Standard TCZ-S9(1)(a);</p> <p>(c) TCZ-S9(1)(a) does not apply to a structure which is not a building.</p>	<p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on the landscape, ecological, cultural and recreational values of the adjacent water body;</li> <li>(b) Adequacy of erosion and sediment control measures;</li> <li>(c) The functional or operational need for the building to be located close to the waterbody;</li> <li>(d) Effects on public access to the waterbody;</li> <li>(e) Effects on the amenity of the locality; and</li> <li>(f) Effects on natural character values.</li> </ul>
<p><b>TCZ-S10</b> Residential units</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) One residential unit on the Record of Title;</li> <li>(b) The residential unit must comply with all of the following standards: <ul style="list-style-type: none"> <li>(i) The residential unit must not be located at ground level;</li> <li>(ii) The entrance lobby, stairwell or lift may be located on the ground floor level;</li> <li>(iii) The residential unit must achieve the internal design sound levels specified achieve the internal design sound levels specified in APPI – Acoustic insulation, Table 25 – Internal sound levels.</li> </ul> </li> <li>(c) Standard TCZ-S10(1) does not apply to multi-unit development (refer to Rule TCZ-R12 (Multi-unit development)).</li> </ul>	<p><b>(2) Activity status where compliance not achieved: DIS</b></p>
<p><b>TCZ-S11</b> Outdoor living space</p>	
<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) An outdoor living space must be provided for each residential unit that meets all of the following standards: <ul style="list-style-type: none"> <li>(i) It is for the exclusive use of the occupants of the residential unit;</li> <li>(ii) It is readily accessible from a living area of the residential unit; and</li> </ul> </li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Design and location of the building;</li> <li>(b) Provision of outdoor living including access to daylight and open space and the useability and accessibility of the outdoor living space proposed;</li> <li>(c) Privacy on adjoining sites;</li> </ul>

Part 3: Area-specific matters / Zones / Commercial and mixed use zones / TCZ – Town centre zone

<p>(iii) It is located on a balcony containing at least 15m<sup>2</sup> and a circle with a diameter of at least 2.4m.</p>	<p>(d) The proximity of the site to communal or public open space that has the potential to mitigate any lack of private outdoor living space.</p>
--	--

## GIZ – General industrial zone

*The relevant district-wide chapter provisions apply in addition to this chapter.*

### Purpose

The GIZ – General industrial zone contains areas used predominantly for a range of industrial activities, other than Heavy Industrial Activities, but also other compatible activities.

### Objectives

GIZ-O1 Economic growth of industry.

The existing and future growth of the district's industry is supported and strengthened.

### Policies

GIZ-PI Provide industrial zones with different functions.

(1) Provide for the operation and growth of a variety of industrial activities in two industrial zones as follows:

- (a) A HIZ – Heavy industrial zone that caters for those industrial and other compatible activities that may have significant adverse effects beyond the boundary of the zone, and where adverse effects of those activities is avoided, remedied or mitigated; and
- (b) A GIZ – General industrial zone that caters for those industrial and other compatible activities, where the significant adverse effects of those activities are confined to locations within the zone, and where the adverse effects of those activities are avoided, remedied or mitigated.

GIZ-P2 Maintain sufficient industrial land.

- (1) Maintain a sufficient supply of industrially zoned land to meet reasonably foreseeable future demand for industrial land.
- (2) Utilise industrial land primarily for industrial purposes so as to preserve the functionality of industrially zoned land.
- (3) Protect industrial activities, and in particular heavy industrial activities, from reverse sensitivity effects associated with activities in non-industrial zones.

GIZ-P3 Management of environmental effects in the zone.

- (1) Avoid significant adverse effects of activities in the zone on the environment of other immediately adjacent zones.
- (2) (b) Avoid, remedy or mitigate other environmental effects of activities in the zone to the extent necessary to:
  - (a) Maintain the functionality of the zone; and
  - (b) Maintain the functionality of adjacent zones.



GIZ-P4 Support of regionally significant industry.

Support the operation and growth of the district’s regionally significant industries.

## Rules

### Land use – activities

In addition to the activity-specific standards listed below, permitted activities must also comply with all relevant Land-use effects standards and Land-use building standards in this chapter, as well as the standards in Part 2 / District-wide matters / General district-wide matters.

<b>GIZ-R1</b>	Industrial activity
(1) Activity status: <b>PER</b> Activity-specific standards: Nil.	(2) Activity status where compliance not achieved: <b>n/a</b>
<b>GIZ-R2</b>	Trade and industry training activity
(1) Activity status: <b>PER</b> Activity-specific standards: Nil.	(2) Activity status where compliance not achieved: <b>n/a</b>
<b>GIZ-R3</b>	Truck stop for refuelling
(1) Activity status: <b>PER</b> Activity-specific standards: Nil.	(2) Activity status where compliance not achieved: <b>n/a</b>
<b>GIZ-R4</b>	Office ancillary to an industrial activity
(1) Activity status: <b>PER</b> Activity-specific standards: (a) Less than 100m <sup>2</sup> gross floor area; or (b) Does not exceed 30% gross floor area of all buildings on the site.	(2) Activity status where compliance not achieved: <b>DIS</b>
<b>GIZ-R5</b>	Food outlet
(1) Activity status: <b>PER</b> Activity-specific standards: (a) Less than 200m <sup>2</sup> gross floor area.	(2) Activity status where compliance not achieved: <b>DIS</b>
<b>GIZ-R6</b>	Ancillary retail
(1) Activity status: <b>PER</b> Activity-specific standards: (a) Does not exceed 10% gross floor area of all buildings on the site.	(2) Activity status where compliance not achieved: <b>DIS</b>
<b>GIZ-R7</b>	Hire centre
(1) Activity status: <b>PER</b> Activity-specific standards: Nil.	(2) Activity status where compliance not achieved: <b>n/a</b>
<b>GIZ-R8</b>	Wholesale
(1) Activity status: <b>PER</b> Activity-specific standards: Nil.	(2) Activity status where compliance not achieved: <b>n/a</b>
<b>GIZ-R9</b>	Trade supply outlet

Part 3: Area-specific matters / Zones / Industrial zones / GIZ – General industrial zone

(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 0</b>	Transport depot
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 1</b>	Garden centre
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 2</b>	Retailing of agricultural and industrial motor vehicles and machinery
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 3</b>	Ancillary activity
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 4</b>	Construction or demolition of, or alteration or addition to, a building or structure
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 5</b>	Community corrections activity
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 6</b>	Service station
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> Nil.	(2) <b>Activity status where compliance not achieved: n/a</b>
<b>GIZ-RI 7</b>	Caretaker's or security person's residential unit
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> (a) Is located within an industrial building; (b) Does not exceed 70m <sup>2</sup> gross floor area; and (c) Accommodates no more than two people.	(2) <b>Activity status where compliance not achieved: DIS</b>
<b>GIZ-RI 8</b>	Buildings, structures and sensitive land use within the National Grid Yard in all other zones as of 18 July 2018
(1) <b>Activity status: PER</b> <b>Activity-specific standards:</b> (a) Within National Grid Yard: (i) Building alterations and additions to an existing building or structure that	(2) <b>Activity status where compliance not achieved: NC</b>

<p>does not involve an increase in the building height or footprint; or</p> <ul style="list-style-type: none"> <li>(ii) Infrastructure (other than for the reticulation and storage of water for irrigation purposes) undertaken by a network utility operator as defined in the Resource Management Act 1991; or</li> <li>(iii) Non-habitable buildings or structures for farming activities in rural zones including accessory structures and yards for milking/dairy sheds (but not including any intensive farming buildings, commercial greenhouses and milking/dairy sheds); or</li> <li>(iv) Non-habitable horticultural buildings; or</li> <li>(v) Artificial crop protection and support structures (excluding commercial greenhouses and <i>Pseudomonas syringae</i> pv. <i>Actinidiae</i> (Psa) disease control structures);</li> <li>(vi) Fences less than 2.5m in height, measured from the natural ground level immediately below the structure; and</li> <li>(vii) Minor structures associated with farming activity that are not situated within 12m of the outer visible foundation of any National Grid tower or 10m of the outer visible foundation of a National Grid tower, including: fences, gates, stock exclusion structures, cattle-stops, stock underpasses, stock bridges and culvert crossings, and drinking water supply pipelines, troughs, and water storage tanks.</li> </ul> <p>(b) All buildings or structures permitted by Rule GIZ-R18(1)(a) must:</p> <ul style="list-style-type: none"> <li>(i) Comply with the New Zealand Electrical Code of Practice for Electrical Safe Distances 34:2001 ISSN 0114-0663 under all National Grid transmission line operating conditions; and</li> <li>(ii) Locate a minimum 12m from the outer visible foundation of any National Grid support structure foundation and associated stay wire, unless it is:             <ul style="list-style-type: none"> <li>(1) A building or structure where Transpower has given written</li> </ul> </li> </ul>	
---	--

<p>approval in accordance with clause 2.4.1 of the NZECP; or</p> <p>(2) Fences less than 2.5m in height, measured from the natural ground level immediately below the structure, and located a minimum of 5m from the nearest National Grid support structure foundation; or</p> <p>(3) Network utilities (other than for the reticulation and storage of water for irrigation purposes) or any part of electricity infrastructure undertaken by a network utility operator as defined in the Resource Management Act 1991, that connects to the National Grid; and</p> <p>(iii) Not permanently physically impede existing vehicular access to a National Grid support structure;</p> <p>(c) Artificial crop protection structures and support structures between 8m and 12m from a pole support structure but not a tower and any associated guy wire that:</p> <p>(i) Meet the requirements of the NZECP 34:2001 ISSN 0114-0663 for separation distances from the conductor;</p> <p>(ii) Are no higher than 2.5m;</p> <p>(iii) Are removable or temporary, to allow a clear working space of at least 12 metres from the pole when necessary for maintenance and emergency repair purposes;</p> <p>(iv) Allow all-weather access to the pole and a sufficient area for maintenance equipment, including a crane.</p>	
<p><b>GIZ-R19</b></p>	<p>Construction or alteration of a building for a sensitive land use</p>
<p><b>(1) Activity status: PER</b></p> <p><b>Activity-specific standards:</b></p> <p>(a) The construction or alteration of a building for a sensitive land use that complies with all of the following standards:</p> <p>(i) It is set back a minimum of 10m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of up to 110kV; or</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <p>(a) Effects on the amenity values of the site;</p> <p>(b) The risk of electrical hazards affecting the safety of people;</p> <p>(c) The risk of damage to property; and</p> <p>(d) Effects on the operation, maintenance and upgrading of the electrical distribution or transmission lines.</p>

Part 3: Area-specific matters / Zones / Industrial zones / GIZ – General industrial zone

	(ii) It is set back a minimum of 12m from the centre of line of any electrical distribution or transmission lines, not associated with the National Grid, that operate at a voltage of 110kV or more.	
<b>GIZ-R20</b>	Construction or demolition of, or alteration or addition to, a building or structure	
<b>(1) Activity status: PER</b> <b>Activity-specific standards:</b> Nil.		<b>(2) Activity status where compliance not achieved: n/a</b>
<b>GIZ-R21</b>	A waste management facility	
<b>(1) Activity status: DIS</b>		
<b>GIZ-R22</b>	Hazardous waste storage, processing or disposal	
<b>Activity status: DIS</b>		
<b>GIZ-R23</b>	Quarrying activities	
<b>(1) Activity status: DIS</b>		
<b>GIZ-R24</b>	An office not provided for by Rule GIZ-R4(1)	
<b>(1) Activity status: DIS</b>		
<b>GIZ-R25</b>	A retail activity not provided for by GIZ-R6(1)	
<b>(1) Activity status: DIS</b>		
<b>GIZ-R26</b>	Any activity that is not specifically listed as a permitted, controlled, restricted discretionary or non-complying activity	
<b>(1) Activity status: DIS</b>		
<b>GIZ-R27</b>	Any new building for a sensitive land use, or addition to an existing building that involves an increase in the building envelope or height for a sensitive land use, within the National Grid Yard	
<b>(1) Activity status: NC</b>		
<b>GIZ-R28</b>	Any change of use of an existing building to a sensitive land use within the National Grid Yard	
<b>(1) Activity status: NC</b>		
<b>GIZ-R29</b>	The establishment of any new sensitive land use within the National Grid Yard	
<b>(1) Activity status: NC</b>		
<b>GIZ-R30</b>	Dairy/milking sheds (excluding accessory structures and buildings), commercial greenhouses, Pseudomonas syringae pv. Actinidiae (Psa) disease control structures, or buildings for intensive farming within the National Grid Yard	
<b>(1) Activity status: NC</b>		
<b>GIZ-R31</b>	A noise-sensitive activity, except as provided for by Rule GIZ-R17	
<b>(1) Activity status: NC</b>		
<b>GIZ-R32</b>	A sensitive land use, except as provided for by Rule GIZ-R17	
<b>(1) Activity status: NC</b>		

Land use – effects

<b>GIZ-S1</b>	Landscape planting	
<b>(1) Activity status: PER</b> <b>Where:</b>		<b>(2) Activity status where compliance not achieved: RDIS</b>

Part 3: Area-specific matters / Zones / Industrial zones / GIZ – General industrial zone

<p>(a) Any building or land use activity on a record of title that has a side and/or rear boundary adjoining any GRZ – General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone, SETZ – Settlement zone, RLZ – Rural lifestyle zone or OSZ – Open space zone that is landscaped to the following minimum standards:</p> <p>(i) A 3m depth measured from the side and/or rear boundary; and</p> <p>(ii) Comprises a mixture of shrubs and trees planted a maximum of 1.5m metres apart.</p>	<p><b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Type, density and scale of landscape plantings; and</p> <p>(b) The extent to which the amenity of the adjoining GRZ – General residential zone, MRZ1 – Medium density residential zone 1, <a href="#">MRZ2 – Medium density residential zone 2</a>, LLRZ – Large lot residential zone, SETZ – Settlement zone, RLZ – Rural lifestyle zone or OSZ – Open space zone is maintained.</p>
<p><b>GIZ-S2</b>   Landscape planting</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <p>(a) Any building or land use activity on a record of title that contains, or adjoins, a river or a permanent stream that is landscaped to the following minimum standards:</p> <p>(i) A 4m depth measured from the bank and extending across the entire length of the water body; and</p> <p>(ii) Comprises mixed indigenous vegetation planted a maximum of 1.5m apart.</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) Type, density and scale of indigenous vegetation; and</p> <p>(b) The extent to which the natural character and cultural values of a river or stream are maintained.</p>
<p><b>PREC7-SI</b>   Land use activities within PREC7 – Huntly North precinct</p>	
<p><b>(3) Activity status: PER</b> <b>Where:</b></p> <p>(a) Any land use activity where it is on a site that:</p> <p>(i) Was created by a subdivision consent decision that had regard to a stop bank breach assessment; and</p> <p>(ii) The stop bank breach assessment assessed risk to the site and future development on the site; and</p> <p>(iii) All flood hazard mitigation measures recommended in the stop bank breach assessment are in place.</p>	<p><b>(4) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p> <p>(a) The avoidance and mitigation of flooding hazards; and</p> <p>(b) Preparation of, and responses to recommendations in, a stop bank breach assessment.</p>

*Land use – building*

<p><b>GIZ-S3</b>   Building height</p>	
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <p>(a) A building measured from the natural ground level immediately below that part</p>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council’s discretion is restricted to the following matters:</b></p>

<p>of the structure that does not exceed a height of:</p> <ul style="list-style-type: none"> <li>(i) 15m; or</li> <li>(ii) 18m if located on Whangarata and Bollard Road in Tuakau; or</li> <li>(iii) 10m if located on Tregoweth Lane and within 50m of the GRZ – General residential zone in Huntly.</li> </ul> <p>(b) Chimneys not exceeding 1m in width and finials measured from the natural ground level immediately below the structure shall not exceed that do not exceed a height of</p> <ul style="list-style-type: none"> <li>(i) 17m; or</li> <li>(ii) 20m if located on Whangarata and Bollard Road in Tuakau; or</li> <li>(iii) 12m if located on Tregoweth Lane and within 50m of the GRZ – General residential zone in Huntly.</li> </ul>	<p>(a) Effects on the amenity of neighbouring properties.</p>
<p><b>GIZ-S4</b></p>	<p>Building height in an Outstanding Natural Feature or Outstanding Natural Landscape</p>
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A building measured from the natural ground level immediately below that part of the structure that does not exceed a height of 5m in an Outstanding Natural Feature or Outstanding Natural Landscape.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) The extent to which the aesthetic value of the identified feature or landscape is maintained</li> </ul>
<p><b>GIZ-S5</b></p>	<p>Height in relation to boundary</p>
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A building or structure that does not project beyond a 45 degree height control plane measured from a point 3m above natural ground level along the boundary of a site located outside of a HIZ – Heavy industrial zone or GIZ – General industrial zone.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effect on the amenity of neighbouring properties.</li> </ul>
<p><b>GIZ-S6</b></p>	<p>Building setbacks – all boundaries</p>
<p><b>(1) Activity status: PER</b> <b>Where:</b></p> <ul style="list-style-type: none"> <li>(a) A building that is set back at least: <ul style="list-style-type: none"> <li>(i) 5m from a road boundary; and</li> <li>(ii) 3m from any other boundary where the site adjoins another zone, other than the HIZ – Heavy industrial zone.</li> </ul> </li> <li>(b) GIZ-S6(1)(a) does not apply to a structure which is not a building.</li> </ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b> <b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"> <li>(a) Effects on amenity values;</li> <li>(b) Effects on streetscape; and</li> <li>(c) Traffic and road safety.</li> </ul>
<p><b>GIZ-S7</b></p>	<p>Building setback – waterbodies</p>

<p><b>(1) Activity status: PER</b></p> <p><b>Where:</b></p> <ul style="list-style-type: none"><li>(a) A building that is set back a minimum of:<ul style="list-style-type: none"><li>(i) 30m from a lake margin;</li><li>(ii) 30m from a wetland that is identified on the planning maps;</li><li>(iii) 37m from the bank of the Waikato River;</li><li>(iv) 10m from the bank of a river, other than the Waikato River;</li><li>(v) 10m from the bank of a perennial or intermittent stream;</li><li>(vi) 10m from a wetland that is not identified on the planning maps</li></ul></li><li>(b) A pump shed, or a public amenity of not exceeding an area of 25m<sup>2</sup>, that is located within the building setbacks identified in Standards GIZ-S7(1)(a);</li><li>(c) GIZ-S7(1)(a) does not apply to a structure which is not a building.</li></ul>	<p><b>(2) Activity status where compliance not achieved: RDIS</b></p> <p><b>Council's discretion is restricted to the following matters:</b></p> <ul style="list-style-type: none"><li>(a) Effects on natural character values.</li></ul>
--	---